



LEGEND

BILL OF MATERIAL

ITEM	UNIT	TOTAL
Concrete Removal	Cu. Yd.	10.8
Structural Repair of Concrete (Depth Equal to or Less Than 5")	Sq. Ft.	10

Notes

Existing reinforcement not extending into the areas of new construction shall be cut at the removal line and removed. Exposed portion will be cleaned and coated with a layer of epoxy. Cost included with Concrete Removal.

Existing reinforcement extending into the areas of new construction are to be cleaned, straightened and incorporated into the new construction. All reinforcement bars to be reused that are damaged during concrete removal shall be replaced with an approved bar splicer or anchorage system. Cost included with Concrete Removal.

CONCRETE REMOVAL DETAILS
WEST ABUTMENT EB STRUCTURE
STRUCTURE NO. 081-0018 (EB)

 Coombe-Bloxdorf P.C. -CIVIL ENGINEERS- -STRUCTURAL ENGINEERS- -LAND SURVEYORS- Design Firm License No.184-002703	PROJECT NO. 09033 SCALE DATE 6/4/2010 DESIGNED BY BD/MCB DRAWN BY CFC CHECKED BY MCR	SHEET NO. 29 55 SHEETS	F.A.I RTE. 280	SECTION 81-1 (VB) R	COUNTY ROCK ISLAND	TOTAL SHEETS 503	SHEET NO. 215
	CONTRACT NO. 64815						
	FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT			

```

PLOT DATE = 7/21/2010
FILE NAME = ...J081-0018-0019-64815-029-west-abut-ab-removal.dgn
PLOT SCALE = 345.175882 1/8" / IN.
USER NAME = CFC_

```