






LEGEND



Denotes Epoxy Crack Injection

BILL OF MATERIAL

ITEM	UNIT	TOTAL
Concrete Removal	Cu. Yd.	11.1
Epoxy Crack Injection	Foot	3.0



Notes

Existing reinforcement not extending into the areas of new construction shall be cut at the removal line and removed. Exposed portion will be cleaned and coated with a layer of epoxy. Cost included with Concrete Removal.

Existing reinforcement extending into the areas of new construction are to be cleaned, straightened and incorporated into the new construction. All reinforcement bars to be reused that are damaged during concrete removal shall be replaced with an approved bar splicer or anchorage system. Cost included with Concrete Removal.

CONCRETE REMOVAL DETAILS
WEST ABUTMENT WB STRUCTURE
STRUCTURE NO. 081-0019 (WB)

CB Coombe-Bloxdorf P.C.
-CIVIL ENGINEERS-
-STRUCTURAL ENGINEERS-
-LAND SURVEYORS-
Design Firm License No. 184-002703

PROJECT NO.	09033
SCALE	
DATE	6/4/2010
DESIGN BY	BD/MCE
DRAWN BY	CFC
CHECKED BY	MCE

SHEET NO. 31

55 SHEETS

F.A.I RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
280	81-1 (VB) R	ROCK ISLAND	503	217
		CONTRACT NO. 64815		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

```
PLOT DATE      = 7/21/2010
FILE NAME      = ...081-0018-0019-64815-031-west-about-web-removal.dgn
PLOT SCALE     = 35.175882 " / IN.
USER NAME      = CFC..
```