

<u>Notes</u>

Existing reinforcement not extending into the areas of new construction shall be cut at the removal line and removed. Exposed portion will be cleaned and coated with a layer of epoxy. Cost included with Concrete Removal. Existing reinforcement extending into the areas of new construction are to be cleaned, straightened and incorporated into the new construction. All reinforcement bars to be reused that are damaged during concrete removal shall be replaced with an approved bar splicer or anchorage system. Cost included with Concrete Removal.



Structural Repair of Concrete (Depth Equal to or Less Than 5")



Concrete Removal

BILL OF MATERIAL

UNIT	TOTAL
Cu. Yd.	11.1
Sq. Ft.	5
	Cu. Yd. Sq. Ft.

CONCRETE REMOVAL DETAILS EAST ABUTMENT WB STRUCTURE STRUCTURE NO. 081-0019 (WB)

