

11:59:08 AM P:\P-05\1719\DCN\Sheets\US 67 Final Plans\0810022-64815-021-WB..W..^but..Rem.dcn



ITEM	UNIT	QUANTITY
Concrete Removal	Cu. Yd.	9.3
Structural Repair of Concrete (Depth Equal to or Less Than 5 Inches)	Sq. Ft.	1

Existing reinforcement bars that project from the abutment after concrete removal shall be cut flush with the concrete left in place. Cost included with Concrete Removal.

Repair of the existing abutment shall include but not be limited to the areas shown. The actual areas to be repaired will be determined by the Engineer at the time of construction.

Indicates limits of Concrete Removal

Indicates limits of Structural Repair of Concrete
(Depth Equal to or Less Than 5 Inches)



**INFRASTRUCTURE
ENGINEERING | INCORPORATED**
33 West Monroe | Suite 1540 | Chicago, IL 60603
P 312.425.9560 | F 312.425.9564 | www.infrastructure-ena.com

SHEET NO. 24	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	280	81-1(HB-2)R	ROCK ISLAND	503	306
			CONTRACT NO. 64815		
54 SHEETS	FED. ROAD DIST. NO. - ILLINOIS		FED. AID PROJECT		

W.B. ROADWAY WEST ABUTMENT
CONCRETE REMOVAL & REPAIRS
STRUCTURE NO. 081-0022 (E.B.)
STRUCTURE NO. 081-0023 (W.B.)