

Station		Offset	Description	Temp. Marking Line - 4"		Pav't Marking removal (Sq.Ft.)	Relocate Temp. Conc. (Foot)	IMP ATTN Relocate NRD (Each)	Work Zone Pav't Mark removal (Sq.Ft)
				WHITE	YELLOW				
				(Foot)					
283+20.2	-	290+43.0	remove left edge line			240.94			
284+99.9	-	288+41.6	left edge line		341.73				
284+99.9	-	288+41.7	right edge line	341.74					
288+41.6	-	290+43.0	left edge line		201.40				
288+41.7	-	290+43.0	right edge line	201.39					
289+00.0	-	317+12.4	remove temp mark						937.47
290+43.0	-	296+49.9	right edge line	606.85					
301+00.0	-	315+27.5	EB - remove temp mark						475.84
301+79.9	-	307+33.4	ramp - right edge line	43.67' - 94.81' Lt	553.49				
302+49.9	-	305+75.8	# ramp gore - turkey tracks 8"	43.67' Lt	130.38				
	-	#	paid as two 4" lines						
305+85.8	-	307+36.8	ramp - left edge line	44.17' - 81.43' Lt	150.98				
343+40.1	-	346+73.5	remove temp mark	44.3' Lt					111.12
346+73.5	-	356+75.0	remove temp mark taper	44.3' - 32' Lt					333.84
343+40.1	-	346+73.5	right edge line	43.7' Lt	333.38				
346+76.5	-	356+75.0	taper - right edge line	43.7' - 56' Lt	998.52				

RELOCATE BARRIER WALL

232+00.1	-	234+64.5	From 46.6' - 45.37' Lt	43.16' - 41.93' Lt			262.5		
234+64.5	-	236+53.2	From taper 45.37' - 32.26' Lt	41.93' - 56.16' Lt			187.5		
		236+53.2	From 32.26' Lt	56.16' Lt				1	
240+52.5	-	242+65.0	From 46.5' Lt	42.90' Lt			212.5		
242+65.0	-	244+52.1	From taper 46.5' - 32.41' Lt	42.90' - 56.45' Lt			187.5		
		244+52.1	From 32.41' Lt	56.45' Lt				1	
253+80.0	-	256+05.0	From 46.5' Lt	43.05' Lt			225.0		
256+05.0	-	257+92.1	From taper 46.5' - 32.68' Lt	43.05' - 56.60' Lt			187.5		
		257+92.1	From 32.68' Lt	56.60' Lt				1	
262+87.5	-	266+25.0	From 46.5' Lt	43.06' Lt			337.5		
266+25.0	-	268+26.5	From taper 46.5' - 32.04' Lt	43.06' - 56.14' Lt			187.5		
		268+25.9	From 32.04' Lt	56.14' Lt				1	
285+00.0	-	288+41.7	From 46.51' Lt	43.33' - 43.06' Lt			337.5		
288+41.7	-	290+43.0	From taper 46.5' - 30.68' Lt	43.06' - 55.31' Lt			187.5		
		290+43.0	From 30.68' Lt	55.31' Lt				1	

TOTALS

6,868.75	3,616.46	1,081.97	2,312.50	5.00	5,000.12
----------	----------	----------	----------	------	----------