

Station	Location	Offset	70400200	70300220	70300240	70300100	70301000	40603345	40600982	40600200	63200310		
			Relocate Temp. Conc. Barrier (Foot)	Temp. Pav't Marking Line - 4"	Temp. Pav't Marking Line - 6"	Short Term Pav't Marking	Work Zone Pav't MARK Removal (Sq.Ft)	HMA Asphalt Surface Course Mix 'D', N90 tapers 1.75" surface (Ton)	HMA Surface removal butt joint (Sc.Yd.)	Bituminous Materials Prime Coat (Ton)	Guardrail removal (Foot)		
				White (Foot)	Yellow (Foot)								
266+40.0 - 267+20.0	Butt Joint Taper						60	27.22		236.44	0.068		
267+20.0 - 268+25.0								105.00					
282+64.0 - 285+36.5											275.00		
283+20.0 - 284+45.0								166.67					
284+45.0 - 285+25.0	Butt Joint Taper						60	26.91		238.33	0.068		
285+25.0 - 288+25.0	Resurfacing						225		110.94		0.324		
288+25.0 - 289+05.0	Butt Joint Taper						60	26.46		227	0.065		
289+05.0 - 290+42.0								182.67					
175+00.0 - 310+00.0	EASTBOUND Winter Shut Down			13,500.0	13,500.0	3,375.0							
220+00.0 - 310+00.0	WESTBOUND Winter Shut Down			9,000	9,000.0	2,250.0							
IL 92						900							
SHEET TOTAL			0	22500	22500	5625	1305	454.33	80.59	110.94	701.77	0.524	275.00
TOTALS			2312.50	45000.00	5625.00	2643.75	1388.67	813.57		2346.55	2.27	1437.50	

FILE NAME =	USER NAME = candermanee	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION					I - 280 PRE-STAGE 'C'				F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
c:\pwworking\pwworking\candermanee\d0179717	0204502-shr-staging.dgn	DRAWN -	REVISED -						280	*	ROCK ISLAND	503	63 B				
	PLOT SCALE = 51.1985' / IN.	CHECKED -	REVISED -						SCALE:		SHEET NO.	OF	SHEETS	STA.	TO STA.	CONTRACT NO. 64815	
	PLOT DATE = Fri Sep 03 16:37:58 2010	DATE -	REVISED -									ILLINOIS FED. AID PROJECT					