



STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

Notes:
See sheet 18 of 54 for Detail A and View B-B.
Approach slab and parapet concrete shall be paid for as Concrete Superstructure.
Approach footing concrete shall be paid for as Concrete Structures.
Reinforcement shall be paid for as Reinforcement Bars, Epoxy Coated.
For V400(E) bar details, see sheet 14 of 54.
The approach footing maximum applied service bearing pressure (Qmax) = 2.0 ksf.
For bar splicer details, see sheet 48 of 54.
Cost of excavation for approach footing included with Concrete Structures.
For Porous Granular Embankment (Special) and drainage treatment details, see sheet 36 of 54.
For additional parapet details, see sheet 14 of 54.




SECTION C-C




SECTION D-D


(See Plan for dimensions not shown)




VIEW E-E



BAR d440(E)



BAR b441(E)



BAR d440(E)

BAR d441(E)

TWO APPROACHES
BILL OF MATERIAL

Bar	No.	Size	Length	Shape
d440(E)	100	#4	22'-7"	
d441(E)	92	#5	41'-6"	
d442(E)	48	#6	6'-6"	
b440(E)	68	#4	29'-8"	
b441(E)	202	#9	29'-9"	
b442(E)	4	#4	14'-8"	
b443(E)	4	#4	14'-8"	
d440(E)	68	#5	6'-10"	
d441(E)	68	#5	7'-11"	
e440(E)	32	#4	14'-8"	
e441(E)	4	#8	14'-8"	
t440(E)	172	#4	9'-8"	
w440(E)	80	#5	41'-6"	
Concrete Superstructure		Cu. Yd.	130.4	
Concrete Structures		Cu. Yd.	25.7	
Bridge Deck Grooving		Sq. Yd.	253	
Protective Coat		Sq. Yd.	302	
Reinforcement Bars, Epoxy Coated		Pound	33,900	


(Sheet 2 of 2)
BRIDGE EAST APPROACH SLAB DETAILS
STRUCTURE NO. 081-0022 (E.B.)
STRUCTURE NO. 081-0023 (W.B.)

DESIGNED	ASJ
CHECKED	SPK
DRAWN	ASJ
CHECKED	SPK


INFRASTRUCTURE
ENGINEERING | INCORPORATED
33 West Monroe | Suite 1540 | Chicago, IL 60603
P 312.425.9560 | F 312.425.9564 | www.infrastructure-eng.com

SHEET NO. 19	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
54 SHEETS	280	81-1(HB-2)R	ROCK ISLAND	503	301
CONTRACT NO. 64815					
FED. ROAD DIST. NO. - ILLINOIS FED. AID PROJECT					


STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION



FRAMING PLAN



SECTION A-A



INTERIOR DIAPHRAGM

INTERIOR BEAM MOMENT TABLE				
		0.4 Sp. 1 or 0.6 Sp. 3	Pier	0.5 Sp. 2
I_s	(in ⁴)	4,760	4,760	4,760
$I_c(n)$	(in ⁴)	13,182	-	13,182
$I_c(3n)$	(in ⁴)	9,719	-	9,719
S_s	(in ³)	345	345	345
$S_c(n)$	(in ³)	513	-	513
$S_c(3n)$	(in ³)	463	-	463
$\bar{Q}$	(k/')	0.867	1.408	0.867
$M\bar{Q}$	(k')	77	479	226
$s\bar{Q}$	(k/')	0.541	-	0.541
$M_s\bar{Q}$	(k')	59	-	169
$M\bar{L}$	(k')	288	223	448
$M\bar{I}$	(k')	86	61	115
$\bar{Q}_3 [M\bar{L} + \bar{I}]$	(k)	623	473	938
M_a	(k)	987	1,238	1,733
M_u	(k)	2,214	-	2,522
$f_s \bar{Q}$ non-comp	(ksi)	2.7	16.7	7.9
$f_s \bar{Q}$ (comp)	(ksi)	1.5	-	4.4
$f_s \bar{Q}_3 [M\bar{L} + M\bar{I}]$	(ksi)	14.6	16.5	21.9
f_s (Overload)	(ksi)	18.8	33.2	34.2
f_s (Total)	(ksi)	-	43.2	-
VR	(k)	59.2	-	48.4

*** Compact section
**** Braced non-compact and partially braced section

INTERIOR BEAM REACTION TABLE		
	Abut.	Pier
$R\bar{Q}$	(k)	56.7
$R\bar{L}$	(k)	42.5
$R\bar{I}$	(k)	10.8
R Total	(k)	110.0

Note:
The interior beam reaction at the abutment includes dead and live loads from both the superstructure and the approach slab.

I_s, S_s : Non-composite moment of inertia and section modulus of the steel section used for computing f_s (Total and Overload) due to non-composite dead loads (in⁴ and in³).
 $I_c(n), S_c(n)$: Composite moment of inertia and section modulus of the steel and deck based upon the modular ratio, "n", used for computing f_s (Total and Overload) due to short-term composite live loads (in⁴ and in³).
 $I_c(3n), S_c(3n)$: Composite moment of inertia and section modulus of the steel and deck based upon 3 times the modular ratio, "3n", used for computing f_s (Total and Overload) due to long-term composite (superimposed) dead loads (in⁴ and in³).
 $\bar{Q}$: Un-factored non-composite dead load (kips/ft.).
 $M\bar{Q}$: Un-factored moment due to non-composite dead load (kip-ft.).
 $s\bar{Q}$: Un-factored long-term composite (superimposed) dead load (kips/ft.).
 $M_s\bar{Q}$: Un-factored moment due to long-term composite (superimposed) dead load (kip-ft.).
 $M\bar{L}$: Un-factored live load moment (kip-ft.).
 $M\bar{I}$: Un-factored moment due to impact (kip-ft.).
 M_a : Factored design moment (kip-ft.).
 $1.3 [M\bar{Q} + M_s\bar{Q} + \frac{1}{3} (M\bar{L} + M\bar{I})]$
 M_u : Compact composite moment capacity according to AASHTO LFD 10.50.1.1 or compact non-composite moment capacity according to AASHTO LFD 10.48.1 (kip-ft.).
 f_s (Overload): Sum of stresses as computed from the moments below (ksi).
 $M\bar{Q} + M_s\bar{Q} + \frac{1}{3} (M\bar{L} + M\bar{I})$
 f_s (Total): Sum of stresses as computed from the moments below on non-compact section (ksi).
 $1.3 [M\bar{Q} + M_s\bar{Q} + \frac{1}{3} (M\bar{L} + M\bar{I})]$
VR: Maximum $\bar{L} +$ impact horizontal shear range within the composite portion of the span for stud shear connector design (kips).

FRAMING PLAN

STRUCTURE NO. 081-0022 (E.B.)
STRUCTURE NO. 081-0023 (W.B.)


DESIGNED SST
CHECKED SPK
DRAWN ASJ
CHECKED SPK

Note:
Two hardened washers required for each set of oversized holes.
*Alternate channel C12x30 is permitted to facilitate material acquisition. Calculated weight of structural steel is based on the lighter section. The alternate, if utilized, shall be provided at no additional cost to the Department.
** $\frac{3}{4}$ " ϕ HS bolts, $\frac{5}{16}$ " ϕ holes


INFRASTRUCTURE
ENGINEERING INCORPORATED
33 West Monroe | Suite 1540 | Chicago, IL 60603
P 312.425.9560 | F 312.425.9564 | www.infrastructure-eng.com

SHEET NO. 20	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	280	81-1(HB-2)R	ROCK ISLAND	503	302
CONTRACT NO. 64815					
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT					


STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION



BEAM ELEVATION



SECTION A-A



FIELD SPICE DETAIL
(24 Required)

TOP OF BEAM ELEVATIONS
(For Fabrication Use Only)

Beam No.	℄ Brg. W. Abut.	℄ Pier 1 or Pier 3	℄ Field Splice #1	℄ Field Splice #2	℄ Pier 2 or Pier 4	℄ Brg. E. Abut.
1	584.28	584.83	584.93	585.69	585.82	586.50
2	584.43	584.98	585.08	585.84	585.97	586.65
3	584.55	585.10	585.20	585.96	586.09	586.77
4	584.62	585.16	585.26	586.03	586.15	586.83
5	584.51	585.05	585.15	585.91	586.04	586.72
6	584.37	584.92	585.02	585.78	585.90	586.59
7	584.37	584.92	585.02	585.78	585.90	586.59
8	584.51	585.05	585.15	585.91	586.04	586.72
9	584.62	585.16	585.26	586.03	586.15	586.83
10	584.55	585.10	585.20	585.96	586.09	586.77
11	584.43	584.98	585.08	585.84	585.97	586.65
12	584.28	584.83	584.93	585.69	585.82	586.50

Notes:
All material on this sheet to be AASHTO M270
Grade 50 unless otherwise noted.
Load carrying components designated "NTR"
shall conform to the Supplemental Requirement
for Notch Toughness, Zone 2.


STEEL BEAM DETAILS
STRUCTURE NO. 081-0022 (E.B.)
STRUCTURE NO. 081-0023 (W.B.)

DESIGNED	SST
CHECKED	SPK
DRAWN	ASJ
CHECKED	SPK


INFRASTRUCTURE
ENGINEERING | INCORPORATED
33 West Monroe | Suite 1540 | Chicago, IL 60603
P 312.425.9560 | F 312.425.9564 | www.infrastructure-eng.com

SHEET NO. 21	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
54 SHEETS	280	81-1(HB-2)R	ROCK ISLAND	503	303
CONTRACT NO. 64815					
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT					


STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION




ELEVATION AT ABUTMENTS



SECTION A-A




ELEVATION AT PIER 2 AND PIER 4



SECTION B-B


TYPE I ELASTOMERIC EXP. BRG.



BEARING ASSEMBLY

Notes:
Anchor bolts shall be ASTM F1554 all-thread (or an Engineer-approved alternate material) of the grade(s) and diameter(s) specified. ASTM A307 Grade C anchor bolts may be used in lieu of ASTM F1554 Grade 36 (Fy=36ksi). The corresponding specified grade of AASHTO M314 anchor bolts may be used in lieu of ASTM F1554.
Anchor bolts for side retainers may be cast in place or installed in holes drilled before or after members are in place.
Drilled and set anchor bolts shall be installed according to Article 521.06 of the Standard Specifications.
Side retainers and other steel members required for the bearing assembly shall be included in the cost of Elastomeric Bearing Assembly, Type I.
The structural steel plates of the Bearing Assembly shall conform to the requirements of AASHTO M270 Grade 50.
Two 1/8" adjusting shims shall be provided for each bearing in addition to all other plates or shims and placed as shown on bearing details.


TYPE I ELASTOMERIC EXP. BRG.



BEARING ASSEMBLY


Note:
Shim plates shall not be placed under Bearing Assembly.

Note:
Shim plates shall not be placed under Bearing Assembly.



SIDE RETAINER AT ABUTMENTS

Equivalent rolled angle with stiffeners will be allowed in lieu of welded plates.



SIDE RETAINER AT PIER 2 & PIER 4

Equivalent rolled angle with stiffeners will be allowed in lieu of welded plates.

BILL OF MATERIAL

Item	Unit	Total
Elastomeric Bearing Assembly Type I	Each	36
Anchor Bolts 1"	Each	48
Anchor Bolts 1 1/4"	Each	24

BEARINGS - ABUTMENTS, PIER 2 & PIER 4

STRUCTURE NO. 081-0022 (E.B.)


STRUCTURE NO. 081-0023 (W.B.)

DESIGNED	SST
CHECKED	SPK
DRAWN	ASJ
CHECKED	SPK

INFRASTRUCTURE
ENGINEERING | INCORPORATED
33 West Monroe | Suite 1540 | Chicago, IL 60603
P 312.425.9560 | F 312.425.9564 | www.infrastructure-eng.com

SHEET NO. 22	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
54 SHEETS	280	81-1(HB-2)R	ROCK ISLAND	503	304
CONTRACT NO. 64815					
FED. ROAD DIST. NO. _ ILLINOIS FED. AID PROJECT					


STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION



ELEVATION AT PIER 1 AND PIER 3

SECTION B-B

FIXED BEARING



PINTLE

Notes:

Anchor bolts shall be ASTM F1554 all-thread (or an Engineer-approved alternate material) of the grade(s) and diameter(s) specified. ASTM A307 Grade C anchor bolts may be used in lieu of ASTM F1554 Grade 36 (Fy=36ksi). The corresponding specified grade of AASHTO M314 anchor bolts may be used in lieu of ASTM F1554.

Anchor bolts at fixed bearings may be either cast in place or installed in holes drilled after the supported member is in place.

Drilled and set anchor bolts shall be installed according to Article 521.06 of the Standard Specifications.

The structural steel plates of the Bearing Assembly shall conform to the requirements of AASHTO M270 Grade 50.

Two 1/8" adjusting shims shall be provided for each bearing in addition to all other plates or shims and placed as shown on bearing details.

BILL OF MATERIAL

Item	Unit	Total
Anchor Bolts 1 1/4"	Each	24


BEARINGS - PIER 1 & PIER 3
STRUCTURE NO. 081-0022 (E.B.)
STRUCTURE NO. 081-0023 (W.B.)

DESIGNED	SST
CHECKED	SPK
DRAWN	ASJ
CHECKED	SPK


INFRASTRUCTURE
ENGINEERING | INCORPORATED
33 West Monroe | Suite 1540 | Chicago, IL 60603
P 312.425.9560 | F 312.425.9564 | www.infrastructure-eng.com

SHEET NO. 23 54 SHEETS	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	280	81-1(HB-2)R	ROCK ISLAND	503	305
	CONTRACT			NO. 64815	
	FED. ROAD DIST. NO. _ ILLINOIS FED. AID PROJECT				


STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION




SOUTH WINGWALL ELEVATION




ELEVATION




NORTH WINGWALL ELEVATION



SECTION A-A



PLAN



SECTION THRU WINGWALL

BILL OF MATERIAL

ITEM	UNIT	QUANTITY
Concrete Removal	Cu. Yd.	9.3
Structural Repair of Concrete (Depth Equal to or Less Than 5 Inches)	Sq. Ft.	1

W.B. ROADWAY WEST ABUTMENT
CONCRETE REMOVAL & REPAIRS
STRUCTURE NO. 081-0022 (E.B.)
STRUCTURE NO. 081-0023 (W.B.)

Notes:
Existing reinforcement bars that project from the abutment after concrete removal shall be cut flush with the concrete left in place. Cost included with Concrete Removal.
Repair of the existing abutment shall include but not be limited to the areas shown. The actual areas to be repaired will be determined by the Engineer at the time of construction.

Indicates limits of Concrete Removal
 Indicates limits of Structural Repair of Concrete (Depth Equal to or Less Than 5 Inches)


DESIGNED	SST
CHECKED	SPK
DRAWN	ASJ
CHECKED	SPK

INFRASTRUCTURE ENGINEERING | INCORPORATED
33 West Monroe | Suite 1540 | Chicago, IL 60603
P 312.425.9560 | F 312.425.9564 | www.infrastructure-eng.com


SHEET NO. 24 54 SHEETS	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	280	81-1(HB-2)R	ROCK ISLAND	503	306
	CONTRACT NO. 64815				
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT					

P: P-051719.DGN Sheets US 67 Final Plot Date 08/02/22 6:48:15 AM W.B. Abut. Rem.dgn
11:55:03 AM
7/22/2012
-1719-

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION



ELEVATION



PLAN

Notes:
See Sheet 26 of 54 for Footing Plan, Sections A-A, B-B, C-C and Bill of Material.
Space reinforcement in cap to miss anchor bolts.
For details of piers, see sheet 47 of 54.
Four steps monolithically with cap.
*See Field Cutting Diagram on sheet 26 of 54.
**Epoxy grout h404 (E), s404 (E), s405 (E), v404 (E), and w401 (E) bars in 9\"/>

B.F. = Back Face
E.F. = Each Face
F.F. = Front Face

W.B. ROADWAY WEST ABUTMENT WIDENING
STRUCTURE NO. 081-0022 (E.B.)
STRUCTURE NO. 081-0023 (W.B.)


DESIGNED	SST
CHECKED	
DRAWN	ASJ
CHECKED	SPK

INFRASTRUCTURE
ENGINEERING | INCORPORATED
33 West Monroe | Suite 1540 | Chicago, IL 60603
P 312.425.9560 | F 312.425.9564 | www.infrastructure-eng.com


SHEET NO. 25	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	280	81-1(HB-2)R	ROCK ISLAND	503	307
CONTRACT NO. 64815					
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT					




STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION




NORTH WINGWALL ELEVATION




ELEVATION




SOUTH WINGWALL ELEVATION



SECTION A-A



PLAN



SECTION THRU WINGWALL

BILL OF MATERIAL

ITEM	UNIT	QUANTITY
Concrete Removal	Cu. Yd.	9.9
Epoxy Crack Injection	Foot	4
Structural Repair of Concrete (Depth Equal to or Less Than 5 Inches)	Sq. Ft.	2

W.B. ROADWAY EAST ABUTMENT
CONCRETE REMOVAL & REPAIRS
STRUCTURE NO. 081-0022 (E.B.)
STRUCTURE NO. 081-0023 (W.B.)

Notes:
Existing reinforcement bars that project from the abutment after concrete removal shall be cut flush with the concrete left in place. Cost included with Concrete Removal.
Repair of the existing abutment shall include but not be limited to the areas shown. The actual areas to be repaired will be determined by the Engineer at the time of construction.

- Indicates limits of Concrete Removal
- Indicates limits of Structural Repair of Concrete (Depth Equal to or Less Than 5 Inches)
- Indicates limits of Epoxy Crack Injection

INFRASTRUCTURE
ENGINEERING | INCORPORATED
33 West Monroe | Suite 1540 | Chicago, IL 60603
P 312.425.9560 | F 312.425.9564 | www.infrastructure-eng.com

SHEET NO. 27	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
54 SHEETS	280	81-1(HB-2)R	ROCK ISLAND	503	309
CONTRACT NO. 64815					
FED. ROAD DIST. NO. - ILLINOIS FED. AID PROJECT					

7/22/2010 12:00:34 PM P:\P-05\1719\DCN\Sheets\US 67 Final Plans\0810022-64815-028-WB-E-Abut-Ext.dgn




Notes:

DESIGNED	SST
CHECKED	-
DRAWN	ASJ
CHECKED	SPK


33 West Monroe | Suite 1540 | Chicago, IL 60603
P 312.425.9560 | F 312.425.9564 | www.infrastructure-eng.com

SHEET NO. 28 54 SHEETS	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	280	81-1(HB-2)R	ROCK ISLAND	503	310
	CONTRACT NO. 64815				
FED. ROAD DIST. NO. - ILLINOIS FED. AID PROJECT					

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION




PARTIAL FOOTING PLAN



SECTION A-A

PILE DATA

Type: HP10x42 with pile shoes
Nominal Required Bearing: 335 kips
Allowable Resistance Available: 112 kips
Est. Length: 29 feet
No. Production Piles: 2
No. Test Piles: 0




FIELD CUTTING DIAGRAM


Order bars full length.
Cut to fit as shown and use remainder
of bars in opposite face.

BILL OF MATERIAL

Bar	No.	Size	Length	Shape
h400 (E)	4	#5	6'-10"	
h401 (E)	4	#5	42'-10"	
h402 (E)	16	#5	5'-6"	
h403 (E)	10	#6	15'-6"	
h404 (E)	12	#6	4'-9"	
h405 (E)	6	#6	11'-5"	
h406 (E)	4	#6	13'-0"	
h407 (E)	3	#6	5'-5"	
h400 (E)	11	#5	5'-8"	
S403 (E)	7	#5	8'-0"	
S404 (E)	58	#5	3'-5"	
S405 (E)	16	#5	3'-9"	
V400 (E)	14	#5	5'-3"	
V401 (E)	8	#5	6'-3"	
V402 (E)	18	#5	7'-0"	
V404 (E)	2	#5	3'-9"	
V405 (E)	2	#5	3'-7"	
V407 (E)	2	#5	2'-10"	
W400 (E)	12	#5	10'-1"	
W401 (E)	12	#5	4'-2"	
Porous Granular Embankment, Special				
Structure Excavation	Cu. Yd.	116		
Concrete Structures	Cu. Yd.	10.7		
Concrete Encasement	Cu. Yd.	0.7		
Reinforcement Bars, Epoxy Coated	Pound	1680		
Furnishing Steel Piles, HP10x42	Foot	58.0		
Driving Piles	Foot	58.0		
Pile Shoes	Each	2		
Geocomposite Wall Drain	Sq. Yd.	43		
Pipe Underdrains for Structures 4"	Foot	63		



SECTION B-B



SECTION C-C

Notes:
→ Denotes direction of batter piles.
* See Field Cutting Diagram

DESIGNED	SST
CHECKED	-
DRAWN	ASJ
CHECKED	SPK

W.B. ROADWAY EAST ABUTMENT DETAILS
STRUCTURE NO. 081-0022 (E.B.)
STRUCTURE NO. 081-0023 (W.B.)



INFRASTRUCTURE
ENGINEERING | INCORPORATED
33 West Monroe | Suite 1540 | Chicago, IL 60603
P 312.425.9560 | F 312.425.9564 | www.infrastructure-eng.com

SHEET NO. 29	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
54 SHEETS	280	81-1(HB-2)R	ROCK ISLAND	503	311
CONTRACT NO. 64815					
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT					

7/22/2010 12:01:24 PM P:\P-05\1719\DCN\Sheets\US 67 Final Plans\0810022-64815-030-EB_W-Abut-Rom.dgn



DESIGNED	SST
CHECKED	SPK
DRAWN	ASJ
CHECKED	SPK



SHEET NO. 30 54 SHEETS	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	280	81-1(HB-2)R	ROCK ISLAND	503	312
				CONTRACT NO. 64815	
FED. ROAD DIST. NO. - ILLINOIS FED. AID PROJECT					





BILL OF MATERIAL

Item	Unit	Total
Concrete Removal	Cu. Yd.	9.3

E.B. ROADWAY WEST ABUTMENT CONCRETE REMOVAL
STRUCTURE NO. 081-0022 (E.B.)
STRUCTURE NO. 081-0023 (W.B.)

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION



Notes:
See Sheet 32 of 54 for Footing Plan, Sections A-A, B-B, C-C, and Bill of Material.
Space reinforcement in cap to miss anchor bolts.
For details of piles, see sheet 47 of 54.
Pour steps monolithically with cap.
*See Field Cutting Diagram on sheet 32 of 54.
**Epoxy grout h404(E), s404(E), s405(E), v404(E), and w401(E) bars in 9\"/>

PLAN

B.F. = Back Face
E.F. = Each Face
F.F. = Front Face

E.B. ROADWAY WEST ABUTMENT WIDENING
STRUCTURE NO. 081-0022 (E.B.)
STRUCTURE NO. 081-0023 (W.B.)


DESIGNED	SST
CHECKED	
DRAWN	ASJ
CHECKED	SPK



INFRASTRUCTURE
ENGINEERING | INCORPORATED
33 West Monroe | Suite 1540 | Chicago, IL 60603
P 312.425.9560 | F 312.425.9564 | www.infrastructure-eng.com

SHEET NO. 31	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	280	81-1(HB-2)R	ROCK ISLAND	503	313
CONTRACT NO. 64815					
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT					


STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION




PARTIAL FOOTING PLAN

PILE DATA

Type: HP10x42 with pile shoes
Nominal Required Bearing: 335 kips
Allowable Resistance Available: 112 kips
Est. Length: 24.1 feet
No. Production Piles: 2
No Test Piles: 0



SECTION A-A



FIELD CUTTING DIAGRAM

Order bars full length.
Cut to fit as shown and use remainder
of bars in opposite face.


BAR S402(E)

BARS S404(E) & S405(E)


BAR n400(E)

BILL OF MATERIAL

Bar	No.	Size	Length	Shape
h400 (E)	4	#5	6'-10"	
h401 (E)	4	#5	42'-10"	
h402 (E)	16	#5	5'-6"	
h403 (E)	10	#6	15'-6"	
h404 (E)	12	#6	4'-9"	
h405 (E)	6	#6	11'-5"	
h406 (E)	4	#6	13'-0"	
h407 (E)	3	#6	5'-5"	
n400 (E)	11	#5	5'-8"	
S401 (E)	18	#5	4'-0"	
S402 (E)	7	#5	8'-0"	
S404 (E)	58	#5	3'-5"	
S405 (E)	16	#5	3'-9"	
t400 (E)	14	#5	5'-3"	
W401 (E)	8	#5	6'-3"	
W402 (E)	18	#5	7'-0"	
W403 (E)	2	#5	3'-1"	
W404 (E)	2	#5	3'-9"	
W405 (E)	2	#5	3'-7"	
W400 (E)	12	#5	10'-1"	
W401 (E)	12	#5	4'-2"	
Porous Granular Embankment, Special				Cu. Yd. 122
Structure Excavation				Cu. Yd. 104
Concrete Structures				Cu. Yd. 10.8
Concrete Encasement				Cu. Yd. 0.7
Reinforcement Bars, Epoxy Coated				Pound 1750
Furnishing Steel Piles, HP10x42				Foot 48.2
Driving Piles				Foot 48.2
Pile Shoes				Each 2
Geocomposite Wall Drain				Sq. Yd. 43
Pipe Underdrains for Structures 4"				Foot 63



SECTION B-B



SECTION C-C

Notes:
→ Denotes direction of batter piles.
* See Field Cutting Diagram

DESIGNED	SST
CHECKED	
DRAWN	ASJ
CHECKED	SPK

E.B. ROADWAY WEST ABUTMENT DETAILS STRUCTURE NO. 081-0022 (E.B.) STRUCTURE NO. 081-0023 (W.B.)



**INFRASTRUCTURE
ENGINEERING** INCORPORATED
33 West Monroe | Suite 1540 | Chicago, IL 60603
P 312.425.9560 | F 312.425.9564 | www.infrastructure-eng.com

SHEET NO. 32	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
54 SHEETS	280	81-1(HB-2)R	ROCK ISLAND	503	314
CONTRACT NO. 64815					
FED. ROAD DIST. NO. - ILLINOIS FED. AID PROJECT					

7/22/2010 12:02:39 PM P:\P-05\1719\0GN\Sheets\US 67 Final Plans\0810022-64815-033-EB_E-Abut-Rem.dgn



PLAN



Item	Unit	Total
Concrete Removal	Cu. Yd.	9.9


DESIGNED SST
CHECKED SPK
DRAWN ASJ
CHECKED SPK




INFRASTRUCTURE
ENGINEERING | INCORPORATED
33 West Monroe | Suite 1540 | Chicago, IL 60603
P 312.425.9560 | F 312.425.9564 | www.infrastructure-eng.com

SHEET NO. 33 54 SHEETS	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	280	81-1(HB-2)R	ROCK ISLAND	503	315
				CONTRACT NO. 64815	
FED. ROAD DIST. NO. _ ILLINOIS FED. AID PROJECT					

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION



ELEVATION



PLAN

Notes:
See sheet 35 of 54 for Footing Plan, Sections A-A, B-B, C-C and Bill of Material.
Space reinforcement in cap to miss anchor bolts.
For details of piles, see sheet 47 of 54.
Pour steps monolithically with cap.
*See Field Cutting Diagram on sheet 35 of 54.
**Epoxy grout h404(E), s404(E), s405(E), v406(E), and w401 (E) bars in 9\"/>

B.F. = Back Face
E.F. = Each Face
F.F. = Front Face


E.B. ROADWAY EAST ABUTMENT WIDENING
STRUCTURE NO. 081-0022 (E.B.)
STRUCTURE NO. 081-0023 (W.B.)

DESIGNED	SST
CHECKED	-
DRAWN	ASJ
CHECKED	SPK


INFRASTRUCTURE
ENGINEERING | INCORPORATED
33 West Monroe | Suite 1540 | Chicago, IL 60603
P 312.425.9560 | F 312.425.9564 | www.infrastructure-eng.com

SHEET NO. 34	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
54 SHEETS	280	81-1(HB-2)R	ROCK ISLAND	503	316
CONTRACT NO. 64815					
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT					

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION




PARTIAL FOOTING PLAN



SECTION A-A


PILE DATA

Type: HP10x42 with pile shoes
Nominal Required Bearing: 335 kips
Allowable Resistance Available: 112 kips
Est. Length: 29 feet
No. Production Piles: 2
No. Test Piles: 0



FIELD CUTTING DIAGRAM

Order bars full length.
Cut to fit as shown and use remainder
of bars in opposite face.




BAR s403(E)

BAR s404(E) & s405(E)


BAR n400(E)

BILL OF MATERIAL

Bar	No.	Size	Length	Shape
n400 (E)	4	#5	6'-10"	
n401 (E)	4	#5	42'-10"	
n402 (E)	16	#5	5'-6"	
n403 (E)	10	#6	15'-6"	
n404 (E)	12	#6	4'-9"	
n405 (E)	6	#6	11'-5"	
n406 (E)	4	#6	13'-0"	
n407 (E)	3	#6	5'-5"	
n400 (E)	11	#5	5'-8"	
s403 (E)	7	#5	8'-0"	
s404 (E)	58	#5	3'-5"	
s405 (E)	16	#5	3'-9"	
t400 (E)	14	#5	5'-3"	
v401 (E)	8	#5	6'-3"	
v402 (E)	18	#5	7'-0"	
v404 (E)	2	#5	3'-9"	
v405 (E)	2	#5	3'-7"	
v407 (E)	2	#5	2'-10"	
w400 (E)	12	#5	10'-1"	
w401 (E)	12	#5	4'-2"	
Porous Granular Embankment, Special			Cu. Yd.	116
Structure Excavation			Cu. Yd.	102
Concrete Structures			Cu. Yd.	10.7
Concrete Encasement			Cu. Yd.	0.7
Reinforcement Bars, Epoxy Coated			Pound	1670
Furnishing Steel Piles, HP10x42			Foot	58.0
Driving Piles			Foot	58.0
Pile Shoes			Each	2
Geocomposite Wall Drain			Sq. Yd.	43
Pipe Underdrains for Structures 4"			Foot	63



SECTION B-B



SECTION C-C

DESIGNED	SST
CHECKED	-
DRAWN	ASJ
CHECKED	SPK


Notes:
→ Denotes direction of batter piles.
* See Field Cutting Diagram

INFRASTRUCTURE
ENGINEERING | INCORPORATED
33 West Monroe | Suite 1540 | Chicago, IL 60603
P 312.425.9560 | F 312.425.9564 | www.infrastructure-eng.com

SHEET NO.	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
54 SHEETS	280	81-1(HB-2)R	ROCK ISLAND	503	317
CONTRACT NO. 64815					
FED. ROAD DIST. NO. - ILLINOIS FED. AID PROJECT					


E.B. ROADWAY EAST ABUTMENT DETAILS
STRUCTURE NO. 081-0022 (E.B.)
STRUCTURE NO. 081-0023 (W.B.)

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION



TYPICAL ABUTMENT DRAINAGE DETAIL

*Included in the cost of Pipe Underdrains for Structures.



SECTION A-A

Note:
All drainage system components shall extend to 2'-0" from the end of each wingwall except an outlet pipe shall extend until intersecting with the side slopes. The pipe shall drain into concrete headwall. See Article 601.05 of the Standard Specifications and Highway Standard 601101.


DESIGNED
CHECKED
DRAWN ASJ
CHECKED SPK




**INFRASTRUCTURE
ENGINEERING** | INCORPORATED
33 West Monroe | Suite 1540 | Chicago, IL 60603
P 312.425.9580 | F 312.425.9584 | www.infrastructure-eng.com

SHEET NO. 36 54 SHEETS	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	280	81-1(HB-2)R	ROCK ISLAND	503	318
CONTRACT NO. 64815					
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT					


STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION




PLAN




NORTH ELEVATION
(Looking South)



WEST ELEVATION
(Looking East)



SOUTH ELEVATION
(Looking North)



EAST ELEVATION
(Looking West)

BILL OF MATERIAL

ITEM	UNIT	QUANTITY
Structural Repair of Concrete (Depth Equal to or Less Than 5 Inches)	Sq. Ft.	13

PIER 1 REPAIRS

STRUCTURE NO. 081-0022 (E.B.)
STRUCTURE NO. 081-0022 (W.B.)

DESIGNED	
CHECKED	
DRAWN	ASJ
CHECKED	SPK

Note:
Repair of the existing pier shall include but not be limited to the areas shown. The actual areas to be repaired will be determined by the Engineer at the time of construction




Indicates limits of Structural Repair of Concrete
(Depth Equal to or Less Than 5 Inches)




INFRASTRUCTURE
ENGINEERING | INCORPORATED
33 West Monroe | Suite 1540 | Chicago, IL 60603
P 312.425.9560 | F 312.425.9564 | www.infrastructure-eng.com


SHEET NO. 37 54 SHEETS	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	280	81-1(HB-2)R	ROCK ISLAND	503	319
				CONTRACT NO. 64815	
FED. ROAD DIST. NO. _ ILLINOIS FED. AID PROJECT					




SECTION B-B




SECTION C-C




TOP PLAN



BARS S461 (E) & U460 (E)



BARS U461 (E) & U462 (E) BAR S460 (E)



END VIEW

ELEVATION
(Looking East)

BAR V463 (E)

BAR V461 (E)

BILL OF MATERIAL				
Bar	No.	Size	Length	Shape
h460 (E)	8	#5	35'-4"	————
S460 (E)	72	#5	4'-8"	┐
S461 (E)	5	#5	8'-7"	┐
SD460	1	#4	12'-9"	~~~~~
SD461 (E)	1	#4	6'-5"	~~~~~
U460 (E)	6	#5	8'-8"	┐
U461 (E)	6	#5	9'-1"	┐
U462 (E)	6	#5	12'-11"	┐
V460	15	#8	12'-9"	————
V461 (E)	15	#6	9'-11"	————
V462 (E)	15	#6	9'-10"	————
V463 (E)	6	#6	9'-0"	————
V464 (E)	6	#6	8'-10"	————
Concrete Structures			Cu. Yd.	11.1
Reinforcement Bars, Epoxy Coated			Pounds	1590
Reinforcement Bars			Pounds	770
Drilled Shaft in Soil			Cu. Yd.	9.3
Drilled Shaft in Rock			Cu. Yd.	0.4
Concrete Sealer			Sq. Ft.	396

Allowable Soil Bearing Pressure is 10,000 psf on sound rock.

Cast Steps monolithically with cap.

Space cap reinforcement to miss anchor bolts.

Minimum lap for spirals = 2'-0"

Epoxy grout S₄₆₀(E) bars in 9" (min.) drilled holes.

See Section 584 of the Standard Specifications.

Cost of hole drilling and epoxy grouting is included with Reinforcement Bars, Epoxy Coated.

** Length is height of spiral.

PIER 1 WIDENING
STRUCTURE NO. 081-0022 (E.B.)
STRUCTURE NO. 081-0023 (W.B.)

DESIGNED	SPK
CHECKED	IAN
DRAWN	ASJ
CHECKED	SPK


* The quantities and reinforcement detailing are based on the top of shaft and the estimated top of rock elevations shown and may change based on the actual top of rock elevation encountered and final top of shaft elevation.




INFRASTRUCTURE
ENGINEERING | INCORPORATED
33 West Monroe | Suite 1540 | Chicago, IL 60603
P 312.425.9560 | F 312.425.9564 | www.infrastructure-eng.com

SHEET NO.38	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	280	81-1(HB-2)R	ROCK ISLAND	503	320
	54 SHEETS		CONTRACT NO. 64815		
FED. ROAD DIST. NO. _		ILLINOIS	FED. AID PROJECT		


STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION




PLAN




NORTH ELEVATION
(Looking South)



WEST ELEVATION
(Looking East)



SOUTH ELEVATION
(Looking North)



EAST ELEVATION
(Looking West)

BILL OF MATERIAL

ITEM	UNIT	QUANTITY
Epoxy Crack Injection	Foot	15
Structural Repair of Concrete (Depth Equal to or Less Than 5 Inches)	Sq. Ft.	4

PIER 2 REPAIRS
STRUCTURE NO. 081-0022 (E.B.)
STRUCTURE NO. 081-0022 (W.B.)

DESIGNED
CHECKED
DRAWN ASJ
CHECKED SPK

Note:
Repair of the existing pier shall include but not be limited to the areas shown. The actual areas to be repaired will be determined by the Engineer at the time of construction.

 Indicates limits of Structural Repair of Concrete (Depth Equal to or Less Than 5 Inches)
 Indicates limits of Epoxy Crack Injection




**INFRASTRUCTURE
ENGINEERING** | INCORPORATED
33 West Monroe | Suite 1540 | Chicago, IL 60603
P 312.425.9560 | F 312.425.9564 | www.infrastructure-eng.com

SHEET NO. 39	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
54 SHEETS	280	81-1(HB-2)R	ROCK ISLAND	503	321
CONTRACT NO. 64815					
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT					

P:\P-081\1715\NDG\Sheets\US 67 Final Plans\0810022-64815-035-Pier 2 Repairs.dgn
12:06:28 PM
7/22/2010

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION



DESIGNED	SPK
CHECKED	LAN
DRAWN	ASJ
CHECKED	SPK

* The quantities and reinforcement detailing are based on the top of shaft and the estimated top of rock elevations shown and may change based on the actual top of rock elevation encountered and the final top of shaft elevation.



**INFRASTRUCTURE
ENGINEERING** | INCORPORATED
33 West Monroe | Suite 1540 | Chicago, IL 60603
P 312.425.9560 | F 312.425.9554 | www.infrastructure-eng.com

SHEET NO. 40	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
54 SHEETS	280	81-1(HB-2)R	ROCK ISLAND	503	322
CONTRACT NO. 64815					
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT					

**PIER 2 WIDENING
STRUCTURE NO. 081-0022 (E.B.)
STRUCTURE NO. 081-0023 (W.B.)**

Q Brg.

1.5' x 1.3'

— 1.5' x 1.9'

— 3.8'

-1.3'

(Looking South)

(Looking East)

(Looking North)

(Looking West)

ITEM	UNIT	QUANTITY
Epoxy Crack Injection	Foot	5
Structural Repair of Concrete (Depth Equal to or Less Than 5 Inches)	Sq. Ft.	5

DESIGNED
CHECKED
DRAWN <i>ASJ</i>
CHECKED <i>SPK</i>

Repair of the existing pier shall include but not be limited to the areas shown. The actual areas to be repaired will be determined by the Engineer at the time of construction.



Indicates limits of Structural Repair of Concrete
(Depth Equal to or Less Than 5 Inches)




Indicates limits of Epoxy Crack Injection




INFRASTRUCTURE
ENGINEERING | INCORPORATED
33 West Monroe | Suite 1540 | Chicago, IL 60603
P 312.425.9560 | F 312.425.9564 | www.infrastructure-eng.com

SHEET NO. 41 54 SHEETS	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	280	81-1(HB-2)R	ROCK ISLAND	503	323
			CONTRACT NO. 64815		
FED. ROAD DIST. NO. -		ILLINOIS	FED. AID PROJECT		


STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION



TOP PLAN



ELEVATION
(Looking East)



BARS U461 (E) & U462 (E)

BAR V463 (E)

BARS S461 (E) & U460 (E)

BAR S460 (E)

BAR V461 (E)

BILL OF MATERIAL

Bar	No.	Size	Length	Shape
h460 (E)	8	#5	35'-4"	
S460 (E)	72	#5	4'-8"	
S461 (E)	5	#5	8'-7"	
S464	1	#4	14'-1"	
S465 (E)	1	#4	6'-1"	
U460 (E)	6	#5	8'-8"	
U461 (E)	6	#5	9'-1"	
U462 (E)	6	#5	12'-11"	
V461 (E)	15	#6	9'-11"	
V463 (E)	6	#6	9'-0"	
V464 (E)	6	#6	8'-10"	
V469	15	#8	14'-1"	
V470 (E)	15	#6	9'-6"	
Concrete Structures		Cu. Yd.	11.1	
Reinforcement Bars, Epoxy Coated		Pound	1580	
Reinforcement Bars		Pounds	850	
Drilled Shaft in Soil		Cu. Yd.	10.3	
Drilled Shaft in Rock		Cu. Yd.	0.4	
Concrete Sealer		Sq. Ft.	406	

Allowable Soil Bearing Pressure is 10,000 psf on sound rock.
Cast Steps monolithically with cap.
Space cap reinforcement to miss anchor bolts.
Minimum lap for spirals = 2'-0"
Epoxy grout S460 (E) bars in 9" (min.) drilled holes.
See Section 584 of the Standard Specifications.
Cost of hole drilling and epoxy grouting is included with Reinforcement Bars, Epoxy Coated.
** Length is height of spiral.

PIER 3 WIDENING
STRUCTURE NO. 081-0022 (E.B.)
STRUCTURE NO. 081-0023 (W.B.)

DESIGNED	SPK
CHECKED	LAN
DRAWN	ASJ
CHECKED	SPK


* The quantities and reinforcement detailing are based on the top of shaft and the estimated top of rock elevations shown and may change based on the actual top of rock elevation encountered and the final top of shaft elevation.




INFRASTRUCTURE
ENGINEERING INCORPORATED
33 West Monroe | Suite 1540 | Chicago, IL 60603
P 312.425.9560 | F 312.425.9564 | www.infrastructure-eng.com

SHEET NO. 42	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
54 SHEETS	280	81-1(HB-2)R	ROCK ISLAND	503	324
CONTRACT NO. 64815					
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT					


STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION




PLAN




NORTH ELEVATION
(Looking South)



WEST ELEVATION
(Looking East)



SOUTH ELEVATION
(Looking North)



EAST ELEVATION
(Looking West)

BILL OF MATERIAL

ITEM	UNIT	QUANTITY
Epoxy Crack Injection	Foot	4
Structural Repair of Concrete (Depth Equal to or Less Than 5 Inches)	Sq. Ft.	2

PIER 4 REPAIRS
STRUCTURE NO. 081-0022 (E.B.)
STRUCTURE NO. 081-0022 (W.B.)

DESIGNED	
CHECKED	
DRAWN	ASJ
CHECKED	SPK

Note:
Repair of the existing pier shall include but not be limited to the areas shown. The actual areas to be repaired will be determined by the Engineer at the time of construction.



Indicates limits of Structural Repair of Concrete
(Depth Equal to or Less Than 5 Inches)



Indicates limits of Epoxy Crack Injection



INFRASTRUCTURE
ENGINEERING . INCORPORATED
33 West Monroe | Suite 1540 | Chicago, IL 60603
P 312.425.9560 | F 312.425.9564 | www.infrastructure-eng.com


SHEET NO. 43 54 SHEETS	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	280	81-1(HB-2)R	ROCK ISLAND	503	325
CONTRACT NO. 64815					
FED. ROAD DIST. NO. _ ILLINOIS FED. AID PROJECT					

17191
7/22/2012
12:08:58 PM
P:\P-05\17191\05\Drawings\Sheet\US 67 Final Plans\081-0022-64815-043-Pier 4 Repairs.dgn

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
280	81-1(HB-2)R	ROCK ISLAND	503	326
		CONTRACT NO. 64815		
FED. ROAD DIST. NO. _		ILLINOIS FED. AID PROJECT		

- Beginning of Wall at Front Face
Sta. 61+84.30 (@ U.S. Route 67), 44.14' Lt.
Elev. 569.83

End of Wall at Front Face _____
Sta. 63+23.38 (C U.S. Route 67), 48.90' Lt.
Elev. 569.83



ELEVATION



Footings shall be placed monolithically and shall have no construction joints and no expansion joints.


*Cost of Roofing Felt included
with Concrete Structures.*

BILL OF MATERIAL

Bar	No.	Size	Length	Shgpe
h 490 (E)	48	#5	31'-1"	_____
h 491 (E)	32	#5	27'-6"	_____
n 490 (E)	290	#5	7'-4"	_____
t 490 (E)	290	#5	10'-4"	_____
v 490 (E)	290	#5	6'-8"	_____
w 490 (E)	32	#6	26'-0"	_____
w 491 (E)	88	#5	30'-5"	_____
w 492 (E)	8	#5	23'-8"	_____
w 493 (E)	8	#5	10'-2"	_____
Structure Excavation			Cu. Yd.	504
Concrete Structures			Cu. Yd.	69.9
Porous Granular Embankment (Special)			Cu. Yd.	31
Reinforcement Bars, Epoxy Coated			Pound	14160
Geocomposite Wall Drain			Sq. Yd.	91
Pipe Underdrains for Structures, 4"			Foot	189

CONSTRUCTION JOINT

DESIGNED	LAN
CHECKED	MMB
DRAWN	LAN
CHECKED	MMB



SECTION A-A

* Included in the cost of Pipe Underdrains for Structures, 4".

** v₄₉₀ (E) bars shall not be placed more than 1½" cl. from back face of wall.


INFRASTRUCTURE
ENGINEERING | INCORPORATED
33 West Monroe | Suite 1540 | Chicago, IL 60603
P 312.425.9560 | F 312.425.9564 | www.infrastructure-eng.com

EXPANSION JOINT


SHEET NO. 45 54 SHEETS	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	280	81-1(HB-2)R	ROCK ISLAND	503	327
	FED. ROAD DIST. NO. - ILLINOIS			CONTRACT NO. 64815	

WEST SLOPE WALL RETAINING WALL
STRUCTURE NO. 081-0022 (E.B.)
STRUCTURE NO. 081-0023 (W.B.)


STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION




NORTHWEST LANDSCAPE WALL LAYOUT
(Showing Location of Bottom Course of Block)



NORTHEAST LANDSCAPE WALL LAYOUT
(Showing Location of Bottom Course of Block)




SOUTHWEST LANDSCAPE WALL LAYOUT
(Showing Location of Bottom Course of Block)



SOUTHEAST LANDSCAPE WALL LAYOUT
(Showing Location of Bottom Course of Block)

Notes:
Contractor to remove existing blocks and store off site.
Contractor to reinstall blocks after completion of bridge widening.
Excavate 1'-0" below ground at each wall and place 6" of CA-7 gradation crushed stone and one 6 inch thick block in excavation. Excavation to extend 1'-0" behind wall.
Backfill behind wall with CA-7 gradation crushed stone.
Cost of CA-7 crushed stone and non-woven filter fabric envelope are included in the cost of Remove and Reinstall Landscape Block Wall.



SECTION A-A

For Information Only

BILL OF MATERIAL

Item	Unit	Total
Remove and Reinstall Landscape Block Wall	Sq. Ft.	1390


LANDSCAPE WALLS
STRUCTURE NO. 081-0022 (E.B.)
STRUCTURE NO. 081-0023 (W.B.)

DESIGNED	LAN
CHECKED	MMB
DRAWN	LAN
CHECKED	MMB

INFRASTRUCTURE ENGINEERING INCORPORATED
33 West Monroe | Suite 1540 | Chicago, IL 60603
P 312.425.9560 | F 312.425.9564 | www.infrastructure-eng.com


SHEET NO. 46	F.A.I. RTE. 280	SECTION 81-1(HB-2)R	COUNTY ROCK ISLAND	TOTAL SHEETS 503	SHEET NO. 328
54 SHEETS	CONTRACT NO. 64815				
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT					

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION




STEEL PILE TABLE

Designation	Depth d	Flange width b _f	Web and Flange thickness t	Encasement diameter A
HP 14x117	14 1/4"	14 7/8"	1 3/16"	30"
x102	14"	14 3/4"	1 1/16"	30"
x89	13 7/8"	14 3/4"	5/8"	30"
x73	13 5/8"	14 5/8"	1/2"	30"
HP 12x84	12 1/4"	12 1/4"	1 1/16"	24"
x74	12 1/8"	12 1/4"	5/8"	24"
x63	12"	12 1/8"	1/2"	24"
x53	11 3/4"	12"	7/16"	24"
HP 10x57	10"	10 1/4"	9/16"	24"
x42	9 3/4"	10 1/8"	7/16"	24"
HP 8x36	8"	8 1/8"	7/16"	18"




ELEVATION




DETAIL A

H-PILE SHOE ATTACHMENT




ELEVATION




DETAIL "B"

WELDED COMMERCIAL SPLICE




ISOMETRIC VIEW



ISOMETRIC VIEW


WELDED COMMERCIAL SPLICE ALTERNATE

- * Interrupt welds 1/4" from end of web and/or each flange.
- ** Remove portions of backup plates that extend outside the flanges.
- *** Weld size per pile shoe manufacturer (5/16" min.).




ELEVATION

PILE ENCASEMENT




ELEVATION




DETAIL D

WELDED PLATE FIELD SPLICE



SECTION A-A



END VIEW

Designation	F	F _t	F _w	W	W _t	W _w
HP 14x117	12 1/2"	1"	7/8"	7 3/4"	5 1/2"	1 1/2"
x102	12 1/2"	7/8"	3/4"	7 3/4"	5 1/2"	1 1/2"
x89	12 1/2"	3/4"	1/2"	7 3/4"	5 1/2"	1 1/2"
x73	12 1/2"	5/8"	9/16"	7 3/4"	5 1/2"	1 1/2"
HP 12x84	10"	7/8"	1 1/16"	6 1/2"	5 1/2"	1 1/2"
x74	10"	7/8"	1 1/16"	6 1/2"	5 1/2"	1 1/2"
x63	10"	5/8"	1/2"	6 1/2"	5 1/2"	3/8"
x53	10"	5/8"	1/2"	6 1/2"	5 1/2"	3/8"
HP 10x57	8"	3/4"	9/16"	5 1/4"	5 1/2"	3/8"
x42	8"	5/8"	9/16"	5 1/4"	5 1/2"	3/8"
HP 8x36	7"	5/8"	7/16"	4 1/4"	5 1/2"	3/8"

HP PILE DETAILS

STRUCTURE NO. 081-0022 (E.B.)
STRUCTURE NO. 081-0023 (W.B.)

Note:
The steel H-piles shall be according to
AASHTO M270 Grade 50.

INFRASTRUCTURE
ENGINEERING INCORPORATED
33 West Monroe | Suite 1540 | Chicago, IL 60603
P 312.425.9560 | F 312.425.9564 | www.infrastructure-eng.com


SHEET NO. 47	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
54 SHEETS	280	81-1(HB-2)R	ROCK ISLAND	503	329
CONTRACT NO. 64815					
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT					

DESIGNED	
CHECKED	
DRAWN	ASJ
CHECKED	SPK

F-HP 11-1-09

1719 1/22/2010 12:11:10 PM P:\NF-08\719\CON Sheets\US 67 Final Plans\0810022-64815-040-Splicer.dgn

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION



STANDARD BAR SPLICER ASSEMBLY


Minimum Lap Lengths				
Bar size to be spliced	Table 1	Table 2	Table 3	Table 4
3, 4	1'-5"	1'-11"	2'-1"	2'-4"
5	1'-9"	2'-5"	2'-7"	2'-11"
6	2'-1"	2'-11"	3'-1"	3'-6"
7	2'-9"	3'-10"	4'-2"	4'-8"
8	3'-8"	5'-1"	5'-5"	6'-2"
9	4'-7"	6'-5"	6'-10"	7'-9"

Table 1: Black bar, 0.8 Class C
Table 2: Black bar, Top bar lap, 0.8 Class C
Table 3: Epoxy bar, 0.8 Class C
Table 4: Epoxy bar, Top bar lap, 0.8 Class C

Threaded splicer bar length = min. lap length + 1 1/2" + thread length


* Epoxy not required on Bar Splicer Assembly components used in conjunction with black bars.

Location	Bar size	No. assemblies required	Table for minimum lap length




BAR SPLICER ASSEMBLY FOR #5 BAR ON SEMI-INTEGRAL ABUTMENTS

No. required = 184



BAR SPLICER ASSEMBLY FOR #5 BAR ON STUB ABUTMENTS

No. required = 0



STANDARD MECHANICAL SPLICER

Location	Bar size	No. assemblies required

INSTALLATION AND SETTING METHODS

"A" : Set bar splicer assembly by means of a template bolt.
"B" : Set bar splicer assembly by nailing to wood forms or cementing to steel forms.
(E) : Indicates epoxy coating.

NOTES

Splicer bars shall be deformed with threaded ends and have a minimum 60 ksi yield strength.
All reinforcement shall be lapped and tied to the splicer bars.
Bar splicer assemblies shall be epoxy coated according to the requirements for reinforcement bars. See Section 508 of the Standard Specifications.
See special provision for Mechanical Splicers.
See approved list of bar splicer assemblies and mechanical splicers for alternatives.

**BAR SPLICER ASSEMBLY AND MECHANICAL SPLICER DETAILS
STRUCTURE NO. 081-0022 (E.B.)
STRUCTURE NO. 081-0023 (W.B.)**

DESIGNED	-
CHECKED	-
DRAWN	ASJ
CHECKED	SPK


BSD-1 11-1-09

INFRASTRUCTURE ENGINEERING INCORPORATED
33 West Monroe | Suite 1540 | Chicago, IL 60603
P 312.425.9560 | F 312.425.9564 | www.infrastructure-eng.com

SHEET NO. 48	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	280	81-1(HB-2)R	ROCK ISLAND	503	330
CONTRACT NO. 64815					
FED. ROAD DIST. NO. _ ILLINOIS FED. AID PROJECT					

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

Notes:
When cantilever forming brackets are used, the work shall be done according to Article 503.06(b) of the Standard Specifications, except as modified below and in the details shown on this sheet.
The finishing machine rails shall be placed on the top flange of the exterior beams.
The beams or girders, supporting cantilever forming brackets, shall be tied together at 4 foot intervals.
For Standard construction, or Stage Construction the Hardwood bracing materials shall be placed as shown between webs of beams in each bay.



**FORM BRACES FOR
STANDARD CONSTRUCTION**

**CANTILEVER FORMING BRACKETS
FOR SUPERSTRUCTURES WITH
W27 BEAMS AND SMALLER
STRUCTURE NO. 081-0022 (E.B.)
STRUCTURE NO. 081-0023 (W.B.)**

DESIGNED
CHECKED
DRAWN ASJ
CHECKED SPK


SB-1 11-1-09



**INFRASTRUCTURE
ENGINEERING** INCORPORATED
33 West Monroe | Suite 1540 | Chicago, IL 60603
P 312.423.9560 | F 312.425.9564 | www.infrastructure-eng.com

SHEET NO. 49 54 SHEETS	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	280	81-1(HB-2)R	ROCK ISLAND	503	331
CONTRACT NO. 64815					
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT					

7/22/2010 12:11:54 PM P:\P-05\1719\DCN\Sheets\US 67 Final Plans\0810022-64815-050-Slipform.mxdn



MP rebar lapped
x(E) bars (at
locations)

2 1/2" c/c

2 1/2" c/c

#3 (E) bar
at 11" c/c.

#4 (E) bar

1 1/2" c/c

6"

1'-0"

SHEET NO. 50	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	280	81-1(HB-2)R	ROCK ISLAND	503	332
	54 SHEETS			CONTRACT NO. 64815	
FED. ROAD DIST. NO. - ILLINOIS FED. AID PROJECT					

All dimensions shall remain the same as shown on superstructure details, except dimensions A and B which are to be revised as shown to provide additional clearance. Additional concrete needed to revise dimension A and B = 0.0218 cu. yds./ft. of parapet.

Place aluminum sheet in curb portion at and near piers. Full thickness saw cut at all joint locations in lieu of cork joint filler.

Steel superstructure shown. Other superstructure types similar.

DESIGNED	
CHECKED	-
DRAWN	ASJ
CHECKED	SPK

CONCRETE PARAPET
SLIPFORMING OPTION

STRUCTURE NO. 081-0022 (E.B.)
STRUCTURE NO. 081-0023 (W.B.)

7/27/2010 12:12:20 PM P:\P-05\1719\DCN\Sheets\US 67 Final Plans\0310022-64815-051-Soil-Log-1.dgn

DESIGNED	
CHECKED	
DRAWN	SV
CHECKED	SPK

SOIL BORING LOG B-1c
STRUCTURE NO. 081-0022 (E.B.)
STRUCTURE NO. 081-0023 (W.B.)

SHEET NO. 51 54 SHEETS	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	280	81-1(HB-2)R	ROCK ISLAND	503	333
				CONTRACT NO. 64815	
FED. ROAD DIST. NO. - ILLINOIS FED. AID PROJECT					

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION



Illinois Department
of Transportation
Division of Highways
IDOT

SOIL BORING LOG

Page 1 of 1

Date 2/27/06

ROUTE FAI 280 DESCRIPTION P92-045-02 I-280 over US 67, .75 m. S. of Rock River LOGGED BY W. Garza
SECTION 81-1VB & 81-1-HB-1 & 2 LOCATION Blackhawk Twp. - 23 SE. SEC. , TWP. 17N. RNG. 2W
COUNTY Rock Island DRILLING METHOD Hollow Stem Auger HAMMER TYPE B-53 Diedrich Automatic

STRUCT. NO.	DEPTH	BLOWS	UCS	MOIST	Surface Water Elev.	Stream Bed Elev.	Groundwater Elev.:
Station	(ft)	(/6")	(tsf)	(%)	ft	ft	First Encounter
BORING NO. <u>B-2c</u>							554.6 ft
Station <u>255+20</u>							Upon Completion
Offset <u>66.00ft Lt CL</u>							After Hrs.
Ground Surface Elev. <u>567.1</u> ft							
MEDIUM reddish brown SANDY LOAM			0.5 P	20			
	564.60	2					
MEDIUM dark gray SILTY LOAM		2	0.8 P	25			
	563.10	3					
MEDIUM dark gray SILTY LOAM with SAND lens		2	0.6 P	24			
	560.60	2					
MEDIUM dark gray SANDY LOAM		2	0.5 P	21			
	558.10	1					
MEDIUM gray SILTY LOAM		2	0.6 B	26			
	555.10	2					
LOOSE gray LIMESTONE with SAND & GRAVEL		59					
	553.10	2					
		4					
VERY DENSE gray LIMESTONE		33					
	551.10	100/3.5"					
Borehole continued with rock coring.							

The Unconfined Compressive Strength (UCS) Failure Mode is indicated by (B-Bulge, S-Shear, P-Penetrometer)
The SPT (N value) is the sum of the last two blow values in each sampling zone (AASHTO T206)
BBS, from 137 (Rev. 8-99)



Illinois Department
of Transportation
Division of Highways
IDOT

ROCK CORE LOG

Page 1 of 1

Date 2/27/06

ROUTE FAI 280 DESCRIPTION P92-045-02 I-280 over US 67, .75 m. S. of Rock River LOGGED BY W. Garza
SECTION 81-1VB & 81-1-HB-1 & 2 LOCATION Blackhawk Twp. - 23 SE. SEC. , TWP. 17N. RNG. 2W
COUNTY Rock Island CORING METHOD

STRUCT. NO.	CORING BARREL TYPE & SIZE	DEPTH	CORE	RECOVERY	R.Q.D.	CORE TIME	STRENGTH
Station	Core Diameter	(ft)	(#)	(%)	(%)	(min/ft)	(tsf)
BORING NO. <u>B-2c</u>	1.5 in						
Station <u>255+20</u>	Top of Rock Elev. <u>552.60</u> ft						
Offset <u>66.00ft Lt CL</u>	Begin Core Elev. <u>551.10</u> ft						
Ground Surface Elev. <u>567.1</u> ft							
Dolomite: buff gray-white, dense and highly fractured throughout, ranging from shard size fragments to less than 3 inch lengths.		1	75	0	6.6		
As above		2	100	0	3.4		
As above		3	100	0	4.6		
End of Boring							

Color pictures of the cores
Cores will be stored for examination until
The "Strength" column represents the uniaxial compressive strength of the core sample (ASTM D-2938)
BBS, form 138 (Rev. 8-99)

SOIL BORING LOG B-2c
STRUCTURE NO. 081-0022 (E.B.)
STRUCTURE NO. 081-0023 (W.B.)



INFRASTRUCTURE
ENGINEERING | INCORPORATED
33 West Monroe | Suite 1540 | Chicago, IL 60603
P 312.425.9560 | F 312.425.9564 | www.infrastructure-eng.com

SHEET NO. 52	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
54 SHEETS	280	81-1(HB-2)R	ROCK ISLAND	503	334
					CONTRACT NO. 64815
					FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT

DESIGNED	
CHECKED	
DRAWN	SV
CHECKED	SPK

1719
7/22/2010
12:25:58 PM
3-2-05\719\DC\Sheets\US 67 Final Plans\0810022-64815-052-Soil Log 2.dgn

SOIL BORING LOG

Date 2/23/06

COUNTY Rock Island DRILLING METHOD Hollow Stem Auger HAMMER TYPE B-53 Diedrich Automatic

BORING NO. B-3c
Station 254+00
Offset ft CL E. Abutment
Ground Surface Elev. 585.0

REVISED
9-20-07 *EEC*

Revised BORING Station
to 256+00

EBS, from 137 (Rev. 8-99)

ROCK CORE LOG

Date 2/23/06

COUNTY	Rock Island	CORING METHOD	R	CORE	S
--------	-------------	---------------	---	------	---

CORING BARREL TYPE & SIZE

BORING NO. B-3c
Station 254 + 00
Offset ft. CLE. Abutment
Ground Surface Elev. 585.0

STRUCT. NO. _____ Station _____		CORING BARREL TYPE & SIZE _____		D E P T H (ft)	C O R E (#)	C O V E R Y (%)	Q U A L I T Y (%)	T I M E (min/ft)	R E N G T H (tsf)
BORING NO. _____ Station _____ Offset _____ Ground Surface Elev. _____ ft	B-3c 256+00 ft C.L.E. Abutment 585.0	Core Diameter _____ in Top of Rock Elev. _____ ft Begin Core Elev. _____ ft	1.5 553.00 551.50						
Dolomite: buff-white, dense, first 24" severely fractured, some crystalline faces visible.				1	90	0	5.6		
As above: some laminating visible.				2	100	0	4.2		
As above: T.S.F.: 540.7 to 540.4 test segment cracked before reaching reasonable value.				3	100	27	3.6	377	
End of Boring									

REVISED
9-30-67 ELL

Revised BORING Station to 256+00

BBS, form 138 (Rev. 8-99)

33 West Monroe | Suite 1540 | Chicago, IL 60603
P 312.425.9560 | F 312.425.9564 | www.infrastructure-eng.com

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
280	81-1(HB-2)R	ROCK ISLAND	503	335
		CONTRACT NO. 64815		
FED. ROAD DIST. NO. - ILLINOIS		FED. AID PROJECT		

SOIL BORING LOG B-3c
STRUCTURE NO. 081-0022 (E.B.)
STRUCTURE NO. 081-0023 (W.B.)

2:\P-05\1719\DCN\Sheets\US 67 Final Plans\0810022-64815-053-Soil Log_3.dgn

1719_ 7/22/2010 12:13:25 PM

SOIL BORING LOG

Date 3/2/06

COUNTY Rock Island DRILLING METHOD Hollow Stem Auger HAMMER TYPE B-53 Diedrich Automatic

DEPTH	BLOWS	UCS	MOIST
(ft)	(/6")	(tsf)	(%)

Surface Water Elev. _____ ft
Stream Bed Elev. _____ ft

Groundwater Elev.:
First Encounter _____ ft
Upon Completion _____ ft
After _____ Hrs. _____ ft

D E P T H	B L O W S	U C S Qu	M O I S T
(ft)	((6"))	(tsf)	(%)

BORING NO. B-4c
Station 253+60
Offset ft CL
Ground Surface Elev. 583.5

Ground Surface Elev. 583.5 ft

(ft)	(1/6")	(tsf)	(%)
------	--------	-------	-----

After _____ Hrs. _____ ft

(ft)	(/6")	(tsf)	(%)
------	-------	-------	-----

1. The first step in the process is to identify the problem or issue that needs to be addressed. This involves gathering information and understanding the context of the problem.

The Unconfined Compressive Strength (UCS) Failure Mode is indicated by (B-Bulge, S-Shear, P-Penetrometer)
The SPT (N value) is the sum of the last two blow values in each sampling zone (AASHTO T206)

SHEET NO. 54	PAY. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	280	81-1(HB-2)R	ROCK ISLAND	503	336
	54 SHEETS			CONTRACT NO. 64815	
FED. ROAD DIST. NO. _ ILLINOIS FED. AID PROJECT					

Bench Mark: IDOT District Network Monument 65723070, 131.5 Feet South of I-280 Centerline at Sta. 283+31.91, Elev. 579.52.

Existing Structures: S.N. 081-0024 (W.B.) and S.N. 081-0025 (E.B.) built as F.A.I. Route 280, Section 81-1VB-1, at Station 264+83.02 in 1968. Deck wearing surface and expansion joints were replaced in 1989. Each superstructure consists of 4 span continuous, composite rolled steel beams with partial length flange cover plates. Each substructure consists of concrete abutments supported on piles and concrete hammerhead piers bearing on rock. The Westbound Structure is 269'-0" long back to back of abutments and the Eastbound Structure is 272'-11" long back to back of abutments. The deck of both structures is 36'-0" out to out. Traffic is to be routed to one side of the interstate roadway during construction of the structure on the other side.


No Salvage.

Note: All existing elevations shown on these drawings are 0.20 feet lower than the corresponding elevations shown on the original drawings.


STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

* See Sheet 3 for Existing and Proposed Horizontal Clearances.

** Minimum vertical clearance is located within 8'-0" of the centerline of track. The point of low vertical clearance is beneath the bottom flange splice plate.



SECTION A-A



PIER 3 LAYOUT

DESIGN SPECIFICATIONS
AASHTO 2002 Standard Specifications
for Highway Bridges

LOADING HS20-44 & ALT
Allow 25#/sq. ft. for future wearing surface.

DESIGN STRESSES

FIELD UNITS (New Construction)

f_c = 3,500 psi (Concrete)
 f_y = 60,000 psi (Reinforcement)
 f_y = 50,000 psi (Structural Steel
AASHTO M270 Grade 50)
 f_y = 36,000 psi (Structural Steel
AASHTO M270 Grade 36)

FIELD UNITS (Existing Construction)

f_c = 1,000 psi (Concrete)
 f_s = 20,000 psi (Reinforcement)
 f_s = 20,000 psi (Structural Steel)

SEISMIC DATA

Seismic Performance Category (SPC) = A
Bedrock Acceleration Coefficient (A) = 0.034
Site Coefficient (S) = 1.0



APPROVED
FOR STRUCTURAL ADEQUACY ONLY

Ralph E. Anderson (Seal)
ENGINEER OF BRIDGES AND STRUCTURES

Steven P. Karlowski
EXP. 11/30/2010
DATE: 7/23/2010

STATION 264+81.03
RE-BUILT BY
STATE OF ILLINOIS
F.A.I. RT. 280 SEC. 81-1VB-1/R
LOADING HS20 & ALT.
STR. NO. 081-0024

WESTBOUND LANES

NAME PLATE


See Std. 515001
Existing Name Plate shall be cleaned and relocated next to new Name Plate. Cost included with Name Plates.

STATION 264+81.03
RE-BUILT BY
STATE OF ILLINOIS
F.A.I. RT. 280 SEC. 81-1VB-1/R
LOADING HS20 & ALT.
STR. NO. 081-0025

EASTBOUND LANES

NAME PLATE

See Std. 515001
Existing Name Plate shall be cleaned and relocated next to new Name Plate. Cost included with Name Plates.



LOCATION SKETCH

GENERAL PLAN & ELEVATION

I-280 OVER IOWA INTERSTATE RAILROAD


F.A.I. RTE. 280 - SEC. 81-1VB-1/R

ROCK ISLAND COUNTY

STATION 264+81.03

STRUCTURE NO. 081-0024 (W.B.)

STRUCTURE NO. 081-0025 (E.B.)



ELEVATION

PLAN

Note: No deck drains will be permitted in the span over tracks or within 10' of cross arms of a rail road pole line.

LEGEND

◆ - Soil Boring Location

DESIGNED	
CHECKED	
DRAWN	ASJ
CHECKED	SPK



INFRASTRUCTURE
ENGINEERING INCORPORATED

33 West Monroe | Suite 1540 | Chicago, IL 60603
P 312.425.9560 | F 312.425.9564 | www.infrastructure-eng.com

SHEET NO. 1	F.A.I. RTE. 280	SECTION 81-1(VB-1)R	COUNTY ROCK ISLAND	TOTAL SHEETS 503	SHEET NO. 337
77 SHEETS				CONTRACT NO. 64815	
	FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT		

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

GENERAL NOTES

Fasteners shall be AASHTO M164 Type 1, mechanically galvanized bolts. Bolts $\frac{7}{8}$ in. ϕ , holes $\frac{15}{16}$ in. ϕ , unless otherwise noted.

Calculated weight of Structural Steel = 7,620 pounds (AASHTO M270 Grade 36)
84,520 pounds (AASHTO M270 Grade 50)

No field welding is permitted except as specified in the contract documents.

The Contractor shall test the existing welds by non-destructive methods within 2 ft. of the end of the existing cover plates for cracks after removal of the existing concrete deck. Dye penetrant (PT), magnetic particle (MT), or other approved testing method shall be performed by qualified personnel approved by the Engineer. If cracks are found, report them to the Bureau of Bridges and Structures for disposition. The cost of testing is included in Removal of Existing Concrete Deck. The cost of crack repair, if necessary, will be paid for according to Article 109.04 of the Standard Specifications.

Reinforcement bars shall conform to the requirements of ASTM A 706 Gr 60. See Special Provisions.

Reinforcement bars designated (E) shall be epoxy coated.

Prior to pouring the new concrete deck, all heavy or loose rust, loose mill scale, and other loose or potentially detrimental foreign material shall be removed from the surfaces in contact with concrete. Tightly adhered paint may remain unless otherwise noted. Removal shall be accomplished by methods that will not damage the steel and the cost will be included in the pay item covering removal of the existing concrete.

As directed by the Engineer, existing construction accessories welded to the top flange of beams shall be removed. The weld areas shall be ground flush and inspected for cracks using magnetic particle testing (MT) or dye penetrant testing (PT) by qualified personnel approved by the Engineer.

Any cracks that cannot be removed by grinding $\frac{1}{4}$ inch deep shall be identified and reported to the Bureau of Bridges and Structures for further disposition. The cost of removing welded accessories, grinding and inspecting weld areas and grinding cracks will be paid for according to Article 109.04 of the Standard Specifications.

If the Contractor elects to use cantilever forming brackets on the exterior beams, the brackets shall be placed at the same locations as required for the hardwood blocks in Article 503.06(b) of the Standard Specifications. If additional cantilever forming brackets are required, hardwood blocking shall be wedged between the exterior and first interior beam at each of these additional bracket locations.

Plan dimensions and details relative to existing plans are subject to nominal construction variations. The Contractor shall field verify existing dimensions and details affecting new construction and make necessary approved adjustments prior to construction or ordering of materials. Such variations shall not be cause for additional compensation for a change in scope of the work, however, the Contractor will be paid for the quantity actually furnished at the unit price bid for the work.

Bearing seat surfaces shall be constructed or adjusted to the designated elevations within a tolerance of $\frac{1}{8}$ inch (0.01 ft.). Adjustment shall be made either by grinding the surface or by shimming the bearings.

Concrete Sealer shall be applied to all exposed surfaces of new concrete on the backwall, bridge seat and front face of the bridge seat of the abutments.

The existing structural steel coating contains lead. The Contractor shall take appropriate precautions to deal with the presence of lead on this project.

Cleaning and painting of the existing structural steel shall be as specified in the Special Provision for "Cleaning and Painting Existing Steel Structures". All existing steel shall be cleaned per Near White Blast Cleaning - SSPC-SP10. All existing steel shall be painted according to the requirements of Paint System 1-02/E/U. The color of the final finish coat for all interior steel surfaces shall be Gray, Munsell No. 5B 7/1. The color of the final finish coat for the exterior and bottom flange of the fascia beams shall be Blue, Munsell No. 10B 3/6.

A minimum of (2) air monitors will be required to monitor abrasive blasting operations at this site. See Special Provision for "Containment and Disposal of Lead Paint Cleaning Residues".

The Organic Zinc Rich Primer/Epoxy/Urethane paint system shall be used for shop and field painting of new structural steel except where otherwise noted. Two coats shall be applied in the shop and the finish coat applied in the field. Masked off connection surfaces, and field installed fasteners, shall be touched up and finish coated in the field. The color of the final finish coat for all interior steel surfaces shall be gray, Munsell No. 5B 7/1. The color of the final finish coat for the exterior and bottom flange of the fascia beams shall be Blue Munsell No. 10B 3/6. See Special Provision for "Cleaning and Painting New Metal Structures".

The embankment configuration shown shall be the minimum that must be placed and compacted prior to construction of the abutments.

A cantilevered sheet piling design does not appear feasible and additional members or other retention systems may be necessary. The Contractor shall submit a temporary soil retention system design including plan details and calculations for review and acceptance by the Engineer.

INDEX OF SHEETS

1	General Plan and Elevation	40	Abutment A Concrete Removal & Repairs
2	General Notes, Total Bill of Material	41	Abutment A Widening
3	Railroad Track Layout & Slope Wall	42	Abutment A Footing & North Wing Wall
4	Top of Slab Elevations	43	Abutment A South Wing Wall
5	W.B. Roadway - Top of Slab Elevations	44	Abutment B Concrete Removal & Repairs
6	W.B. Roadway - Top of Slab Elevations	45	Abutment B Widening
7	W.B. Roadway - Top of Slab Elevations	46	Abutment B Footing & North Wing Wall
8	E.B. Roadway - Top of Slab Elevations	47	Abutment B South Wing Wall
9	E.B. Roadway - Top of Slab Elevations	48	Abutment C Concrete Removal & Repairs
10	E.B. Roadway - Top of Slab Elevations	49	Abutment C Widening
11	Top of W.B. Roadway West Approach Slab Elevations	50	Abutment C Footing & South Wing Wall
12	Top of W.B. Roadway East Approach Slab Elevations	51	Abutment C North Wing Wall
13	Top of E.B. Roadway West Approach Slab Elevations	52	Abutment D Concrete Removal & Repairs
14	Top of E.B. Roadway East Approach Slab Elevations	53	Abutment D Widening
15	W.B. Roadway Deck	54	Abutment D Footing & South Wing Wall
16	E.B. Roadway Deck	55	Abutment D North Wing Wall
17	W.B. Roadway North Parapet	56	Abutment Drainage
18	W.B. Roadway South Parapet	57	Pier 1 Repairs
19	E.B. Roadway North Parapet	58	Pier 1 Widening
20	E.B. Roadway South Parapet	59	Pier 2 Repairs
21	Superstructure Details	60	Pier 2 Widening
22	Superstructure Details	61	Pier 3 Concrete Removal & Repairs
23	W.B. Roadway West Approach Slab Details	62	Pier 3 Widening
24	W.B. Roadway West Approach Slab Details	63	Pier 4 Repairs
25	E.B. Roadway West Approach Slab Details	64	Pier 4 Widening
26	E.B. Roadway West Approach Slab Details	65	Pier 5 Repairs
27	Bridge East Approach Slab Details	66	Pier 5 Widening
28	Bridge East Approach Slab Details	67	Pier 6 Repairs
29	Preformed Joint Strip Seal	68	Pier 6 Widening
30	Drainage Scupper, DS-II	69	Temporary Soil Retention System
31	Framing Plan	70	HP Piles Details
32	Steel Beam 1A Details	71	Bar Splicer Assembly and Mechanical Splicer Details
33	Steel Beam 13 Details	72	Concrete Parapet Slipforming Option
34	Existing Steel Beams 1-6 Details	73	Soil Boring Log B-1a
35	Existing Steel Beams 7-12 Details	74	Soil Boring Log B-2a
36	Existing Beams Design Data Tables	75	Soil Boring Log B-3a
37	Diaphragms	76	Soil Boring Log B-4a
38	Bearing Details - Abutments	77	Soil Boring Log B-5a
39	Bearing Details - Piers		

TOTAL BILL OF MATERIAL

ITEM	UNIT	SUPER	SUB	TOTAL
Porous Granular Embankment, Special	Cu. Yd.		389	389
Concrete Removal	Cu. Yd.		41.5	41.5
Slope Wall Removal	Sq. Yd.		2,080	2,080
Protective Shield	Sq. Yd.	606		606
Structure Excavation	Cu. Yd.		897	897
Floor Drains	Each	12		12
Concrete Structures	Cu. Yd.		411.8	411.8
Concrete Superstructure	Cu. Yd.	1,079.8		1,079.8
Bridge Deck Grooving	Sq. Yd.	2,776		2,776
Concrete Encasement	Cu. Yd.		2.4	2.4
* Protective Coat	Sq. Yd.	3,538		3,538
Stud Shear Connectors	Each	13,341		13,341
Cleaning and Painting Steel Bridge No. 2	L. Sum	1		1
Containment and Disposal of Lead Paint Cleaning Residues No. 2	L. Sum	1		1
Reinforcement Bars	Pound		810	810
Reinforcement Bars, Epoxy Coated	Pound	235,280	47,840	283,120
Bar Splicers	Each		183	183
Slope Wall 4 Inch	Sq. Yd.		182	182
Bituminous Coated Aggregate				
Slopedwall 6"	Sq. Yd.		2,120	2,120
Furnishing Steel Piles HP8x36	Foot		396	396
Driving Piles	Foot		396	396
Pile Shoes	Each		12	12
Name Plates	Each	2		2
Drilled Shaft in Soil	Cu. Yd.		7.9	7.9
Drilled Shaft in Rock	Cu. Yd.		3.5	3.5
Preformed Joint Strip Seal	Foot	188		188
Elastomeric Bearing Assembly, Type II	Each	4		4
Anchor Bolts, $\frac{5}{8}$ "	Each	8		8
Anchor Bolts, 1"	Each	8		8
Anchor Bolts, 1 $\frac{1}{2}$ "	Each	4		4
Concrete Sealer	Sq. Ft.		391	391
Epoxy Crack Injection	Foot		112	112
Geocomposite Wall Drain	Sq. Yd.		184	184
Pipe Underdrains for Structures 4"	Foot		179	179
Drainage Scuppers, DS-II	Each	4		4
Temporary Soil Retention System	Sq. Ft.		206	206
Structural Repair of Concrete (Depth Equal to or Less than 5 Inches)	Sq. Ft.		110	110
Removal of Existing Concrete Deck, No. 2	Each	2		2
Furnishing and Erecting Structural Steel Bridge No. 4	L. Sum	1		1


* Quantity is for deck surface and inside face and top of parapets.

GENERAL NOTES AND TOTAL BILL OF MATERIAL
STRUCTURE NO. 081-0024 (W.B.)
STRUCTURE NO. 081-0025 (E.B.)

DESIGNED	
CHECKED	
DRAWN	ASJ
CHECKED	SPK

SHEET NO. 2 77 SHEETS	F.A.I. RTE. 280	SECTION 81-1(VB-1)R	COUNTY ROCK ISLAND	TOTAL SHEETS 503	SHEET NO. 338
	CONTRACT NO. 64815				
	FED. ROAD DIST. NO. - ILLINOIS FED. AID PROJECT				


STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION



* Skew angle is measured at a line tangent to @ Track 1 curve at Sta. 4465+40.66.
** Existing and Proposed

TRACK CURVE DATA

	@ Track 1				@ Track 1A	
Curve	RRI-1	RRI-2	RRI-3	RRI-4	RRIA-1	RRIA-2
P.I. Sta.	4464+05.71	4465+04.05	4465+74.94	4467+09.73	1000+35.79	1001+01.31
Δ	28°35'32" (Rt)	3°45'23" (Rt)	1°8'43" (Lt)	24°29'14" (Lt)	4°32'26" (Rt)	2°15'38" (Lt)
D	20°39'37"	6°08'17"	1°25'15"	13°09'36"	6°20'51"	3°47'47"
T	70.67'	30.61'	40.31'	94.48'	35.79'	29.77'
L	138.39'	61.20'	80.62'	186.07'	71.53'	59.54'
R'	277.32'	933.43'	4,032.61'	435.38'	902.67'	1,509.19'
E	8.86'	0.50'	0.20'	10.13'	0.71'	0.29'
P.C. Sta.	4463+35.05	4464+73.44	4465+34.63	4466+15.25	1000+00.00	1000+71.53
P.T. Sta.	4464+73.44	4465+34.63	4466+15.25	4468+01.32	1001+71.53	1001+31.08




SECTION THRU SLOPE WALL


All Rubbish and Loose Earth in the Slopes Shall be Removed and any Eroded Portion of the Slopes Shall be Filled and Compacted with Suitable Materials to the Lines and Grades as Shown on the Plans and/or Directed by the Engineer. Cost included with Bituminous Coated Aggregate Slope Wall (6").

Slope Wall (4") shall be reinforced with welded wire fabric, 6" x 6" - W4.0 x W4.0, weighing 58 lbs. per 100 sq. ft.


RAILROAD TRACKS LAYOUT
(Beneath Structures)



PROFILE GRADE
TRACK 1A
(Along Top of East Rail of Track)



PROFILE GRADE
TRACK 1
(Along Top of West Rail of Track)



DESIGNED	
CHECKED	
DRAWN	ASJ
CHECKED	SPK


INFRASTRUCTURE ENGINEERING INCORPORATED
33 West Monroe | Suite 1540 | Chicago, IL 60603
P 312.425.9560 | F 312.425.9564 | www.infrastructure-eng.com

SHEET NO. 3	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	280	81-1(VB-1)R	ROCK ISLAND	503	339
77 SHEETS	SN 081-0024 (WB), 0025 (EB)		CONTRACT NO. 64815		
	FED. ROAD DIST. NO. _ ILLINOIS FED. AID PROJECT				

RAILROAD TRACK LAYOUT & SLOPE WALL
STRUCTURE NO. 081-0024 (W.B.)
STRUCTURE NO. 081-0025 (E.B.)

1719
7/22/2018
11:48:03 AM
P:\P-25\1719\DEN\Sheets\Iowa Interstate RR Final Plans\081-0024-64815-203-RR-Layout.dgn

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION



**W.B. ROADWAY VARIABLE
DIMENSION TABLE**

Beam	A	B
1A	13'-10 1/4"	8'-4 3/4"
1	13'-0"	9'-3"
2	13'-0"	9'-3"
3	13'-0"	9'-3"
4	13'-0"	9'-3"
5	13'-0"	9'-3"
6	13'-0"	9'-3"

**E.B. ROADWAY VARIABLE
DIMENSION TABLE**

Beam	C	D	E
7	12'-11"	0'-0"	0'-0"
8	10'-0"	5'-1 1/4"	0'-0"
9	10'-0"	7'-3 3/8"	0'-0"
10	10'-0"	8'-4 1/2"	0'-0"
11	10'-0"	9'-5 5/8"	0'-0"
12	10'-0"	11'-7 3/4"	0'-0"
13	10'-0"	13'-10"	5'-10 1/2"

PLAN

* @ E.B. Roadway & P.G.L.




**INFRASTRUCTURE
ENGINEERING** | INCORPORATED
33 West Monroe | Suite 1540 | Chicago, IL 60603
P 312.425.9560 | F 312.425.9564 | www.infrastructure-eng.com

SHEET NO. 4
77 SHEETS

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
280	81-1(VB-1)R	ROCK ISLAND	503	340
CONTRACT NO. 64815				
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				


**TOP OF SLAB ELEVATIONS
STRUCTURE NO. 081-0024 (W.B.)
STRUCTURE NO. 081-0025 (E.B.)**

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION



DEAD LOAD DEFLECTION DIAGRAM

Note:
(Includes weight of concrete only.)
The above deflections are not to be used in the field if the engineer is working from the grade elevations adjusted for dead load deflections as shown below and on Sheets 6-10.



To determine "f": After all structural steel has been erected, elevations of the top flanges of the beams shall be taken at intervals shown on Sheet 4. These elevations subtracted from the "Theoretical Grade Elevations Adjusted for Dead Load Deflection" shown below and on Sheets 6-10, minus slab thickness, equals the fillet heights "f" above top flange of beams.

FILLET HEIGHTS

BEAM 1A

Location	Station	Offset	Theoretical Grade Elevations	Theoretical Grade Elevations Adjusted For Dead Load Deflection
Bk. Abut. A	263+10.42	-21.96	591.86	591.86
@ Brg. Abut. A	263+12.67	-21.96	591.86	591.86
A	263+22.67	-21.96	591.85	591.86
B	263+32.67	-21.96	591.84	591.86
C	263+42.67	-21.96	591.82	591.85
D	263+52.67	-21.96	591.81	591.83
E	263+62.67	-21.96	591.79	591.80
@ Pier 1	263+71.92	-21.96	591.78	591.78
F	263+81.92	-21.96	591.76	591.76
G	263+91.92	-21.96	591.73	591.75
H	264+01.92	-21.96	591.71	591.74
I	264+11.92	-21.96	591.68	591.71
J	264+21.92	-21.96	591.65	591.68
K	264+31.92	-21.96	591.62	591.63
@ Pier 2	264+44.92	-21.96	591.58	591.58
L	264+54.92	-21.96	591.55	591.56
M	264+64.92	-21.96	591.51	591.53
N	264+74.92	-21.96	591.47	591.51
O	264+84.92	-21.96	591.43	591.47
P	264+94.92	-21.96	591.39	591.42
Q	265+04.92	-21.96	591.35	591.36
@ Pier 3	265+18.78	-21.96	591.28	591.28
R	265+28.78	-21.96	591.23	591.24
S	265+38.78	-21.96	591.18	591.20
T	265+48.78	-21.96	591.13	591.15
U	265+58.78	-21.96	591.07	591.10
V	265+68.78	-21.96	591.02	591.03
@ Brg. Abut. B	265+77.17	-21.96	590.97	590.97
Bk. Abut. B	265+79.42	-21.96	590.95	590.95

BEAM 1

Location	Station	Offset	Theoretical Grade Elevations	Theoretical Grade Elevations Adjusted For Dead Load Deflection
Bk. Abut. A	263+13.84	-16.04	591.98	591.98
@ Brg. Abut. A	263+16.09	-16.04	591.98	591.98
A	263+26.09	-16.04	591.97	591.99
B	263+36.09	-16.04	591.96	591.99
C	263+46.09	-16.04	591.94	591.98
D	263+56.09	-16.04	591.93	591.95
E	263+66.09	-16.04	591.91	591.92
@ Pier 1	263+75.34	-16.04	591.89	591.89
F	263+85.34	-16.04	591.87	591.88
G	263+95.34	-16.04	591.85	591.87
H	264+05.34	-16.04	591.82	591.86
I	264+15.34	-16.04	591.80	591.84
J	264+25.34	-16.04	591.77	591.80
K	264+35.34	-16.04	591.74	591.75
@ Pier 2	264+48.34	-16.04	591.69	591.69
L	264+58.34	-16.04	591.66	591.67
M	264+68.34	-16.04	591.62	591.65
N	264+78.34	-16.04	591.58	591.62
O	264+88.34	-16.04	591.54	591.58
P	264+98.34	-16.04	591.50	591.53
Q	265+08.34	-16.04	591.45	591.47
@ Pier 3	265+21.34	16.04	591.39	591.39
R	265+31.34	-16.04	591.34	591.35
S	265+41.34	-16.04	591.29	591.32
T	265+51.34	-16.04	591.24	591.27
U	265+61.34	-16.04	591.18	591.22
V	265+71.34	-16.04	591.13	591.15
@ Brg. Abut. B	265+80.59	-16.04	591.07	591.07
Bk. Abut. B	265+82.84	-16.04	591.06	591.06

BEAM 2

Location	Station	Offset	Theoretical Grade Elevations	Theoretical Grade Elevations Adjusted For Dead Load Deflection
Bk. Abut. A	263+17.54	-9.63	592.10	592.10
@ Brg. Abut. A	263+19.79	-9.63	592.09	592.09
A	263+29.79	-9.63	592.08	592.11
B	263+39.79	-9.63	592.07	592.11
C	263+49.79	-9.63	592.06	592.09
D	263+59.79	-9.63	592.04	592.07
E	263+69.79	-9.63	592.02	592.03
@ Pier 1	263+79.04	-9.63	592.01	592.01
F	263+89.04	-9.63	591.98	591.99
G	263+99.04	-9.63	591.96	591.99
H	264+09.04	-9.63	591.93	591.97
I	264+19.04	-9.63	591.91	591.95
J	264+29.04	-9.63	591.88	591.91
K	264+39.04	-9.63	591.85	591.86
@ Pier 2	264+52.04	-9.63	591.80	591.80
L	264+62.04	-9.63	591.77	591.77
M	264+72.04	-9.63	591.73	591.75
N	264+82.04	-9.63	591.69	591.73
O	264+92.04	-9.63	591.65	591.69
P	265+02.04	-9.63	591.60	591.63
Q	265+12.04	-9.63	591.56	591.57
@ Pier 3	265+25.04	-9.63	591.49	591.49
R	265+35.04	-9.63	591.44	591.45
S	265+45.04	-9.63	591.39	591.42
T	265+55.04	-9.63	591.34	591.37
U	265+65.04	-9.63	591.28	591.32
V	265+75.04	-9.63	591.22	591.25
@ Brg. Abut. B	265+84.29	-9.63	591.17	591.17
Bk. Abut. B	265+86.54	-9.63	591.16	591.16

W.B. ROADWAY - TOP OF SLAB ELEVATIONS

STRUCTURE NO. 081-0024 (W.B.)

STRUCTURE NO. 081-0025 (E.B.)

DESIGNED LAN
CHECKED LC
DRAWN LAN
CHECKED LC

Note:
Offset is measured from @ W.B. Roadway & P.G.L.
Negative number indicates distance left of @. Positive number indicates distance right of @.



**INFRASTRUCTURE
ENGINEERING** | INCORPORATED
33 West Monroe | Suite 1540 | Chicago, IL 60603
P 312.425.9560 | F 312.425.9564 | www.infrastructure-eng.com

SHEET NO.	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
77 SHEETS	280	81-1(VB-1)R	ROCK ISLAND	503	341
CONTRACT NO. 64815					
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT					

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

BEAM 3

Location	Station	Offset	Theoretical Grade Elevations	Theoretical Grade Elevations Adjusted For Dead Load Deflection
Bk. Abut. A	263+21.25	-3.21	592.19	592.19
@ Brg. Abut. A	263+23.50	-3.21	592.19	592.19
A	263+33.50	-3.21	592.18	592.20
B	263+43.50	-3.21	592.17	592.20
C	263+53.50	-3.21	592.15	592.19
D	263+63.50	-3.21	592.14	592.16
E	263+73.50	-3.21	592.12	592.12
@ Pier 1	263+82.75	-3.21	592.10	592.10
F	263+92.75	-3.21	592.08	592.09
G	264+02.75	-3.21	592.05	592.08
H	264+12.75	-3.21	592.02	592.06
I	264+22.75	-3.21	592.00	592.04
J	264+32.75	-3.21	591.97	592.00
K	264+42.75	-3.21	591.93	591.95
@ Pier 2	264+55.75	-3.21	591.89	591.89
L	264+65.75	-3.21	591.85	591.86
M	264+75.75	-3.21	591.81	591.84
N	264+85.75	-3.21	591.77	591.81
O	264+95.75	-3.21	591.73	591.77
P	265+05.75	-3.21	591.69	591.72
Q	265+15.75	-3.21	591.64	591.65
@ Pier 3	265+28.75	-3.21	591.58	591.58
R	265+38.75	-3.21	591.53	591.53
S	265+48.75	-3.21	591.47	591.50
T	265+58.75	-3.21	591.42	591.45
U	265+68.75	-3.21	591.36	591.40
V	265+78.75	-3.21	591.30	591.32
@ Brg. Abut. B	265+88.00	-3.21	591.25	591.25
Bk. Abut. B	265+90.25	-3.21	591.23	591.23

@ W.B. ROADWAY & P.G.L.

Location	Station	Offset	Theoretical Grade Elevations	Theoretical Grade Elevations Adjusted For Dead Load Deflection
Bk. Abut. A	263+23.10	0.00	592.24	592.24
@ Brg. Abut. A	263+25.35	0.00	592.24	592.24
A	263+35.35	0.00	592.23	592.25
B	263+45.35	0.00	592.22	592.25
C	263+55.35	0.00	592.20	592.24
D	263+65.35	0.00	592.18	592.21
E	263+75.35	0.00	592.16	592.17
@ Pier 1	263+84.60	0.00	592.14	592.14
F	263+94.60	0.00	592.12	592.13
G	264+04.60	0.00	592.10	592.12
H	264+14.60	0.00	592.07	592.11
I	264+24.60	0.00	592.04	592.08
J	264+34.60	0.00	592.01	592.04
K	264+44.60	0.00	591.98	591.99
@ Pier 2	264+57.60	0.00	591.93	591.93
L	264+67.60	0.00	591.90	591.90
M	264+77.60	0.00	591.86	591.88
N	264+87.60	0.00	591.82	591.85
O	264+97.60	0.00	591.77	591.81
P	265+07.60	0.00	591.73	591.76
Q	265+17.60	0.00	591.68	591.70
@ Pier 3	265+30.60	0.00	591.62	591.62
R	265+40.60	0.00	591.57	591.57
S	265+50.60	0.00	591.51	591.54
T	265+60.60	0.00	591.46	591.49
U	265+70.60	0.00	591.40	591.44
V	265+80.60	0.00	591.34	591.36
@ Brg. Abut. B	265+89.85	0.00	591.29	591.29
Bk. Abut. B	265+92.10	0.00	591.27	591.27

BEAM 4

Location	Station	Offset	Theoretical Grade Elevations	Theoretical Grade Elevations Adjusted For Dead Load Deflection
Bk. Abut. A	263+24.95	3.21	592.19	592.19
@ Brg. Abut. A	263+27.20	3.21	592.19	592.19
A	263+37.20	3.21	592.18	592.20
B	263+47.20	3.21	592.16	592.20
C	263+57.20	3.21	592.15	592.18
D	263+67.20	3.21	592.13	592.15
E	263+77.20	3.21	592.11	592.12
@ Pier 1	263+86.45	3.21	592.09	592.09
F	263+96.45	3.21	592.07	592.08
G	264+06.45	3.21	592.04	592.07
H	264+16.45	3.21	592.01	592.05
I	264+26.45	3.21	591.99	592.03
J	264+36.45	3.21	591.95	591.98
K	264+46.45	3.21	591.92	591.94
@ Pier 2	264+59.45	3.21	591.88	591.88
L	264+69.45	3.21	591.84	591.85
M	264+79.45	3.21	591.80	591.82
N	264+89.45	3.21	591.76	591.80
O	264+99.45	3.21	591.71	591.76
P	265+09.45	3.21	591.67	591.70
Q	265+19.45	3.21	591.62	591.64
@ Pier 3	265+32.45	3.21	591.56	591.56
R	265+42.45	3.21	591.51	591.52
S	265+52.45	3.21	591.45	591.48
T	265+62.45	3.21	591.40	591.43
U	265+72.45	3.21	591.34	591.38
V	265+82.45	3.21	591.28	591.30
@ Brg. Abut. B	265+91.70	3.21	591.22	591.22
Bk. Abut. B	265+93.95	3.21	591.21	591.21

W.B. ROADWAY - TOP OF SLAB ELEVATIONS

STRUCTURE NO. 081-0024 (W.B.)

STRUCTURE NO. 081-0025 (E.B.)

DESIGNED	LAN
CHECKED	LC
DRAWN	LAN
CHECKED	LC

Note:
Offset is measured from @ W.B. Roadway & P.G.L.
Negative number indicates distance left of @. Positive
number indicates distance right of @.



INFRASTRUCTURE
ENGINEERING | INCORPORATED

33 West Monroe | Suite 1540 | Chicago, IL 60603
P 312.425.9560 | F 312.425.9564 | www.infrastructure-eng.com

SHEET NO. 6	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	280	81-1(VB-1)R	ROCK ISLAND	503	342
CONTRACT NO. 64815					
FED. ROAD DIST. NO. _ ILLINOIS FED. AID PROJECT					

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

BEAM 5

Location	Station	Offset	Theoretical Grade Elevations	Theoretical Grade Elevations Adjusted For Dead Load Deflection
Bk. Abut. A	263+28.66	9.63	592.09	592.09
☉ Brg. Abut. A	263+30.91	9.63	592.08	592.08
A	263+40.91	9.63	592.07	592.09
B	263+50.91	9.63	592.06	592.09
C	263+60.91	9.63	592.04	592.08
D	263+70.91	9.63	592.02	592.05
E	263+80.91	9.63	592.00	592.01
☉ Pier 1	263+90.16	9.63	591.98	591.98
F	264+00.16	9.63	591.96	591.97
G	264+10.16	9.63	591.93	591.96
H	264+20.16	9.63	591.90	591.94
I	264+30.16	9.63	591.87	591.91
J	264+40.16	9.63	591.84	591.87
K	264+50.16	9.63	591.81	591.82
☉ Pier 2	264+63.16	9.63	591.76	591.76
L	264+73.16	9.63	591.72	591.73
M	264+83.16	9.63	591.68	591.71
N	264+93.16	9.63	591.64	591.68
O	265+03.16	9.63	591.60	591.64
P	265+13.16	9.63	591.55	591.58
Q	265+23.16	9.63	591.50	591.52
☉ Pier 3	265+36.16	9.63	591.44	591.44
R	265+46.16	9.63	591.39	591.40
S	265+56.16	9.63	591.33	591.36
T	265+66.16	9.63	591.28	591.31
U	265+76.16	9.63	591.22	591.25
V	265+86.16	9.63	591.16	591.18
☉ Brg. Abut. B	265+95.41	9.63	591.10	591.10
Bk. Abut. B	265+97.66	9.63	591.09	591.09

BEAM 6

Location	Station	Offset	Theoretical Grade Elevations	Theoretical Grade Elevations Adjusted For Dead Load Deflection
Bk. Abut. A	263+32.36	16.04	591.96	591.96
☉ Brg. Abut. A	263+34.61	16.04	591.96	591.96
A	263+44.61	16.04	591.94	591.97
B	263+54.61	16.04	591.93	591.96
C	263+64.61	16.04	591.91	591.95
D	263+74.61	16.04	591.89	591.92
E	263+84.61	16.04	591.87	591.88
☉ Pier 1	263+93.86	16.04	591.85	591.85
F	264+03.86	16.04	591.83	591.84
G	264+13.86	16.04	591.80	591.83
H	264+23.86	16.04	591.77	591.81
I	264+33.86	16.04	591.74	591.78
J	264+43.86	16.04	591.71	591.74
K	264+53.86	16.04	591.67	591.69
☉ Pier 2	264+66.86	16.04	591.63	591.63
L	264+76.86	16.04	591.59	591.60
M	264+86.86	16.04	591.55	591.57
N	264+96.86	16.04	591.50	591.54
O	265+06.86	16.04	591.46	591.50
P	265+16.86	16.04	591.41	591.44
Q	265+26.86	16.04	591.36	591.38
☉ Pier 3	265+39.86	16.04	591.30	591.30
R	265+49.86	16.04	591.25	591.25
S	265+59.86	16.04	591.19	591.22
T	265+69.86	16.04	591.13	591.17
U	265+79.86	16.04	591.08	591.11
V	265+89.86	16.04	591.01	591.04
☉ Brg. Abut. B	265+99.11	16.04	590.96	590.96
Bk. Abut. B	266+01.36	16.04	590.94	590.94

W.B. ROADWAY - TOP OF SLAB ELEVATIONS
STRUCTURE NO. 081-0024 (W.B.)
STRUCTURE NO. 081-0025 (E.B.)

DESIGNED	LAN
CHECKED	LC
DRAWN	LAN
CHECKED	LC

Note:
Offset is measured from ☉ W.B. Roadway & P.G.L.
Negative number indicates distance left of ☉. Positive
number indicates distance right of ☉.



INFRASTRUCTURE
ENGINEERING | INCORPORATED
33 West Monroe | Suite 1540 | Chicago, IL 60603
P 312.425.9560 | F 312.425.9564 | www.infrastructure-eng.com

SHEET NO. 7 77 SHEETS	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	280	81-1(VB-1)R	ROCK ISLAND	503	343
	CONTRACT NO. 64815				
FED. ROAD DIST. NO. _ ILLINOIS FED. AID PROJECT					

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

BEAM 7

Location	Station	Offset	Theoretical Grade Elevations	Theoretical Grade Elevations Adjusted For Dead Load Deflection
Bk. Abut. C	263+64.39	-16.04	591.91	591.91
☉ Brg. Abut. C	263+66.31	-16.04	591.91	591.91
A	263+76.31	-16.04	591.89	591.91
B	263+86.31	-16.04	591.87	591.90
C	263+96.31	-16.04	591.85	591.87
D	264+06.31	-16.04	591.82	591.84
E	264+16.31	-16.04	591.79	591.80
☉ Pier 4	264+22.31	-16.04	591.78	591.78
F	264+32.31	-16.04	591.75	591.76
G	264+42.31	-16.04	591.71	591.74
H	264+52.31	-16.04	591.68	591.71
I	264+62.31	-16.04	591.64	591.68
J	264+72.31	-16.04	591.61	591.63
K	264+82.31	-16.04	591.57	591.57
☉ Pier 5	264+95.22	-16.04	591.51	591.51
N	265+05.22	-16.04	591.47	591.48
O	265+15.22	-16.04	591.42	591.46
P	265+25.22	-16.04	591.37	591.43
Q	265+35.22	-16.04	591.32	591.39
R	265+45.22	-16.04	591.27	591.33
S	265+55.22	-16.04	591.22	591.25
T	265+65.22	-16.04	591.16	591.17
☉ Pier 6	265+73.60	-16.04	591.11	591.11
U	265+83.60	-16.04	591.05	591.06
V	265+93.60	-16.04	590.99	591.00
W	266+03.60	-16.04	590.93	590.95
X	266+13.60	-16.04	590.86	590.88
Y	266+23.60	-16.04	590.79	590.80
☉ Brg. Abut. D	266+29.60	-16.04	590.75	590.75
Bk. Abut. D	266+31.85	-16.04	590.74	590.74

BEAM 8

Location	Station	Offset	Theoretical Grade Elevations	Theoretical Grade Elevations Adjusted For Dead Load Deflection
Bk. Abut. C	263+65.91	-9.63	592.03	592.03
☉ Brg. Abut. C	263+67.83	-9.63	592.03	592.03
A	263+77.83	-9.63	592.01	592.02
B	263+87.83	-9.63	591.99	592.01
C	263+97.83	-9.63	591.96	591.99
D	264+07.83	-9.63	591.94	591.95
E	264+17.83	-9.63	591.91	591.91
☉ Pier 4	264+23.83	-9.63	591.89	591.89
F	264+33.83	-9.63	591.86	591.87
G	264+43.83	-9.63	591.83	591.86
H	264+53.83	-9.63	591.80	591.84
I	264+63.83	-9.63	591.76	591.80
J	264+73.83	-9.63	591.72	591.75
K	264+83.83	-9.63	591.68	591.70
L	264+93.83	-9.63	591.64	591.64
☉ Pier 5	264+98.93	-9.63	591.62	591.62
N	265+08.93	-9.63	591.57	591.58
O	265+18.93	-9.63	591.52	591.56
P	265+28.93	-9.63	591.48	591.53
Q	265+38.93	-9.63	591.42	591.48
R	265+48.93	-9.63	591.37	591.43
S	265+58.93	-9.63	591.32	591.35
T	265+68.93	-9.63	591.26	591.27
☉ Pier 6	265+77.30	-9.63	591.21	591.21
U	265+87.30	-9.63	591.15	591.15
V	265+97.30	-9.63	591.09	591.10
W	266+07.30	-9.63	591.02	591.05
X	266+17.30	-9.63	590.96	590.98
Y	266+27.30	-9.63	590.89	590.90
☉ Brg. Abut. D	266+33.30	-9.63	590.85	590.85
Bk. Abut. D	266+35.55	-9.63	590.83	590.83

BEAM 9

Location	Station	Offset	Theoretical Grade Elevations	Theoretical Grade Elevations Adjusted For Dead Load Deflection
Bk. Abut. C	263+67.43	-3.21	592.13	592.13
☉ Brg. Abut. C	263+69.35	-3.21	592.13	592.13
A	263+79.35	-3.21	592.11	592.12
B	263+89.35	-3.21	592.08	592.11
C	263+99.35	-3.21	592.06	592.08
D	264+09.35	-3.21	592.03	592.04
E	264+19.35	-3.21	592.01	592.01
☉ Pier 4	264+25.35	-3.21	591.99	591.99
F	264+35.35	-3.21	591.96	591.97
G	264+45.35	-3.21	591.93	591.96
H	264+55.35	-3.21	591.89	591.94
I	264+65.35	-3.21	591.85	591.91
J	264+75.35	-3.21	591.82	591.86
K	264+85.35	-3.21	591.78	591.80
L	264+95.35	-3.21	591.73	591.74
☉ Pier 5	265+02.63	-3.21	591.70	591.70
N	265+12.63	-3.21	591.65	591.67
O	265+22.63	-3.21	591.61	591.64
P	265+32.63	-3.21	591.56	591.61
Q	265+42.63	-3.21	591.51	591.56
R	265+52.63	-3.21	591.45	591.50
S	265+62.63	-3.21	591.40	591.43
T	265+72.63	-3.21	591.34	591.35
☉ Pier 6	265+81.01	-3.21	591.29	591.29
U	265+91.01	-3.21	591.23	591.23
V	266+01.01	-3.21	591.17	591.18
W	266+11.01	-3.21	591.10	591.12
X	266+21.01	-3.21	591.03	591.05
Y	266+31.01	-3.21	590.97	590.97
☉ Brg. Abut. D	266+37.01	-3.21	590.92	590.92
Bk. Abut. D	266+39.26	-3.21	590.91	590.91

E.B. ROADWAY - TOP OF SLAB ELEVATIONS
STRUCTURE NO. 081-0024 (W.B.)
STRUCTURE NO. 081-0025 (E.B.)

DESIGNED LAN
CHECKED LC
DRAWN LAN
CHECKED LC

Note:
Offset is measured from ☉ E.B. Roadway & P.G.L.
Negative number indicates distance left of ☉. Positive
number indicates distance right of ☉.



INFRASTRUCTURE
ENGINEERING | INCORPORATED

33 West Monroe | Suite 1540 | Chicago, IL 60603
P 312.425.9560 | F 312.425.9564 | www.infrastructure-eng.com

SHEET NO. 8	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
77 SHEETS	280	81-1(VB-1)R	ROCK ISLAND	503	344
CONTRACT NO. 64815					
FED. ROAD DIST. NO. - ILLINOIS FED. AID PROJECT					

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

☉ E.B. ROADWAY & P.G.L.

Location	Station	Offset	Theoretical Grade Elevations	Theoretical Grade Elevations Adjusted For Dead Load Deflection
Bk. Abut. C	263+68.19	0.00	592.18	592.18
☉ Brg. Abut. C	263+70.11	0.00	592.17	592.17
A	263+80.11	0.00	592.15	592.17
B	263+90.11	0.00	592.13	592.15
C	264+00.11	0.00	592.11	592.13
D	264+10.11	0.00	592.08	592.09
E	264+20.11	0.00	592.05	592.05
☉ Pier 4	264+26.11	0.00	592.04	592.04
F	264+36.11	0.00	592.01	592.02
G	264+46.11	0.00	591.97	592.01
H	264+56.11	0.00	591.94	591.99
I	264+66.11	0.00	591.90	591.96
J	264+76.11	0.00	591.86	591.91
K	264+86.11	0.00	591.82	591.85
L	264+96.11	0.00	591.78	591.79
☉ Pier 5	265+04.49	0.00	591.74	591.74
N	265+14.49	0.00	591.70	591.71
O	265+24.49	0.00	591.65	591.68
P	265+34.49	0.00	591.60	591.65
Q	265+44.49	0.00	591.55	591.60
R	265+54.49	0.00	591.49	591.54
S	265+64.49	0.00	591.44	591.47
T	265+74.49	0.00	591.38	591.39
☉ Pier 6	265+82.86	0.00	591.33	591.33
U	265+92.86	0.00	591.27	591.27
V	266+02.86	0.00	591.20	591.22
W	266+12.86	0.00	591.14	591.16
X	266+22.86	0.00	591.07	591.09
Y	266+32.86	0.00	591.00	591.01
☉ Brg. Abut. D	266+38.86	0.00	590.96	590.96
Bk. Abut. D	266+41.11	0.00	590.94	590.94

BEAM 10

Location	Station	Offset	Theoretical Grade Elevations	Theoretical Grade Elevations Adjusted For Dead Load Deflection
Bk. Abut. C	263+68.95	3.21	592.13	592.13
☉ Brg. Abut. C	263+70.87	3.21	592.12	592.12
A	263+80.87	3.21	592.10	592.12
B	263+90.87	3.21	592.08	592.10
C	264+00.87	3.21	592.06	592.07
D	264+10.87	3.21	592.03	592.04
E	264+20.87	3.21	592.00	592.00
☉ Pier 4	264+26.87	3.21	591.98	591.98
F	264+36.87	3.21	591.95	591.97
G	264+46.87	3.21	591.92	591.96
H	264+56.87	3.21	591.89	591.94
I	264+66.87	3.21	591.85	591.91
J	264+76.87	3.21	591.81	591.86
K	264+86.87	3.21	591.77	591.80
L	264+96.87	3.21	591.73	591.74
☉ Pier 5	265+06.34	3.21	591.68	591.68
N	265+16.34	3.21	591.64	591.65
O	265+26.34	3.21	591.59	591.62
P	265+36.34	3.21	591.54	591.59
Q	265+46.34	3.21	591.49	591.54
R	265+56.34	3.21	591.43	591.48
S	265+66.34	3.21	591.38	591.41
T	265+76.34	3.21	591.32	591.33
☉ Pier 6	265+84.71	3.21	591.27	591.27
U	265+94.71	3.21	591.21	591.21
V	266+04.71	3.21	591.14	591.16
W	266+14.71	3.21	591.08	591.10
X	266+24.71	3.21	591.01	591.03
Y	266+34.71	3.21	590.94	590.95
☉ Brg. Abut. D	266+40.71	3.21	590.90	590.90
Bk. Abut. D	266+42.96	3.21	590.88	590.88

BEAM 11

Location	Station	Offset	Theoretical Grade Elevations	Theoretical Grade Elevations Adjusted For Dead Load Deflection
Bk. Abut. C	263+70.48	9.63	592.02	592.02
☉ Brg. Abut. C	263+72.39	9.63	592.02	592.02
A	263+82.39	9.63	592.00	592.01
B	263+92.39	9.63	591.98	591.99
C	264+02.39	9.63	591.95	591.97
D	264+12.39	9.63	591.93	591.93
E	264+22.39	9.63	591.90	591.90
☉ Pier 4	264+28.39	9.63	591.88	591.88
F	264+38.39	9.63	591.85	591.87
G	264+48.39	9.63	591.81	591.86
H	264+58.39	9.63	591.78	591.84
I	264+68.39	9.63	591.74	591.81
J	264+78.39	9.63	591.70	591.76
K	264+88.39	9.63	591.66	591.70
L	264+98.39	9.63	591.62	591.63
☉ Pier 5	265+10.04	9.63	591.57	591.57
N	265+20.04	9.63	591.52	591.53
O	265+30.04	9.63	591.47	591.49
P	265+40.04	9.63	591.42	591.46
Q	265+50.04	9.63	591.37	591.41
R	265+60.04	9.63	591.31	591.35
S	265+70.04	9.63	591.25	591.28
T	265+80.04	9.63	591.20	591.21
☉ Pier 6	265+88.42	9.63	591.14	591.14
U	265+98.42	9.63	591.08	591.09
V	266+08.42	9.63	591.02	591.03
W	266+18.42	9.63	590.95	590.97
X	266+28.42	9.63	590.88	590.90
Y	266+38.42	9.63	590.81	590.82
☉ Brg. Abut. D	266+44.42	9.63	590.77	590.77
Bk. Abut. D	266+46.67	9.63	590.75	590.75

E.B. ROADWAY - TOP OF SLAB ELEVATIONS
STRUCTURE NO. 081-0024 (W.B.)
STRUCTURE NO. 081-0025 (E.B.)

DESIGNED	LAN
CHECKED	LC
DRAWN	LAN
CHECKED	LC

Note:
Offset is measured from ☉ E.B. Roadway & P.G.L.
Negative number indicates distance left of ☉. Positive
number indicates distance right of ☉.



**INFRASTRUCTURE
ENGINEERING** | INCORPORATED

33 West Monroe | Suite 1540 | Chicago, IL 60603
P 312.425.9560 | F 312.425.9564 | www.infrastructure-eng.com

SHEET NO. 9	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	280	81-1(VB-1)R	ROCK ISLAND	503	345
CONTRACT NO. 64815					
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT					

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

BEAM 12

Location	Station	Offset	Theoretical Grade Elevations	Theoretical Grade Elevations Adjusted For Dead Load Deflection
Bk. Abut. C	263+72.00	16.04	591.90	591.90
@ Brg. Abut. C	263+73.91	16.04	591.89	591.89
A	263+83.91	16.04	591.87	591.89
B	263+93.91	16.04	591.85	591.87
C	264+03.91	16.04	591.83	591.84
D	264+13.91	16.04	591.80	591.80
E	264+23.91	16.04	591.77	591.77
@ Pier 4	264+29.91	16.04	591.75	591.75
F	264+39.91	16.04	591.72	591.74
G	264+49.91	16.04	591.69	591.73
H	264+59.91	16.04	591.65	591.72
I	264+69.91	16.04	591.62	591.69
J	264+79.91	16.04	591.58	591.64
K	264+89.91	16.04	591.53	591.58
L	264+99.91	16.04	591.49	591.51
@ Pier 5	265+13.75	16.04	591.43	591.43
N	265+23.75	16.04	591.38	591.39
O	265+33.75	16.04	591.33	591.35
P	265+43.75	16.04	591.28	591.32
Q	265+53.75	16.04	591.22	591.27
R	265+63.75	16.04	591.17	591.21
S	265+73.75	16.04	591.11	591.14
T	265+83.75	16.04	591.05	591.06
@ Pier 6	265+92.12	16.04	591.00	591.00
U	266+02.12	16.04	590.94	590.94
V	266+12.12	16.04	590.87	590.89
W	266+22.12	16.04	590.81	590.83
X	266+32.12	16.04	590.74	590.76
Y	266+42.12	16.04	590.67	590.67
@ Brg. Abut. D	266+48.12	16.04	590.62	590.62
Bk. Abut. D	266+50.37	16.04	590.61	590.61

BEAM 13

Location	Station	Offset	Theoretical Grade Elevations	Theoretical Grade Elevations Adjusted For Dead Load Deflection
Bk. Abut. C	263+73.40	21.96	591.77	591.77
@ Brg. Abut. C	263+75.32	21.96	591.77	591.77
A	263+85.32	21.96	591.75	591.76
B	263+95.32	21.96	591.72	591.74
C	264+05.32	21.96	591.70	591.71
D	264+15.32	21.96	591.67	591.67
E	264+25.32	21.96	591.64	591.64
@ Pier 4	264+31.32	21.96	591.63	591.63
F	264+41.32	21.96	591.59	591.62
G	264+51.32	21.96	591.56	591.61
H	264+61.32	21.96	591.52	591.60
I	264+71.32	21.96	591.49	591.57
J	264+81.32	21.96	591.45	591.53
K	264+91.32	21.96	591.41	591.47
L	265+01.32	21.96	591.36	591.40
M	265+11.32	21.96	591.32	591.33
@ Pier 5	265+17.16	21.96	591.29	591.29
N	265+27.16	21.96	591.24	591.24
O	265+37.16	21.96	591.19	591.21
P	265+47.16	21.96	591.14	591.17
Q	265+57.16	21.96	591.08	591.13
R	265+67.16	21.96	591.03	591.07
S	265+77.16	21.96	590.97	590.99
T	265+87.16	21.96	590.91	590.92
@ Pier 6	265+95.54	21.96	590.86	590.86
U	266+05.54	21.96	590.79	590.80
V	266+15.54	21.96	590.73	590.74
W	266+25.54	21.96	590.66	590.68
X	266+35.54	21.96	590.59	590.61
Y	266+45.54	21.96	590.52	590.53
@ Brg. Abut. D	266+51.54	21.96	590.47	590.47
Bk. Abut. D	266+53.79	21.96	590.46	590.46

E.B. ROADWAY - TOP OF SLAB ELEVATIONS
STRUCTURE NO. 081-0024 (W.B.)
STRUCTURE NO. 081-0025 (E.B.)

DESIGNED	LAN
CHECKED	LC
DRAWN	LAN
CHECKED	LC

Note:
Offset is measured from @ E.B. Roadway & P.G.L.
Negative number indicates distance left of @. Positive
number indicates distance right of @.



INFRASTRUCTURE
ENGINEERING | INCORPORATED
33 West Monroe | Suite 1540 | Chicago, IL 60603
P 312.425.9560 | F 312.425.9564 | www.infrastructure-eng.com

SHEET NO. 10 77 SHEETS	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	280	81-1(VB-1)R	ROCK ISLAND	503	346
CONTRACT NO. 64815					
FED. ROAD DIST. NO. - ILLINOIS FED. AID PROJECT					

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

NORTH EDGE OF SHOULDER

Location	Station	Offset	Theoretical Grade Elevations
W. End W. Appr. Pav't.	262+80.40	-22.00	591.87
A1	262+90.40	-22.00	591.87
A2	263+00.40	-22.00	591.86
E. End W. Appr. Pav't.	263+10.40	-22.00	591.86

NORTH EDGE OF PAVEMENT

Location	Station	Offset	Theoretical Grade Elevations
W. End W. Appr. Pav't.	262+86.17	-12.00	592.08
A1	262+96.17	-12.00	592.07
A2	263+06.17	-12.00	592.07
E. End W. Appr. Pav't.	263+16.17	-12.00	592.06

W.B. ROADWAY & PGL

Location	Station	Offset	Theoretical Grade Elevations
W. End W. Appr. Pav't.	262+93.10	0.00	592.26
A1	263+03.10	0.00	592.26
A2	263+13.10	0.00	592.25
E. End W. Appr. Pav't.	263+23.10	0.00	592.24


SOUTH EDGE OF PAVEMENT

Location	Station	Offset	Theoretical Grade Elevations
W. End W. Appr. Pav't.	263+00.03	12.00	592.07
A1	263+10.03	12.00	592.07
A2	263+20.03	12.00	592.06
E. End W. Appr. Pav't.	263+30.03	12.00	592.05

SOUTH EDGE OF SHOULDER

Location	Station	Offset	Theoretical Grade Elevations
W. End W. Appr. Pav't.	263+03.49	18.00	591.95
A1	263+13.49	18.00	591.94
A2	263+23.49	18.00	591.93
E. End W. Appr. Pav't.	263+33.49	18.00	591.92

TOP OF W.B. ROADWAY
WEST APPROACH SLAB ELEVATIONS
STRUCTURE NO. 081-0024 (W.B.)
STRUCTURE NO. 081-0025 (E.B.)



PLAN

DESIGNED	LAN
CHECKED	LC
DRAWN	LAN
CHECKED	LC



**INFRASTRUCTURE
ENGINEERING** | INCORPORATED
33 West Monroe | Suite 1540 | Chicago, IL 60603
P 312.425.9560 | F 312.425.9564 | www.infrastructure-eng.com

SHEET NO. 11 77 SHEETS	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	280	81-1(VB-1)R	ROCK ISLAND	503	347
	CONTRACT NO. 64815				
	FED. ROAD DIST. NO. _ ILLINOIS FED. AID PROJECT				

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

NORTH EDGE OF SHOULDER

Location	Station	Offset	Theoretical Grade Elevations
W. End E. Appr. Pav't.	265+79.40	-22.00	590.95
A3	265+89.40	-22.00	590.89
A4	265+99.40	-22.00	590.83
E. End E. Appr. Pav't.	266+09.40	-22.00	590.77

NORTH EDGE OF PAVEMENT

Location	Station	Offset	Theoretical Grade Elevations
W. End E. Appr. Pav't.	265+85.17	-12.00	591.13
A3	265+95.17	-12.00	591.07
A4	266+05.17	-12.00	591.00
E. End E. Appr. Pav't.	266+15.17	-12.00	590.94

W.B. ROADWAY & PGL

Location	Station	Offset	Theoretical Grade Elevations
W. End E. Appr. Pav't.	265+92.10	0.00	591.27
A3	266+02.10	0.00	591.21
A4	266+12.10	0.00	591.14
E. End E. Appr. Pav't.	266+22.10	0.00	591.08

SOUTH EDGE OF PAVEMENT

Location	Station	Offset	Theoretical Grade Elevations
W. End E. Appr. Pav't.	265+99.03	12.00	591.04
A3	266+09.03	12.00	590.98
A4	266+19.03	12.00	590.91
E. End E. Appr. Pav't.	266+29.03	12.00	590.84

SOUTH EDGE OF SHOULDER

Location	Station	Offset	Theoretical Grade Elevations
W. End E. Appr. Pav't.	266+02.49	18.00	590.89
A3	266+12.49	18.00	590.83
A4	266+22.49	18.00	590.76
E. End E. Appr. Pav't.	266+32.49	18.00	590.69

TOP OF W.B. ROADWAY
EAST APPROACH SLAB ELEVATIONS
STRUCTURE NO. 081-0024 (W.B.)
STRUCTURE NO. 081-0025 (E.B.)

DESIGNED	LAN
CHECKED	LC
DRAWN	LAN
CHECKED	LC

PLAN



**INFRASTRUCTURE
ENGINEERING** | INCORPORATED
33 West Monroe | Suite 1540 | Chicago, IL 60603
P 312.425.9560 | F 312.425.9564 | www.infrastructure-eng.com

SHEET NO. 12 77 SHEETS	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	280	81-1(VB-1)R	ROCK ISLAND	503	348
	CONTRACT NO. 64815				
FED. ROAD DIST. NO. _ ILLINOIS FED. AID PROJECT					

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

NORTH EDGE OF SHOULDER

Location	Station	Offset	Theoretical Grade Elevations
W. End W. Appr. Pav't.	263+33.92	-18.00	591.92
A1	263+43.92	-18.00	591.90
A2	263+53.92	-18.00	591.89
E. End W. Appr. Pav't.	263+63.92	-18.00	591.87

NORTH EDGE OF PAVEMENT

Location	Station	Offset	Theoretical Grade Elevations
W. End W. Appr. Pav't.	263+35.34	-12.00	592.04
A1	263+45.34	-12.00	592.03
A2	263+55.34	-12.00	592.01
E. End W. Appr. Pav't.	263+65.34	-12.00	592.00

CL E.B. ROADWAY & PGL

Location	Station	Offset	Theoretical Grade Elevations
W. End W. Appr. Pav't.	263+38.19	0.00	592.22
A1	263+48.19	0.00	592.21
A2	263+58.19	0.00	592.20
E. End W. Appr. Pav't.	263+68.19	0.00	592.18


SOUTH EDGE OF PAVEMENT

Location	Station	Offset	Theoretical Grade Elevations
W. End W. Appr. Pav't.	263+41.04	12.00	592.03
A1	263+51.04	12.00	592.02
A2	263+61.04	12.00	592.00
E. End W. Appr. Pav't.	263+71.04	12.00	591.98

SOUTH EDGE OF SHOULDER

Location	Station	Offset	Theoretical Grade Elevations
W. End W. Appr. Pav't.	263+43.41	22.00	591.82
A1	263+53.41	22.00	591.81
A2	263+63.41	22.00	591.79
E. End W. Appr. Pav't.	263+73.41	22.00	591.77

TOP OF E.B. ROADWAY
WEST APPROACH SLAB ELEVATIONS
STRUCTURE NO. 081-0024 (W.B.)
STRUCTURE NO. 081-0025 (E.B.)



PLAN

DESIGNED	LAN
CHECKED	LC
DRAWN	LAN
CHECKED	LC



**INFRASTRUCTURE
ENGINEERING** | INCORPORATED
33 West Monroe | Suite 1540 | Chicago, IL 60603
P 312.425.9560 | F 312.425.9564 | www.infrastructure-eng.com

SHEET NO. 13	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
77 SHEETS	280	81-1(VB-1)R	ROCK ISLAND	503	349
CONTRACT NO. 64815					
FED. ROAD DIST. NO. - ILLINOIS FED. AID PROJECT					

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

NORTH EDGE OF SHOULDER

Location	Station	Offset	Theoretical Grade Elevations
W. End E. Appr. Pav't.	266+30.72	-18.00	590.71
A3	266+40.72	-18.00	590.63
A4	266+50.72	-18.00	590.56
E. End E. Appr. Pav't.	266+60.72	-18.00	590.49

NORTH EDGE OF PAVEMENT

Location	Station	Offset	Theoretical Grade Elevations
W. End E. Appr. Pav't.	266+34.18	-12.00	590.81
A3	266+44.18	-12.00	590.73
A4	266+54.18	-12.00	590.66
E. End E. Appr. Pav't.	266+64.18	-12.00	590.59

CL E.B. ROADWAY & PGL

Location	Station	Offset	Theoretical Grade Elevations
W. End E. Appr. Pav't.	266+41.11	0.00	590.94
A3	266+51.11	0.00	590.87
A4	266+61.11	0.00	590.80
E. End E. Appr. Pav't.	266+71.11	0.00	590.72

SOUTH EDGE OF PAVEMENT

Location	Station	Offset	Theoretical Grade Elevations
W. End E. Appr. Pav't.	266+48.04	12.00	590.71
A3	266+58.04	12.00	590.63
A4	266+68.04	12.00	590.56
E. End E. Appr. Pav't.	266+78.04	12.00	590.48

SOUTH EDGE OF SHOULDER

Location	Station	Offset	Theoretical Grade Elevations
W. End E. Appr. Pav't.	266+53.81	22.00	590.46
A3	266+63.81	22.00	590.38
A4	266+73.81	22.00	590.30
E. End E. Appr. Pav't.	266+83.81	22.00	590.22

TOP OF E.B. ROADWAY
EAST APPROACH SLAB ELEVATIONS
STRUCTURE NO. 081-0024 (W.B.)
STRUCTURE NO. 081-0025 (E.B.)

DESIGNED	LAN
CHECKED	LC
DRAWN	LAN
CHECKED	LC

PLAN



**INFRASTRUCTURE
ENGINEERING** | INCORPORATED


33 West Monroe | Suite 1540 | Chicago, IL 60603
P 312.425.9560 | F 312.425.9564 | www.infrastructure-eng.com

SHEET NO.14 77 SHEETS	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	280	81-1(VB-1)R	ROCK ISLAND	503	350
				CONTRACT NO. 64815	
	FED. ROAD DIST. NO. _ ILLINOIS FED. AID PROJECT				


P:\P-081\719\UGNSheets\Iowa Interstate RR Final Plans\Sevised Aug 2010\0810024-64815-014-EB-105 Elevations
3/15/10 PM 8/12/2010

** Place 6 bars between Beams 1A & 1 and 7 bars between each existing beam from Beam 1 to Beam 6.

Aluminum sheeted construction
joints in base of parapet



PLAN



NEAR MIDSPAN

CROSS SECTION
(Looking East)

NEAR PIER

W.B. ROADWAY DECK
STRUCTURE NO. 081-0024 (W.B.)
STRUCTURE NO. 081-0025 (E.B.)

DESIGNED	ASJ
CHECKED	SPK
DRAWN	ASJ
CHECKED	SPK

Notes:
 Bars indicated thus 20 x 3-#5 etc. indicates 20 lines of bars with 3 lengths per line.
 See sheets 21 and 22 of 77 for superstructure details and Bill of Material.
 See sheets 17, 18 and 21 of 77 for parapet reinforcement.
 Dimensions are based on Rolled Rail Strip Seal Joint. If the Contractor elects to use the Welded Rail Strip Seal Joint, deck dimensions may require adjustments to satisfy the details on sheet 29 of 77.



INFRASTRUCTURE
ENGINEERING | INCORPORATED
33 West Monroe | Suite 1540 | Chicago, IL 60603
P 312.425.9560 | F 312.425.9564 | www.infrastructure-eng.com


SHEET NO. 15	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	280	81-1(VB-1)R	ROCK ISLAND	503	351
	77 SHEETS			CONTRACT NO. 64815	
FED. ROAD DIST. NO. _ ILLINOIS FED. AID PROJECT					

* See Field Cutting Diagram on sheet 22 of 77.
** Place 7 bars between each existing beam from Beam 7 to Beam 12 and 6 bars between Beam 12 and Beam 13.

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION


263'-8 1/2" end to end deck

Notes:
Bars indicated thus 20 x 3-#5 etc. indicates 20 lines of bars with 3 lengths per line.
See sheets 21 and 22 of 77 for superstructure details and Bill of Material.
See sheets 19, 20 and 21 of 77 for parapet reinforcement.
Dimensions are based on Rail Strip Seal Joint. If the Contractor elects to use the Welded Rail Strip Seal Joint, deck dimensions may require adjustments to satisfy the details on sheet 29 of 77.



MINIMUM BAR LAP
(Slab)
#5 bar = 3'-3"

PLAN



NEAR PIER

STIRRUP TABLE

Beam	#5 (E) Quantity
7	266
8	268
9	270
10	272
11	275
12	277

CROSS SECTION
(Looking East)

NEAR MIDSPAN

E.B. ROADWAY DECK
STRUCTURE NO. 081-0024 (W.B.)
STRUCTURE NO. 081-0025 (E.B.)


DESIGNED	ASJ
CHECKED	SPK
DRAWN	ASJ
CHECKED	SPK




INFRASTRUCTURE
ENGINEERING INCORPORATED
33 West Monroe | Suite 1540 | Chicago, IL 60603
P 312.425.9560 | F 312.425.9564 | www.infrastructure-eng.com

SHEET NO.	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
77 SHEETS	280	81-1(VB-1)R	ROCK ISLAND	503	352
CONTRACT NO. 64815					
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT					

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION



INSIDE ELEVATION OF NORTH PARAPET



INSIDE ELEVATION OF NORTH PARAPET

MINIMUM BAR LAP

(Parapet)

#4 bar = 2'-0"

#5 bar = 5'-2"

Note:
See sheet 21 of 77 for parapet details.
See sheet 22 of 77 for Bill of Material.
Dimensions are measured along inside face of parapet.

DESIGNED	ASJ
CHECKED	SPK
DRAWN	ASJ
CHECKED	SPK



INFRASTRUCTURE
ENGINEERING | INCORPORATED
33 West Monroe | Suite 1540 | Chicago, IL 60603
P 312.425.9560 | F 312.425.9564 | www.infrastructure-eng.com

SHEET NO.17 77 SHEETS	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	280	81-1(VB-1)R	ROCK ISLAND	503	353
CONTRACT NO. 64815					
FED. ROAD DIST. NO. - ILLINOIS FED. AID PROJECT					


W.B. ROADWAY NORTH PARAPET
STRUCTURE NO. 081-0024 (W.B.)
STRUCTURE NO. 081-0025 (E.B.)

P:\P-20\1719\00\Sheets\Iowa Interstate AP Final Plans\081-0024-64815-017-WB-NP-Parapet.dgn


12:29:09 PM

1/22/2010

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION



INSIDE ELEVATION OF SOUTH PARAPET



INSIDE ELEVATION OF SOUTH PARAPET

MINIMUM BAR LAP

(Parapet)

#4 bar = 2'-0"

#5 bar = 5'-2"

Note:
See sheet 21 of 77 for parapet details.
See sheet 22 of 77 for Bill of Material.
Dimensions are measured along inside face of parapet.

DESIGNED	ASJ
CHECKED	SPK
DRAWN	ASJ
CHECKED	SPK



INFRASTRUCTURE
ENGINEERING | INCORPORATED
33 West Monroe | Suite 1540 | Chicago, IL 60603
P 312.425.9560 | F 312.425.9564 | www.infrastructure-eng.com

SHEET NO. 18	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
77 SHEETS	280	81-1(VB-1)R	ROCK ISLAND	503	354
CONTRACT NO. 64815					
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT					

W.B. ROADWAY SOUTH PARAPET
STRUCTURE NO. 081-0024 (W.B.)
STRUCTURE NO. 081-0025 (E.B.)


P:\P-05\1719\05N\Sheets\Iowa Interstate Rd Final Plans\081-0024-64815-08-WB-S-Parapet.dgn

12:29:34 PM

7/22/2010

1719

7/22/2010 12:29:59 PM P:\P-05\1719\DCN\Sheets\Iowa Interstate RR Final Plans\0810024-64815-019-EB_N_Protd.dgn




(Parapet)

Note:
See sheet 21 of 77 for parapet details.
See sheet 22 of 77 for Bill of Material.
Dimensions are measured along inside
face of parapet.


SHEET NO. 19 77 SHEETS	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	280	81-1(VB-1)R	ROCK ISLAND	503	355
	CONTRACT NO. 64815				
FED. ROAD DIST. NO. _		ILLINOIS	FED. AID PROJECT		

E.B. ROADWAY NORTH PARAPET
STRUCTURE NO. 081-0024 (W.B.)
STRUCTURE NO. 081-0025 (E.B.)

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION



INSIDE ELEVATION OF SOUTH PARAPET



INSIDE ELEVATION OF SOUTH PARAPET

MINIMUM BAR LAP
(Parapet)

#4 bar = 2'-0"
#5 bar = 5'-2"

Note:
See sheet 21 of 77 for parapet details.
See sheet 22 of 77 for Bill of Material.
Dimensions are measured along inside
face of parapet.

E.B. ROADWAY SOUTH PARAPET
STRUCTURE NO. 081-0024 (W.B.)
STRUCTURE NO. 081-0025 (E.B.)

DESIGNED	ASJ
CHECKED	SPK
DRAWN	ASJ
CHECKED	SPK

INFRASTRUCTURE
ENGINEERING INCORPORATED
33 West Monroe | Suite 1540 | Chicago, IL 60603
P 312.425.9560 | F 312.425.9564 | www.infrastructure-eng.com

SHEET NO. 20 77 SHEETS	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	280	81-1(VB-1)R	ROCK ISLAND	503	356
CONTRACT NO. 64815					
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT					

P:\P-05\719\DCN\Sheets\New Interstate RR Final Plans\0810024-64815-020-EB-S-Parapet.dgn
12/22/2010 12:30:19 PM 1719

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

Notes:

Drains shall be located clear of all diaphragms.

The exterior surfaces of the floor drains shall be painted with the finish coat as specified in the special provisions for Cleaning and Painting New Metal Structures. The exterior surfaces of the drains shall be cleaned according to the Society of Protective Coatings Spec. SSPC-SP1 prior to painting.

Fiberglass pipe shall conform to ASTM D 2996, with short-time rupture strength hoop tensile stress of 30,000 p.s.i. minimum.

Galvanize clamping device according to AASHTO M232. Cost of clamping device and inserts is included with Floor Drains.

SECTION THRU W.B. ROADWAY
NORTH PARAPET

SECTION THRU W.B. ROADWAY
SOUTH PARAPET

SECTION THRU E.B. ROADWAY
NORTH PARAPET

SECTION THRU E.B. ROADWAY
SOUTH PARAPET

FIBERGLASS
PIPE

ALUMINUM
TUBE

SECTION A-A

Notes:

Cut longitudinal reinforcement to clear drainage scouppers.

TOP PLAN

(Showing Aluminum Tube)

SECTION B-B

* Dimension as required by Pipe Clamp

TOP PLAN

SUPERSTRUCTURE DETAILS
STRUCTURE NO. 081-0024 (W.B.)
STRUCTURE NO. 081-0025 (E.B.)

SHEET NO. 21	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
77 SHEETS	280	81-1(VB-1)R	ROCK ISLAND	503	357
CONTRACT NO. 64815					
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT					

INFRASTRUCTURE
ENGINEERING INCORPORATED
33 West Monroe | Suite 1540 | Chicago, IL 60603
P 312.425.9560 | F 312.425.9564 | www.infrastructure-eng.com

DESIGNED	ASJ
CHECKED	SPK
DRAWN	ASJ
CHECKED	SPK

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

W.B. ROADWAY SUPERSTRUCTURE

BILL OF MATERIAL

Bar	No.	Size	Length	Shape
a500 (E)	377	#5	42'-6"	
a501 (E)	321	#5	41'-10"	
a502 (E)	378	#6	6'-6"	
a503 (E)	6	#5	7'-9"	
a504 (E)	30	#5	8'-4"	
a505 (E)	8	#5	49'-1"	
a506 (E)	2	#5	48'-4"	
a507 (E)	15	#5	1'-6"	
b500 (E)	414	#4	32'-6"	
b501 (E)	424	#4	36'-2"	
b502 (E)	86	#4	40'-10"	
b503 (E)	43	#4	41'-4"	
d500 (E)	584	#5	6'-10"	
d501 (E)	292	#5	6'-5"	
d502 (E)	292	#5	8'-5"	
e500 (E)	17	#4	16'-8"	
e501 (E)	46	#4	17'-6"	
e502 (E)	32	#4	8'-9"	
e503 (E)	21	#4	17'-11"	
e504 (E)	16	#4	9'-0"	
e505 (E)	21	#4	18'-2"	
e506 (E)	17	#4	16'-5"	
e507 (E)	4	#4	15'-7"	
e508 (E)	2	#4	26'-10"	
e509 (E)	2	#8	28'-0"	
e510 (E)	4	#8	30'-2"	
e511 (E)	2	#8	29'-9"	
e512 (E)	2	#8	9'-0"	
e513 (E)	2	#8	30'-2"	
e514 (E)	2	#8	27'-7"	
e515 (E)	2	#4	28'-3"	
e516 (E)	2	#4	28'-7"	
e517 (E)	2	#4	25'-7"	
e518 (E)	34	#4	16'-7"	
e519 (E)	4	#4	15'-9"	
e520 (E)	4	#4	17'-5"	
e521 (E)	32	#4	9'-2"	
e522 (E)	16	#4	9'-3"	
e523 (E)	2	#4	25'-9"	
e524 (E)	4	#4	27'-10"	
e525 (E)	2	#4	26'-7"	
e526 (E)	4	#8	27'-9"	
e527 (E)	4	#8	9'-2"	
e528 (E)	2	#8	9'-3"	
e529 (E)	4	#8	29'-5"	
s510 (E)	1602	#4	7'-4"	
x500 (E)	82	#5	6'-5"	
Concrete Superstructure		Cu. Yds.	414.0	
Bridge Deck Grooving		Sq. Yd.	1,124	
Protective Coat		Sq. Yd.	1,456	
Reinforcement Bars, Epoxy Coated		Pound	79,400	

E.B. ROADWAY SUPERSTRUCTURE

BILL OF MATERIAL

Bar	No.	Size	Length	Shape
a500 (E)	359	#5	42'-6"	
a501 (E)	305	#5	41'-10"	
a502 (E)	384	#6	6'-6"	
a503 (E)	3	#5	7'-9"	
a504 (E)	15	#5	8'-4"	
a505 (E)	4	#5	49'-1"	
a506 (E)	1	#5	48'-4"	
a507 (E)	16	#5	1'-6"	
a508 (E)	3	#5	7'-0"	
a509 (E)	15	#5	7'-6"	
a510 (E)	4	#5	43'-9"	
a511 (E)	1	#5	43'-0"	
a512 (E)	7	#5	40'-7"	
a513 (E)	6	#5	39'-9"	
a514 (E)	17	#5	42'-6"	
a515 (E)	15	#5	42'-1"	
b520 (E)	414	#5	33'-10"	
b521 (E)	424	#5	37'-8"	
b522 (E)	43	#6	43'-4"	
b523 (E)	43	#6	46'-6"	
b524 (E)	43	#6	40'-6"	
d500 (E)	594	#5	6'-10"	
d502 (E)	289	#5	8'-5"	
d503 (E)	305	#5	6'-5"	
e501 (E)	21	#4	17'-6"	
e502 (E)	16	#4	8'-9"	
e504 (E)	16	#4	9'-0"	
e510 (E)	2	#8	8'-9"	
e512 (E)	2	#8	9'-0"	
e519 (E)	17	#4	15'-9"	
e530 (E)	4	#4	16'-1"	
e531 (E)	21	#4	19'-3"	
e532 (E)	17	#4	15'-6"	
e533 (E)	4	#4	14'-8"	
e534 (E)	16	#4	8'-3"	
e535 (E)	16	#4	9'-11"	
e536 (E)	2	#4	25'-1"	
e537 (E)	2	#4	27'-7"	
e538 (E)	2	#4	30'-4"	
e539 (E)	2	#4	24'-3"	
e540 (E)	2	#8	26'-6"	
e541 (E)	2	#8	8'-3"	
e542 (E)	2	#8	29'-2"	
e543 (E)	2	#8	9'-11"	
e544 (E)	2	#8	31'-10"	
e545 (E)	2	#8	26'-3"	
e546 (E)	17	#4	15'-2"	
e547 (E)	4	#4	14'-8"	
e548 (E)	28	#4	15'-8"	
e549 (E)	21	#4	19'-2"	
e550 (E)	17	#4	15'-8"	
e551 (E)	4	#4	16'-6"	
e552 (E)	16	#4	10'-0"	
e553 (E)	16	#4	10'-6"	
e554 (E)	2	#4	23'-11"	
e555 (E)	2	#4	33'-3"	

Bar	No.	Size	Length	Shape
e556 (E)	2	#4	30'-1"	
e557 (E)	2	#4	25'-2"	
e558 (E)	2	#8	25'-8"	
e559 (E)	2	#8	10'-0"	
e560 (E)	2	#8	34'-10"	
e561 (E)	2	#8	10'-6"	
e562 (E)	2	#8	31'-8"	
e563 (E)	2	#8	26'-4"	
s510 (E)	1628	#5	7'-4"	
x500 (E)	82	#5	6'-5"	
Concrete Superstructure		Cu. Yds.	421.0	
Bridge Deck Grooving		Sq. Yd.	1,144	
Protective Coat		Sq. Yd.	1,482	
Reinforcement Bars, Epoxy Coated		Pound	101,610	


Non-staining gray one component non-sag elastomeric gun grade polyurethane sealant meeting the requirements of ASTM C-920, Type S, Grade NS, Class 25, use T with a 5/8" backer rod.

1/2" Preformed Self-Expanding Cork Joint Filler according to Article 1051.07 of the Std. Spec. Cost included with Concrete Superstructure.

Const. Jts. at Piers 1/8" Aluminum sheet ASTM B 209 alloy 3003-H14 coated to minimize reaction with wet concrete. Cost included with Concrete Superstructure.

PARAPET JOINT DETAILS


Hatched area to be poured after superstructure forms have been removed. Quantity of concrete included with Concrete Superstructure.




SECTION A-A

EDGE BEAM REINFORCEMENT TABLE

Location	Beams 1A-1 Beams 12-13	Beams 1-6 Beams 7-12
Abutment A	#5 a503(E) bars	#5 a504(E) bars
Abutment B	#5 a503(E) bars	#5 a504(E) bars
Abutment C	#5 a508(E) bars	#5 a509(E) bars
Abutment D	#5 a503(E) bars	#5 a504(E) bars




BAR s510 (E)




BAR d500 (E)


BARS a503 (E) & a504 (E)




BARS a508 (E) & a509 (E)




BAR d501 (E)



BAR d503 (E)



BAR d502 (E)




FIELD CUTTING DIAGRAM

Order bars full length. Cut to fit as shown and place at one end of the dimension line shown on the plans. Use remainder of bars at opposite end of the dimension line.
*Indicates bar length to be discarded when an odd number of bars are required.

SUPERSTRUCTURE DETAILS
STRUCTURE NO. 081-0024 (W.B.)
STRUCTURE NO. 081-0025 (E.B.)

DESIGNED	ASJ
CHECKED	SPK
DRAWN	ASJ
CHECKED	SPK


BAR x500 (E)




INFRASTRUCTURE
ENGINEERING, INC.
33 West Monroe | Suite 1540 | Chicago, IL 60603
P 312.425.9560 | F 312.425.9564 | www.infrastructure-eng.com

SHEET NO. 22	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
77 SHEETS	280	81-1(VB-1)R	ROCK ISLAND	503	358
CONTRACT NO. 64815					
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT					

Notes:
See sheet 24 of 77 for Sections A-A & B-B.
a₅₄₀ (E), a₅₄₁ (E), a₅₄₂ (E) and a₅₄₃ (E) bar spacings
measured along C Roadway.



*** Cost included with Concrete Superstructure.



DETAIL C

*** Closed cell joint filler according to Article 1051.08 of the Standard Specifications; full depth of slab, full length of parapet. Typ. each parapet.*

DESIGNED	ASJ
CHECKED	SPK
DRAWN	ASJ
CHECKED	SPK

**INFRASTRUCTURE
ENGINEERING | INCORPORATED**
33 West Monroe | Suite 1540 | Chicago, IL 60603
P 312.425.9560 | F 312.425.9564 | www.infrastructure-ena.com

SHEET NO.23	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	280	81-1(VB-1)R	ROCK ISLAND	503	359
	77 SHEETS		CONTRACT NO. 64815		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT		

(Sheet 1 of 2)


W.B. ROADWAY WEST APPROACH SLAB DETAILS

STRUCTURE NO. 081-0024 (W.B.)


STRUCTURE NO. 081-0025 (E.B.)

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

Notes:
See sheet 23 of 77 for Detail C.
Approach slab shall be paid for as Concrete Superstructure.
Approach footing concrete shall be paid for as Concrete Structures.
Reinforcement shall be paid for as Reinforcement Bars, Epoxy Coated.
For $v_{500}(E)$ bar details, see sheet 43 of 77.
The approach footing maximum applied service bearing pressure (Q_{max}) = 2.0 ksf.
For bar splicer details, see sheet 71 of 77.
Cost of excavation for approach footing included with Concrete Structures.
For Porous Granular Embankment (Special) and drainage treatment details, see sheet 56 of 77.



SECTION A-A



AT APPROACH FOOTING

SECTION B-B

(See Plan for dimensions not shown)


NEAR ABUTMENT

* Tilt #9 $b_{541}(E)$ bars as required to maintain clearance.
** Cost included with Concrete Superstructure.

ONE APPROACH
BILL OF MATERIAL

Bar	No.	Size	Length	Shape
$a_{540}(E)$	16	#4	24'-5"	
$a_{541}(E)$	15	#5	45'-10"	
$a_{542}(E)$	34	#4	25'-9"	
$a_{543}(E)$	31	#5	47'-11"	
$b_{540}(E)$	33	#4	29'-8"	
$b_{541}(E)$	97	#9	29'-9"	
$b_{542}(E)$	6	#4	18'-2"	
$t_{540}(E)$	86	#4	11'-3"	
$w_{540}(E)$	40	#5	47'-11"	
Concrete Superstructure			Cu. Yd.	61.2
Concrete Structures			Cu. Yd.	12.9
Bridge Deck Grooving			Sq. Yd.	127
Protective Coat			Cu. Yd.	150
Reinforcement Bars, Epoxy Coated			Pound	16,300

DESIGNED	ASJ
CHECKED	SPK
DRAWN	ASJ
CHECKED	SPK




INFRASTRUCTURE
ENGINEERING | INCORPORATED
33 West Monroe | Suite 1540 | Chicago, IL 60603
P 312.425.9560 | F 312.425.9564 | www.infrastructure-eng.com

(Sheet 2 of 2)
W.B. ROADWAY WEST APPROACH SLAB DETAILS
STRUCTURE NO. 081-0024 (W.B.)
STRUCTURE NO. 081-0025 (E.B.)

SHEET NO. 24	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
77 SHEETS	280	81-1(VB-1)R	ROCK ISLAND	503	360
CONTRACT NO. 64815					
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT					

7/22/2010 12:32:31 PM P:\P-05\1719\DG\N\Sheets\Iowa interstate RR Final Plans\0810024-64815-025-EB_W_Appr_Details.dgn

*** Cost included with Concrete Superstructure.



FLEXIBLE PAVEMENT

[illegible]

* Tilt #9 b₅₄₁ (E) bars as required to maintain clearance.

DESIGNED	ASJ
CHECKED	SPK
DRAWN	ASJ
CHECKED	SPK



INFRASTRUCTURE
ENGINEERING | INCORPORATED
33 West Monroe | Suite 1540 | Chicago, IL 60603
P 312.425.9560 | F 312.425.9564 | www.infrastructure-eng.com

SHEET NO. 25	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	280	81-1(VB-1)R	ROCK ISLAND	503	361
			CONTRACT NO. 64815		
77 SHEETS	FED. ROAD DIST. NO. _ ILLINOIS		FED. AID PROJECT		

(Sheet 1 of 2)


E.B. ROADWAY WEST APPROACH SLAB DETAILS

STRUCTURE NO. 081-0024 (W.B.)


STRUCTURE NO. 081-0025 (E.B.)

Notes:

- See sheet 25 of 77 for Detail C.
- Approach slab shall be paid for as Concrete Superstructure.
- Approach footing concrete shall be paid for as Concrete Structures.
- Reinforcement shall be paid for as Reinforcement Bars, Epoxy Coated.
- For $V_{500}(E)$ bar details, see sheet 51 of 77.
- The approach footing maximum applied service bearing pressure (Q_{max}) = 2.0 ksf.
- For bar splicer details, see sheet 71 of 77.
- Cost of excavation for approach footing included with Concrete Structures.
- For Porous Granular Embankment (Special) and drainage treatment details, see sheet 56 of 77.



(See Plan for dimensions not shown)



BAR b541 (E)

(Sheet 2 of 2)

E.B. ROADWAY WEST APPROACH SLAB DETAILS


STRUCTURE NO. 081-0024 (W.B.)

STRUCTURE NO. 081-0025 (E.B.)


SHEET NO. 26 77 SHEETS	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	280	81-(VB-1)R	ROCK ISLAND	503	362
			CONTRACT NO. 64815		
FED. ROAD DIST. NO. -		ILLINOIS	FED. AID PROJECT		

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

Notes:
See sheet 28 of 77 for Sections A-A & B-B.
a₅₄₀ (E), a₅₄₁ (E), a₅₄₂ (E) and a₅₄₃ (E) bar spacings
measured along @ Roadway.
Order a₅₄₂ (E), a₅₄₃ (E), b₅₄₀ (E), b₅₄₁ (E) and b₅₄₂ (E) bars
full length. Cut in field to fit Type C and Type D
Inlet Boxes.



*** Cost included with Concrete Superstructure.



DETAIL C

(Sheet 1 of 2)
BRIDGE EAST APPROACH SLAB DETAILS
STRUCTURE NO. 081-0024 (W.B.)
STRUCTURE NO. 081-0025 (E.B.)

DESIGNED	ASJ
CHECKED	SPK
DRAWN	ASJ
CHECKED	SPK


* Tilt #9 b₅₄₁ (E) bars as required to maintain clearance.
** See Highway Standard 609006. See Roadway Plans for details and quantities.
*** Closed cell joint filler according to Article 1051.08 of the Standard Specifications; full depth of slab, full length of parapet. Typ. each parapet.



**INFRASTRUCTURE
ENGINEERING** | INCORPORATED
33 West Monroe | Suite 1540 | Chicago, IL 60603
P 312.425.9560 | F 312.425.9564 | www.infrastructure-eng.com

SHEET NO. 27 77 SHEETS	F.A.I. RTE. 280	SECTION 81-1(VB-1)R	COUNTY ROCK ISLAND	TOTAL SHEETS 503	SHEET NO. 363
	CONTRACT NO. 64815				
	FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

Notes:
 See sheet 27 of 77 for Detail C.
 Approach slab shall be paid for as Concrete Superstructure.
 Approach footing concrete shall be paid for as Concrete Structures.
 Reinforcement shall be paid for as Reinforcement Bars, Epoxy Coated.
 For v_{500} (E) bar details, see sheet 47 or 55 of 77.
 The approach footing maximum applied service bearing pressure (Q_{max}) = 2.0 ksf.
 For bar splicer details, see sheet 71 of 77.
 Cost of excavation for approach footing included with Concrete Structures.
 For Porous Granular Embankment (Special) and drainage treatment details, see sheet 56 of 77.










Bar	No.	Size	Length	Shape
Q540 (E)	32	#1	24'-5"	————
Q541 (E)	30	#5	45'-10"	————
Q542 (E)	68	#4	25'-9"	————
Q543 (E)	62	#5	47'-11"	————
b540 (E)	66	#4	29'-8"	————
b541 (E)	194	#9	29'-9"	————
b542 (E)	12	#4	18'-2"	————
t540 (E)	172	#4	11'-3"	————
w540 (E)	80	#5	47'-11"	————
Concrete Superstructure			Cu. Yd.	122.4
Concrete Structures			Cu. Yd.	25.8
Bridge Deck Grooving			Sq. Yd.	254
Protective Coat			Cu. Yd.	300
Reinforcement Bars, Epoxy Coated			Pound	32,590



SHEET NO. 28	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	280	81-1(VB-1)R	ROCK ISLAND	503	364
	77 SHEETS			CONTRACT NO. 64815	
FED. ROAD DIST. NO. - ILLINOIS FED. AID PROJECT					

12/2/2010 12:34:57 PM P:\P-05\1719\DCN\Sheets\Iowa Interstate RR Final Plans\0310024-64815-023-Pref-Jt.Strip.Seal.dgn

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION



BILL OF MATERIAL

ITEM	UNIT	QUANTITY
Drainage Scupper, DS-11	Each	4

DRAINAGE SCUPPER, DS-11
STRUCTURE NO. 081-0024 (W.B.)
STRUCTURE NO. 081-0025 (E.B.)

DESIGNED
CHECKED
DRAWN ASJ
CHECKED SPK

DS-11


11-1-09



INFRASTRUCTURE
ENGINEERING | INCORPORATED
33 West Monroe | Suite 1540 | Chicago, IL 60603
P 312.425.9560 | F 312.425.9564 | www.infrastructure-eng.com

SHEET NO. 30	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
77 SHEETS	280	81-1(VB-1)R	ROCK ISLAND	503	366
CONTRACT NO. 64815					
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT					

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION



PLAN

* Kink indicates the location of the change in skew of Pier 3.

FRAMING PLAN
STRUCTURE NO. 081-0024 (W.B.)
STRUCTURE NO. 081-0025 (E.B.)

DESIGNED	SST
CHECKED	SPK
DRAWN	ASJ
CHECKED	SPK

Note:
All diaphragms shall be installed as steel is erected and secured with erection pins and bolts except as otherwise noted. Individual diaphragms at supports may be temporarily disconnected to install bearing anchor rods.

INFRASTRUCTURE ENGINEERING
33 West Monroe | Suite 1540 | Chicago, IL 60603
P 312.425.9560 | F 312.425.9564 | www.infrastructure-eng.com

SHEET NO. 31 77 SHEETS	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	280	81-1(VB-1)R	ROCK ISLAND	503	367
				CONTRACT NO. 64815	
FED. ROAD DIST. NO. _ ILLINOIS FED. AID PROJECT					

1719
7/22/2010
12:36:00 PM
E:\P-05\715\081\Sheets\Novo Interstate RR Final Plans\081\0024-64815-03-Framing Plan.dgn

8/25/2010 11:28:31 AM P:\P-25\1719\Drawn\Sheets\Iowa Interstate RR Final Plans\0810024-64815-032-Stl-Beam-1A.dgn



8/25/11



8/25/11

8/25/118/25/11

8/25/11

8/25/11


8/25/11




8/25/11

8/25/11

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION



BEAM 13 ELEVATION



SECTION A-A

BEAM 13 FASCIA MOMENT TABLE								
		0.4 Span 1	Pier 4	0.5 Span 2	Pier 5	0.5 Span 3	Pier 6	0.6 span 4
I_e	(in ⁴)	6,680	6,680	6,680	6,680	6,680	6,680	6,680
$I_e(n)$	(in ⁴)	15,400		15,400		15,400		15,400
$I_e(3n)$	(in ⁴)	11,084		11,084		11,084		11,084
S_e	(in ³)	435	435	435	435	435	435	435
$S_e(n)$	(in ³)	606		606		606		606
$S_e(3n)$	(in ³)	541		541		541		541
ϕ	(k/')	0.624	0.923	0.624	0.923	0.624	0.923	0.624
$M\phi$	(k)	101	458	218	528	153	378	124
$s\phi$	(k/')	0.299		0.299		0.299		0.299
$M_s\phi$	(k)	56		123		89		66
M_L	(k)	211	167	297	187	268	150	212
M_I	(k)	58	43	70	45	66	39	58
$\phi_3 [M_L + I]$	(k)	448	350	612	387	557	315	450
M_a	(k)	786	1,050	1,239	1,190	1,039	901	832
M_u	(k)	2,786		2,786		2,786		2,786
$f_s \phi$ non-comp	(ksi)	2.8	12.6	6.0	14.6	4.2	10.4	3.4
$f_s \phi$ (comp)	(ksi)	1.2		2.7		2.0		1.5
$f_s \phi_3 [M_L + M_I]$	(ksi)	8.9	9.7	12.1	10.7	11.0	8.7	8.9
f_s (Overload)	(ksi)	12.9	22.3	20.8	25.3	17.2	19.1	13.8
f_s (Total)	(ksi)	16.8	29.0	27.0	32.9	22.4	24.8	17.9
VR	(k)	28.4		25.3		25.3		28.0

BEAM 13 FASCIA REACTION TABLE						
	Abut. C	Pier 4	Pier 5	Pier 6	Abut. D	
$R\phi$	(k)	17.8	71.6	77.1	65.7	19.2
R_L	(k)	19.5	26.4	27.9	25.4	19.6
R_I	(k)	5.4	4.9	4.9	4.9	5.4
R_{Total}	(k)	42.7	102.9	109.9	96.0	44.2

* Compact section
** Braced non-compact and partially braced section

TOP OF BEAM ELEVATIONS
(For Fabrication Use Only)

	Abut. C	Pier 4	Field Splice D	Pier 5	Field Splice E	Field Splice F	Pier 6	Abut. D
Beam 13	591.05	590.82	590.77	590.46	590.39	590.10	590.04	589.76

Notes:
All material on this sheet to be AASHTO M270
Grade 50 unless otherwise noted.
Load carrying components designated "NTR" shall
conform to the Supplemental Requirement for Notch
Toughness, Zone 2.
For Field Splice Detail see sheet 32 of 77.

STEEL BEAM 13 DETAILS
STRUCTURE NO. 081-0024 (W.B.)
STRUCTURE NO. 081-0025 (E.B.)

DESIGNED	SPK
CHECKED	LAN
DRAWN	ASJ
CHECKED	SPK



INFRASTRUCTURE
ENGINEERING | INCORPORATED
33 West Monroe | Suite 1540 | Chicago, IL 60603
P 312.425.9560 | F 312.425.9564 | www.infrastructure-eng.com

SHEET NO. 33	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	280	81-1(VB-1)R	ROCK ISLAND	503	369
CONTRACT NO. 64815					
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT					


12/22/2010 12:37:46 PM P:\P-05\1719\DGNNSheets\Iowa Interstate RR Final Plans\0810024-64815-034-Ex-Beam-1-6.dgn



SHEET NO. 34	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	280	81-1(VB-1)R	ROCK ISLAND	503	370
			CONTRACT NO. 64815		
77 SHEETS	FED. ROAD DIST. NO. _ ILLINOIS FED. AID PROJECT				

EXISTING STEEL BEAMS 1-6 DETAILS
STRUCTURE NO. 081-0024 (W.B.)
STRUCTURE NO. 081-0025 (E.B.)

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION



EXISTING BEAMS 7-12 ELEVATION


Note:
If the 3/4" stud spacing locates a row of studs within 3 1/2" of a row of existing 7/8" studs, relocate the row of 3/4" studs so that it is 3 1/2" away from the existing 7/8" studs.

SHEAR STUD SPACINGS AND DIMENSIONS TABLE

Beam	A	B	C	D	E	F	G	H	I	J	K	L	M	N
7	34 Spa. at 6" = 17'-0"	8 Spa. at 3" = 2'-0"	14'-4"	14'-3"	4 Spa. at 3" = 1'-0"	6"	2 Spa. at 3" = 6"	4 Spa. at 6" = 2'-0"	52 Spa. at 8" = 34'-8"	8 Spa. at 3" = 2'-0"	18'-0"	16'-6"	6 Spa. at 3" = 1'-6"	1 Spa. at 6" = 6"
8	33 Spa. at 6" = 16'-6"	8 Spa. at 3" = 2'-0"	14'-10"	14'-6"	3 Spa. at 3" = 9"	6"	4 Spa. at 3" = 1'-0"	5 Spa. at 6" = 2'-6"	54 Spa. at 8" = 36'-0"	8 Spa. at 3" = 2'-0"	17'-10 3/8"	17'-0"	6 Spa. at 3" = 1'-6"	-
9	32 Spa. at 6" = 16'-0"	7 Spa. at 3" = 1'-9"	15'-7"	14'-6"	3 Spa. at 3" = 9"	6"	4 Spa. at 3" = 1'-0"	7 Spa. at 6" = 3'-6"	56 Spa. at 8" = 37'-4"	7 Spa. at 3" = 1'-9"	17'-11 3/8"	17'-6"	4 Spa. at 3" = 1'-0"	-
10	30 Spa. at 6" = 15'-0"	8 Spa. at 3" = 2'-0"	16'-4"	14'-9"	2 Spa. at 3" = 6"	6"	4 Spa. at 3" = 1'-0"	5 Spa. at 6" = 2'-6"	61 Spa. at 8" = 40'-8"	7 Spa. at 3" = 1'-9"	17'-9 3/8"	18'-0"	2 Spa. at 3" = 6"	-
11	29 Spa. at 6" = 14'-6"	7 Spa. at 3" = 1'-9"	17'-1"	15'-0"	1 Spa. at 3" = 3"	6"	5 Spa. at 3" = 1'-3"	5 Spa. at 6" = 2'-6"	64 Spa. at 8" = 42'-8"	7 Spa. at 3" = 1'-9"	17'-8 1/8"	19'-0"	-	-
12	27 Spa. at 6" = 13'-6"	8 Spa. at 3" = 2'-0"	17'-10"	15'-9"	-	-	7 Spa. at 3" = 1'-9"	3 Spa. at 6" = 1'-6"	68 Spa. at 8" = 45'-4"	7 Spa. at 3" = 1'-9"	17'-9"	19'-3"	-	-


SHEAR STUD SPACINGS AND DIMENSIONS TABLE

Beam	O	P	Q	R	S	T	U	V	W	X	Y	Z	AA
7	6"	-	5 Spa. at 6" = 2'-6"	57 Spa. at 8" = 38'-0"	4 Spa. at 3" = 1'-0"	16'-4"	31 Spa. at 6" = 15'-6"	25 Spa. at 8" = 16'-8"	3 Spa. at 2'-0" = 6'-0"	18'-5"	57'-5"	72'-11"	263'-3 1/2"
8	6"	-	5 Spa. at 6" = 2'-6"	57 Spa. at 8" = 38'-0"	4 Spa. at 3" = 1'-0"	16'-2"	30 Spa. at 6" = 15'-0"	26 Spa. at 8" = 17'-4"	4 Spa. at 2'-0" = 8'-0"	18'-7 3/8"	59'-7 3/8"	75'-1 3/8"	265'-5 1/8"
9	6"	2 Spa. at 3" = 6"	8 Spa. at 6" = 4'-0"	54 Spa. at 8" = 36'-0"	4 Spa. at 3" = 1'-0"	16'-0"	29 Spa. at 6" = 14'-6"	27 Spa. at 8" = 18'-0"	5 Spa. at 2'-0" = 10'-0"	18'-9 3/8"	61'-9 3/8"	77'-3 3/8"	267'-7 1/8"
10	6"	4 Spa. at 3" = 1'-0"	3 Spa. at 6" = 1'-6"	57 Spa. at 8" = 38'-0"	4 Spa. at 3" = 1'-0"	15'-10"	28 Spa. at 6" = 14'-0"	28 Spa. at 8" = 18'-0"	6 Spa. at 2'-0" = 12'-0"	18'-11 3/8"	63'-11 3/8"	79'-5 3/8"	269'-10 1/8"
11	-	9 Spa. at 3" = 2'-3"	4 Spa. at 6" = 2'-0"	54 Spa. at 8" = 36'-0"	5 Spa. at 3" = 1'-3"	15'-8"	27 Spa. at 6" = 13'-6"	29 Spa. at 8" = 19'-4"	7 Spa. at 2'-0" = 14'-0"	19'-1 1/8"	66'-1 1/8"	81'-7 1/8"	272'-0 1/8"
12	-	6 Spa. at 3" = 1'-6"	5 Spa. at 6" = 2'-6"	54 Spa. at 8" = 36'-0"	5 Spa. at 3" = 1'-3"	15'-6"	26 Spa. at 6" = 13'-0"	30 Spa. at 8" = 20'-0"	8 Spa. at 2'-0" = 16'-0"	19'-4"	68'-4"	83'-10"	274'-2 1/2"




SECTION A-A

DESIGNED	SPK
CHECKED	LAN
DRAWN	ASJ
CHECKED	SPK



SECTION B-B
SECTION C-C



EXISTING STEEL BEAMS 7-12 DETAILS
STRUCTURE NO. 081-0024 (W.B.)
STRUCTURE NO. 081-0025 (E.B.)

INFRASTRUCTURE ENGINEERING | INCORPORATED

33 West Monroe | Suite 1540 | Chicago, IL 60603

P 312.425.9560 | F 312.425.9564 | www.infrastructure-eng.com

SHEET NO. 35	F.A.I. RTE. 280	SECTION 81-1(VB-1)R	COUNTY ROCK ISLAND	TOTAL SHEETS 503	SHEET NO. 371
77 SHEETS	CONTRACT NO. 64815				
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT					

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

BEAMS 2-5 MOMENT TABLE							
	0.4 Span 1	Pier 1	0.5 Span 2	Pier 2	0.5 Span 3	Pier 3	0.6 Span 4
I_s	(in ⁴)	6,710	8,811	6,710	8,811	6,710	8,811
$I_o(n)$	(in ⁴)	22,118	-	22,118	-	22,118	-
$I_o(3n)$	(in ⁴)	15,590	-	15,590	-	15,590	-
S_s	(in ³)	405	521	405	521	405	521
$S_o(n)$	(in ³)	682	-	682	-	682	-
$S_o(3n)$	(in ³)	604	-	604	-	604	-
P	(k/')	0.846	1.189	0.846	1.189	0.846	1.189
M_P	(k)	203	503	181	509	181	503
s_P	(k/')	0.317	-	0.317	-	0.317	-
M_sP	(k)	86	-	88	-	88	-
M_L	(k)	399	242	434	263	434	242
M_I	(k)	109	64	110	66	110	64
$S_3[M_L + I]$	(k)	847	510	907	548	907	510
M_o	(k)	1,477	1,317	1,529	1,374	1,529	1,317
M_u	(k)	2,224	-	2,744	-	2,744	-
$f_s P$ non-comp	(ksi)	6.0	11.6	5.4	11.7	5.4	11.6
$f_s P$ (comp)	(ksi)	1.7	-	1.7	-	1.7	-
$f_s S_3[M_L + M_I]$	(ksi)	14.9	11.7	16.0	12.6	16.0	11.7
f_s (Overload)	(ksi)	22.6	23.3	23.1	24.3	23.1	23.3
f_s (Total)	(ksi)	-	30.3	-	31.6	-	30.3
VR	(k)	53.9	-	43.3	-	43.3	-

BEAMS 2-5 REACTION TABLE					
	Abut. A	Pier 1	Pier 2	Pier 3	Abut. B
R_P	(k)	26.8	85.5	85.3	85.5
R_L	(k)	38.9	44.6	45.1	44.6
R_I	(k)	10.6	8.7	8.3	8.7
R_{Total}	(k)	76.3	138.8	138.7	138.8

BEAM 11 MOMENT TABLE							
	0.4 Span 1	Pier 4	0.5 Span 2	Pier 5	0.5 Span 3	Pier 6	0.6 Span 4
I_s	(in ⁴)	8,160	8,160	8,160	10,312	8,160	8,160
$I_o(n)$	(in ⁴)	25,381	-	25,381	-	25,381	-
$I_o(3n)$	(in ⁴)	17,692	-	17,692	-	17,692	-
S_s	(in ³)	487	487	487	602	487	487
$S_o(n)$	(in ³)	797	-	797	-	797	-
$S_o(3n)$	(in ³)	703	-	703	-	703	-
P	(k/')	0.869	1.186	0.869	1.211	0.869	1.186
M_P	(k)	162	541	264	670	224	497
s_P	(k/')	0.317	-	0.317	-	0.317	-
M_sP	(k)	68	-	119	-	104	-
M_L	(k)	372	256	502	306	477	244
M_I	(k)	102	66	121	75	118	64
$S_3[M_L + I]$	(k)	790	537	1,038	635	992	513
M_o	(k)	1,326	1,401	1,847	1,697	1,716	1,313
M_u	(k)	3,302	1,677	2,791	-	2,744	1,677
$f_s P$ non-comp	(ksi)	4.0	13.3	6.5	13.4	5.5	12.2
$f_s P$ (comp)	(ksi)	1.2	-	2.0	-	1.8	-
$f_s S_3[M_L + M_I]$	(ksi)	11.9	13.2	15.6	12.7	14.9	12.6
f_s (Overload)	(ksi)	17.1	26.5	24.1	26.1	22.2	24.8
f_s (Total)	(ksi)	-	-	-	33.9	-	-
VR	(k)	54.4	-	44.3	-	44.4	-

BEAM 11 REACTION TABLE					
	Abut. C	Pier 4	Pier 5	Pier 6	Abut. D
R_P	(k)	24.3	89.7	98.9	86.3
R_L	(k)	38.5	44.9	48.0	44.8
R_I	(k)	10.7	8.6	8.4	8.6
R_{Total}	(k)	73.5	143.2	155.3	139.7

BEAM 10 MOMENT TABLE							
	0.4 Span 1	Pier 4	0.5 Span 2	Pier 5	0.5 Span 3	Pier 6	0.6 Span 4
I_s	(in ⁴)	7,450	7,450	7,450	9,576	7,450	7,450
$I_o(n)$	(in ⁴)	23,793	-	23,793	-	23,793	-
$I_o(3n)$	(in ⁴)	16,670	-	16,670	-	16,670	-
S_s	(in ³)	447	447	447	563	447	447
$S_o(n)$	(in ³)	741	-	741	-	741	-
$S_o(3n)$	(in ³)	655	-	655	-	655	-
P	(k/')	0.858	1.175	0.858	1.200	0.858	1.175
M_P	(k)	167	511	239	644	226	496
s_P	(k/')	0.317	-	0.317	-	0.317	-
M_sP	(k)	71	-	111	-	106	-
M_L	(k)	374	248	485	299	477	243
M_I	(k)	103	64	118	73	118	63
$S_3[M_L + I]$	(k)	795	520	1,005	620	992	510
M_o	(k)	1,343	1,340	1,752	1,643	1,721	1,308
M_u	(k)	3,094	1,542	2,529	-	2,514	1,542
$f_s P$ non-comp	(ksi)	4.5	13.7	6.4	13.7	6.1	13.3
$f_s P$ (comp)	(ksi)	1.3	-	2.0	-	1.9	-
$f_s S_3[M_L + M_I]$	(ksi)	12.9	14.0	16.3	13.2	16.1	13.7
f_s (Overload)	(ksi)	18.7	27.7	24.7	26.9	24.1	27.0
f_s (Total)	(ksi)	-	-	-	35.0	-	-
VR	(k)	54.4	-	44.4	-	44.2	-

BEAM 10 REACTION TABLE					
	Abut. C	Pier 4	Pier 5	Pier 6	Abut. D
R_P	(k)	24.6	87.0	96.5	85.9
R_L	(k)	38.6	44.8	47.5	44.8
R_I	(k)	10.6	8.7	8.4	8.6
R_{Total}	(k)	73.8	140.5	152.4	139.3

I_s, S_s : Non-composite moment of inertia and section modulus of the steel section used for computing f_s (Total and Overload) due to non-composite dead loads (in⁴ and in³).

$I_o(n), S_o(n)$: Composite moment of inertia and section modulus of the steel and deck based upon the modular ratio, "n", used for computing f_s (Total and Overload) due to short-term composite live loads (in⁴ and in³).

$I_o(3n), S_o(3n)$: Composite moment of inertia and section modulus of the steel and deck based upon 3 times the modular ratio, "3n", used for computing f_s (Total and Overload) due to long-term composite (superimposed) dead loads (in⁴ and in³).

P : Un-factored non-composite dead load (kips/ft.).

M_P : Un-factored moment due to non-composite dead load (kip-ft.).

s_P : Un-factored long-term composite (superimposed) dead load (kips/ft.).

M_sP : Un-factored moment due to long-term composite (superimposed) dead load (kip-ft.).

M_L : Un-factored live load moment (kip-ft.).

M_I : Un-factored moment due to impact (kip-ft.).

M_o : Factored design moment (kip-ft.).

$1.3 [M_P + M_sP + \frac{5}{8} (M_L + M_I)]$

M_u : Compact composite moment capacity according to AASHTO LFD 10.50.1.1 or compact non-composite moment capacity according to AASHTO LFD 10.48.1 (kip-ft.).

f_s (Overload): Sum of stresses as computed from the moments below (ksi).

$M_P + M_sP + \frac{5}{8} (M_L + M_I)$

f_s (Total): Sum of stresses as computed from the moments below on non-compact section (ksi).

$1.3 [M_P + M_sP + \frac{5}{8} (M_L + M_I)]$

VR: Maximum $\frac{1}{4}$ impact horizontal shear range within the composite portion of the span for stud shear connector design (kips).

EXISTING BEAMS DESIGN DATA TABLES
STRUCTURE NO. 081-0024 (W.B.)
STRUCTURE NO. 081-0025 (E.B.)




INFRASTRUCTURE
ENGINEERING | INCORPORATED
33 West Monroe | Suite 1540 | Chicago, IL 60603
P 312.425.9560 | F 312.425.9564 | www.infrastructure-eng.com

SHEET NO.36 77 SHEETS	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	280	81-1(VB-1)R	ROCK ISLAND	503	372
	CONTRACT NO. 64815				
	FED. ROAD DIST. NO. _ ILLINOIS FED. AID PROJECT				


DESIGNED SPK
CHECKED
DRAWN ASJ
CHECKED SPK

* Compact section
** Braced non-compact and partially braced section


STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION




SECTION A-A




END DIAPHRAGM
(4 Required)




SECTION B-B




SECTION C-C



INTERIOR DIAPHRAGM
(24 Required)



SECTION D-D



SECTION E-E

SECTION F-F

DIAPHRAGMS
STRUCTURE NO. 081-0024 (W.B.)
STRUCTURE NO. 081-0025 (E.B.)

Notes:
Two hardened washers required for each set of oversized holes.
*Alternate channel C12x30 is permitted to facilitate material acquisition. Calculated weight of structural steel is based on the lighter section.
The alternate, if utilized, shall be provided at no additional cost to the Department.




INFRASTRUCTURE
ENGINEERING | INCORPORATED
33 West Monroe | Suite 1540 | Chicago, IL 60603
P 312.425.9560 | F 312.425.9564 | www.infrastructure-eng.com


SHEET NO. 37 77 SHEETS	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	280	81-1(VB-1)R	ROCK ISLAND	503	373
CONTRACT NO. 64815					
FED. ROAD DIST. NO. _ ILLINOIS FED. AID PROJECT					

DESIGNED	SST
CHECKED	SPK
DRAWN	ASJ
CHECKED	SPK

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION




ELEVATION AT ABUT.




SECTION A-A


TYPE II ELASTOMERIC EXP. BRG.




TOP BEARING ASSEMBLY




PLAN-PTFE SURFACE



BOTTOM BEARING ASSEMBLY




SECTION THRU PTFE



SIDE RETAINER

Equivalent rolled angle with stiffeners will be allowed in lieu of welded plates.



BELOW 50°F. ABOVE 50°F.
(Move bott. brg. away from fixed brg.) (Move bott. brg. toward fixed brg.)

SETTING ANCHOR BOLTS AT EXP. BRG.

D=1/8" per each 100' of expansion for every 15° temp. change from the normal temp. of 50°F.

Notes:
Anchor bolts shall be ASTM F1554 all-thread (or an Engineer-approved alternate material) of the grade(s) and diameter(s) specified. ASTM A307 Grade C anchor bolts may be used in lieu of ASTM F1554 Grade 36 (Fy=36ksi). The corresponding specified grade of AASHTO M311 anchor bolts may be used in lieu of ASTM F1554.
Anchor bolts for Type II bearings shall be placed in holes drilled in the concrete through holes in the bottom bearing plate after members are in place. Side retainers shall be placed after bolts are installed.
Drilled and set anchor bolts shall be installed according to Article 521.06 of the Standard Specifications.
Side retainers and other steel members required for the bearing assembly shall be included in the cost of Elastomeric Bearing Assembly, Type II.
The 1/8" PTFE sheet shall be bonded directly to the top steel plate with a two-component, medium viscosity epoxy resin, conforming to the requirements of the Federal Specification MMM-A-134, Type I. The bond agent shall be applied on the full area of the contact surfaces.
Bonding of 1/8" PTFE sheet during vulcanizing process will be permitted provided the process and method of adjusting assembly height is approved by the Engineer.
Two 1/8" adjusting shims shall be provided for each bearing in addition to all other plates or shims and placed as shown on bearing details.

BILL OF MATERIAL

Item	Unit	Total
Elastomeric Bearing Assembly Type II	Each	4
Anchor Bolts, 5/8"	Each	8


BEARING DETAILS - ABUTMENTS
STRUCTURE NO. 081-0024 (W.B.)
STRUCTURE NO. 081-0025 (E.B.)

DESIGNED	SST
CHECKED	SPK
DRAWN	ASJ
CHECKED	SPK

INFRASTRUCTURE ENGINEERING INCORPORATED
33 West Monroe | Suite 1540 | Chicago, IL 60603
P 312.425.9560 | F 312.425.9564 | www.infrastructure-eng.com


SHEET NO. 38 77 SHEETS	F.A.I. RTE. 280	SECTION 81-1(VB-1)R	COUNTY ROCK ISLAND	TOTAL SHEETS 503	SHEET NO. 374
	CONTRACT NO. 64815				
	FED. ROAD DIST. NO. - ILLINOIS FED. AID PROJECT				

P:\P-05\1719\DCN\Sheets\Iowa Interstate RR Final Plans\0810024-64815-039-Pier-Bra.dgn 7/22/2010 12:40:00 PM



FIXED BEARING

SECTION A-A




SECTION B-B

(4 Required)




ROCKER DETAIL



Anchor bolts shall be ASTM F1554 all-thread (or an Engineer-approved alternate material) of the grade and diameters specified. ASTM A307 Grade C anchor bolts may be used in lieu of ASTM F1554 Grade 36 ($F_y=36\text{ksi}$). The corresponding specified grade of AASHTO M314 anchor bolts may be used in lieu of ASTM F1554.

Drilled and set anchor bolts shall be installed according to Article 521.06 of the Standard Specifications.

BOLSTER PINTLE DETAIL



a). D^* (Side of brg. away from fixed brg.)
 $D^* = \frac{1}{8}"$ per each 100' of expansion for
 every 15° fall below the normal temp.
 of 50° F.

D** (Side of brg. toward fixed brg.)
D** = $\frac{1}{8}$ " per each 100' of expansion for
every 15° rise above the normal temp.
of 50° F.


ROCKER PINTLE DETAIL

ITEM	UNIT	QUANTITY
Anchor Bolts, 1"	Each	8
Anchor Bolts, 1½"	Each	4


SHEET NO. 39 77 SHEETS	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	280	81-1(VB-1)R	ROCK ISLAND	503	375
	CONTRACT NO. 64815				
FED. ROAD DIST. NO. - ILLINOIS FED. AID PROJECT					

DESIGNED	SST
CHECKED	SPK
DRAWN	ASJ
CHECKED	SPK


STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION




SOUTH WINGWALL ELEVATION




ELEVATION




NORTH WINGWALL ELEVATION




SECTION A-A



**SECTION B-B
SECTION E-E**



TOP VIEW



SECTION C-C

SECTION D-D

Notes:
Existing reinforcement bars not extending into the new construction shall be cut flush with the concrete left in place unless noted otherwise. Cost included with Concrete Removal.
Existing exposed reinforcement indicated to remain in place shall be cleaned and incorporated into the new construction. Cost included with Concrete Removal.
Repair of the existing abutment shall include but not be limited to the areas shown. The actual areas to be repaired will be determined by the Engineer at the time of construction.

BILL OF MATERIAL

Item	Unit	Total
Concrete Removal	Cu. Yd.	10.4
Structural Repair of Concrete (Depth Equal to or Less Than 5 Inches)	Sq. Ft.	17

**ABUTMENT A CONCRETE REMOVAL & REPAIRS
STRUCTURE NO. 081-0024 (W.B.)
STRUCTURE NO. 081-0025 (E.B.)**


DESIGNED LAN
CHECKED SPK
DRAWN LAN
CHECKED SPK

INFRASTRUCTURE ENGINEERING INCORPORATED
33 West Monroe | Suite 1540 | Chicago, IL 60603
P 312.425.9560 | F 312.425.9564 | www.infrastructure-eng.com


SHEET NO. 42 77 SHEETS	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	280	81-1(VB-1)R	ROCK ISLAND	503	376
	CONTRACT NO. 64815				
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT					

1719
7/22/2020
12:10:18 PM
P:\P-05\N719\00N\Sheets\New Interstate RR Final Plans\0810024 64815-042-Abut A Rem.dgn


STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION




ELEVATION



SECTION F-F



TOP VIEW



SECTION A-A

* Epoxy grout h500(E), h515(E), h516(E), p500(E), s502(E), v503(E), and w500(E) bars in 9" (min.) drilled holes. See Section 584 of the Standard Specifications. Cost of hole drilling and epoxy grouting are included with "Reinforcement Bars, Epoxy Coated".

** Elevation at Back of Abutment
B.F. = Back Face
E.F. = Each Face
F.F. = Front Face

Notes:
Hatched area to be poured after superstructure false work has been removed. Quantity of concrete included with Concrete Superstructure. Space reinforcement in cap to miss anchor bolts. For Concrete Encasement details, see sheet 70 of 77. Reinforcement bars that are to be grouted into existing concrete shall be spaced at least 6" (unless noted) from the edge of existing concrete and shall be embedded into the existing concrete a minimum of 9". Contractor shall avoid drilling into existing reinforcement. See Sheet 42 of 77 for Footing Plan, North Wing Wall, and Secs. B-B, C-C, D-D, & E-E. See Sheet 43 of 77 for South Wing Wall and Bill of Material.

ABUTMENT A WIDENING
STRUCTURE NO. 081-0024 (W.B.)
STRUCTURE NO. 081-0025 (E.B.)

DESIGNED	LAN
CHECKED	MMB
DRAWN	LAN
CHECKED	MMB



INFRASTRUCTURE
ENGINEERING | INCORPORATED
33 West Monroe | Suite 1540 | Chicago, IL 60603
P 312.425.9560 | F 312.425.9564 | www.infrastructure-eng.com

SHEET NO.	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
41	280	81-1(VB-1)R	ROCK ISLAND	503	377
77 SHEETS					
CONTRACT NO. 64815					
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT					

Back of Abut. $1'-11\frac{3}{8}"$ $\varnothing$ Brg.

6'-0" 1'-6"

Bar splicer (E) for #5 bars 3" cl. h502 (E)

For Exp. Joint details see sheet 29 of 77.

Varies 1'-0" v500 (E) h502 (E) v504 (E) 1'-0" min.

10'-0" h503 (E) or h504 (E) v501 (E)

6" h503 (E) or h504 (E)

1'-2 5/8" 3'-2 5/8" 3'-1 3/4" 6" 1'-8 5/8" 1'-7 3/4"

h503 (E) or h506 (E)




1/2" cl. 1/2" cl.

Existing reinforcement h503 (E) or h506 (E)

h503 (E) or h504 (E)

Section C-C
Section F-F
Section C-C
Section E-E


SECTION C-C
SECTION E-E




Notes:
See Sheet 43 of 77 for Bill of Material.
Quantity of concrete in end post included
with Concrete Superstructure on sheet 22 of 77.

ABUTMENT A FOOTING WIDENING
AND NORTH WING WALL
STRUCTURE NO. 081-0024 (W.B.)
STRUCTURE NO. 081-0025 (E.B.)

E.F. = Each Face
I.F. = Inside Face
O.F. = Outside Face




PARTIAL FOOTING PLAN




NORTH WING WALL ELEVATION
Showing Dimensions


DESIGNED	LAN
CHECKED	MMB
DRAWN	LAN
CHECKED	MMB




PILE DATA



VIEW M-M



SECTION K-K




NORTH WING WALL ELEVATION
Showing Reinforcement




INFRASTRUCTURE
ENGINEERING | INCORPORATED
33 West Monroe | Suite 1540 | Chicago, IL 60603
P 312.425.9560 | F 312.425.9564 | www.infrastructure-eng.com

SHEET NO. 42	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	280	81-1(VB-1)R	ROCK ISLAND	503	378
			CONTRACT NO. 64815		
77 SHEETS					
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT					


BILL OF MATERIAL



SOUTH WING WALL ELEVATION
Showing Dimensions



SOUTH WING WALL ELEVATION
Showing Reinforcement




SECTION G-G

Bar	No.	Size	Length	Shape
h500(E)	7	#5	4'-11"	
h501(E)	9	#5	5'-3"	
h502(E)	4	#6	45'-11"	
h503(E)	12	#5	8'-5"	
h504(E)	4	#4	8'-8"	
h505(E)	10	#5	8'-10"	
h506(E)	4	#5	8'-0"	
h507(E)	3	#4	11'-10"	
h508(E)	1	#4	11'-3"	
h509(E)	4	#4	12'-0"	
h510(E)	3	#4	10'-11"	
h511(E)	10	#4	11'-1"	
h512(E)	13	#4	10'-4"	
h513(E)	12	#5	11'-3"	
h514(E)	12	#5	12'-0"	
h515(E)	3	#5	4'-2"	
h516(E)	3	#5	5'-8"	
n500(E)	6	#5	6'-0"	
n501(E)	10	#6	18'-0"	
n502(E)	6	#6	9'-0"	
n503(E)	2	#5	3'-11"	
n504(E)	16	#9	7'-9"	
p500(E)	3	#7	7'-0"	
p501(E)	6	#7	14'-4"	
s500(E)	6	#4	8'-7"	
s501(E)	14	#4	9'-5"	
s502(E)	2	#4	7'-1"	
t500(E)	12	#5	9'-9"	
u500(E)	4	#5	9'-6"	
u501(E)	12	#5	7'-5"	
u502(E)	12	#5	8'-1"	
v500(E)	14	#5	3'-9"	
v501(E)	14	#4	4'-8"	
v502(E)	10	#4	6'-5"	
v503(E)	33	#5	4'-2"	
v504(E)	42	#4	3'-3"	
v505(E)	26	#6	7'-1"	
v507(E)	6	#6	7'-1"	
v508(E)	20	#6	7'-2"	
v509(E)	11	#5	6'-11"	
w500(E)	7	#6	9'-4"	
Porous Granular Embankment, Special			Cu. Yd.	100
Structure Excavation			Cu. Yd.	125
Concrete Structures			Cu. Yd.	17.7
Reinforcement Bars, Epoxy Coated			Pound	3820
Furnishing Steel Piles, HPBx36			Foot	96
Driving Piles			Foot	96
Pile Shoes			Each	3
Concrete Encasement			Cu. Yd.	0.6
Concrete Sealer			Sq. Ft.	99
Geocomposite Wall Drain			Sq. Yd.	47
Pipe Underdrains for Structures 4"			Foot	46
Bar Splicers			Each	47


Notes:
Quantity of concrete in end post included with
Concrete Superstructure on sheet 22 of 77.
For details of Bar Splicers, see sheet 71 of 77.

*Epoxy grout n504(E) bars in 1'-3" (min.) drilled holes.
See Section 584 of the Standard Specifications.
Cost of hole drilling and epoxy grouting are
included with "Reinforcement Bars, Epoxy Coated".


E.F. = Each Face
I.F. = Inside Face
O.F. = Outside Face



SECTION H-H




BAR 5501 (E)




BAR W500 (E)


Order bars full length. Cut to fit as shown and place in the bottom of the footing. Place remainder of bars in the top of the footing.




BARS $u_{500}(E)$
and $u_{502}(E)$




BAR v508 (E)




BARS $h_{503}(E)$, $h_{515}(E)$,
& $h_{516}(E)$




BARS $n_{500}(E)$
and $n_{502}(E)$




BAR h505(E)




BARS n 501(E)
and v 504(E)



BARS $h_{508}(E)$, $h_{511}(E)$,
 $h_{513}(E)$, and $v_{507}(E)$



BARS $s_{500}(E)$, $s_{502}(E)$,
 $v_{500}(E)$, and $v_{503}(E)$



BAR U 501(E)

DESIGNED	LAN
CHECKED	MMB
DRAWN	LAN
CHECKED	MMB

**INFRASTRUCTURE
ENGINEERING | INCORPORATED**

33 West Monroe | Suite 1540 | Chicago, IL 60603
P 312.425.9560 | F 312.425.9564 | www.infrastructure-eng.com


SHEET NO.43

77 SHEETS

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
280	81-1(VB-1)R	ROCK ISLAND	503	379
		CONTRACT NO. 64815		
FED. ROAD DIST. NO. - ILLINOIS FED. AID PROJECT				

DESIGNED	LAN
CHECKED	SPK
DRAWN	ASJ
CHECKED	SPK

43-#4 v₅₁₂ (E) bars at 12" cts.



** Elevation at Back of Abutment

See Sheet 47 of 77 for South Wing Wall and Bill of Material.




B.F. = Back Face
E.F. = Each Face
F.F. = Front Face

33 West Monroe | Suite 1540 | Chicago, IL 60603
P 312.425.9560 | F 312.425.9564 | www.infrastructure-eng.com


SHEET NO. 45 77 SHEETS	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	280	81-1(VB-1)R	ROCK ISLAND	503	381
			CONTRACT NO. 64815		
FED. ROAD DIST. NO. - ILLINOIS FED. AID PROJECT					

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION




SOUTH WING WALL ELEVATION
Showing Dimensions


VIEW F-F




SOUTH WING WALL ELEVATION
Showing Reinforcement




SECTION G-G




SECTION H-H




BAR v501 (E)




BAR u502 (E)




BAR h524 (E)




**BARS h523 (E),
h527 (E), & h528 (E)**




**BARS h508 (E), h511 (E),
h529 (E), & v507 (E)**




**BARS n505 (E)
& n507 (E)**




BAR u501 (E)




**BARS n506 (E)
and v512 (E)**




**BARS s503 (E), s504 (E),
v500 (E), & v503 (E)**




BAR s501 (E)



BAR w520 (E)



BAR u500 (E)



BAR v508 (E)

E.F. = Each Face
I.F. = Inside Face
O.F. = Outside Face

BILL OF MATERIAL

Bar	no.	Size	Length	Shape
h500 (E)	7	#5	4'-11"	
h502 (E)	4	#6	45'-11"	
h507 (E)	3	#4	11'-10"	
h508 (E)	10	#4	11'-3"	
h509 (E)	13	#4	12'-0"	
h510 (E)	3	#4	10'-11"	
h511 (E)	1	#4	11'-1"	
h512 (E)	4	#4	10'-4"	
h520 (E)	4	#4	8'-0"	
h521 (E)	4	#4	7'-2"	
h523 (E)	12	#5	9'-8"	
h524 (E)	12	#5	8'-5"	
h525 (E)	12	#5	10'-3"	
h526 (E)	9	#5	6'-1"	
h527 (E)	3	#5	4'-3"	
h528 (E)	3	#5	5'-5"	
h529 (E)	12	#5	11'-3"	
n505 (E)	7	#5	6'-1"	
n506 (E)	11	#6	18'-4"	
n507 (E)	6	#6	9'-2"	
n508 (E)	2	#5	4'-0"	
n509 (E)	14	#9	8'-3"	
p500 (E)	3	#7	7'-0"	
p521 (E)	6	#7	14'-9"	
s501 (E)	15	#4	9'-5"	
s503 (E)	2	#4	7'-0"	
s504 (E)	7	#4	8'-6"	
t520 (E)	14	#5	11'-8"	
u500 (E)	4	#5	9'-6"	
u501 (E)	12	#5	7'-5"	
u502 (E)	12	#5	8'-1"	
v500 (E)	13	#5	3'-9"	
v501 (E)	13	#4	4'-8"	
v503 (E)	34	#5	4'-2"	
v507 (E)	6	#6	7'-1"	
v508 (E)	20	#6	7'-2"	
v510 (E)	26	#6	7'-0"	
v511 (E)	14	#4	6'-6"	
v512 (E)	12	#5	7'-0"	
v513 (E)	43	#4	3'-5"	
w520 (E)	12	#6	9'-10"	
Porous Granular Embankment, Special			Cu. Yd.	100
Structure Excavation			Cu. Yd.	124
Concrete Structures			Cu. Yd.	17.7
Reinforcement Bars, Epoxy Coated			Pouhd	4,010
Furhishing Steel Piles, HP8x36			Foot	99
Driving Piles			Foot	99
Pile Shoes			Each	3
Concrete Encasement			Cu. Yd.	0.6
Concrete Sealer			Sq. Ft.	102
Geocomposite Wall Drain			Sq. Yd.	47
Pipe Underdrain for Structures 4"			Foot	46
Bar Splicers			Each	47

**ABUTMENT B SOUTH WINGWALL
STRUCTURE NO. 081-0024 (W.B.)
STRUCTURE NO. 081-0025 (E.B.)**

DESIGNED	LAN
CHECKED	MMB
DRAWN	LAN
CHECKED	MMB

* Epoxy grout n509 (E) bars in 1'-3" (min.) drilled holes. See Section 584 of the Standard Specifications. Cost of hole drilling and epoxy grouting are included with "Reinforcement Bars, Epoxy Coated".


Notes:
For details of Bar Splicers, see sheet 71 of 77.
Quantity of concrete in end post included with Concrete Superstructure on sheet 22 of 77.





**INFRASTRUCTURE
ENGINEERING** INCORPORATED
33 West Monroe | Suite 1540 | Chicago, IL 60603
P 312.425.9560 | F 312.425.9564 | www.infrastructure-eng.com

SHEET NO. 47	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
77 SHEETS	280	81-1(VB-1)R	ROCK ISLAND	503	383
CONTRACT NO. 64815					
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT					

DEPARTMENT OF TRANSPORTATION



ELEVATION



PLAN



Indicates limits of Concrete Removal

Indicates limits of
Structural Repair of Concrete
(Depth Equal to or Less Than 5 Inches)



Existing reinforcement bars not extending into the new construction shall be cut flush with the concrete left in place unless noted otherwise. Cost included with Concrete Removal.

Existing exposed reinforcement indicated to remain in place shall be cleaned and incorporated into the new construction. Cost included with Concrete Removal.

Repair of the existing abutment shall include but not be limited to the areas shown. The actual areas to be repaired will be determined by the Engineer at the time of construction.

BILL OF MATERIAL


Item	Unit	Total
Concrete Removal	Cu. Yd.	10.2
Structural Repair of Concrete (Depth Equal to or Less Than 5 Inches)	Sq. Ft.	17

ABUTMENT C CONCRETE REMOVAL & REPAIRS
STRUCTURE NO. 081-0024 (W.B.)
STRUCTURE NO. 081-0025 (E.B.)

SHEET NO. 48	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	280	81-1(VB-1)R	ROCK ISLAND	503	384
	77 SHEETS		CONTRACT NO. 64815		
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT					

**INFRASTRUCTURE
ENGINEERING | INCORPORATED**
33 West Monroe | Suite 1540 | Chicago, IL 60603
P 312.425.9560 | F 312.425.9564 | www.infrastructure-eng.com

P:\NP-05\1719\06\10\24-64915-043-About_C_Miden.dgn 8/13/2010 9:54:27 AM



SECTION A-A

* Epoxy grout h500(E), h545(E), h546(E), p540(E), s506(E), v503(E), and w540(E) bars in 9" (min.) drilled holes.
See Section 584 of the Standard Specifications.
Cost of hole drilling and epoxy grouting are included with "Reinforcement Bars, Epoxy Coated".

** Elevation at Back of Abutment
B.F. = Back Face
E.F. = Each Face
F.F. = Front Face

Notes:

Hatched area to be poured after superstructure false work has been removed. Quantity of concrete included with Concrete Superstructure.

Space reinforcement in cap to miss anchor bolts.

For Concrete Encasement details, see sheet 70 of 77.

Reinforcement bars that are to be grouted into existing concrete shall be spaced at least 6" (unless noted) from the edge of existing concrete and shall be embedded into the existing concrete a minimum of 9".

Contractor shall avoid drilling into existing reinforcement.

See Sheet 50 of 77 for Footing Plan, South Wing Wall, and Secs. B-B, C-C, D-D, & E-E.

See Sheet 51 of 77 for South Wing Wall and Bill of Material.


ABUTMENT C WIDENING
STRUCTURE NO. 081-0024 (W.B.)
STRUCTURE NO. 081-0025 (E.B.)

SHEET NO. 49 77 SHEETS	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	280	81-1(VB-1)R	ROCK ISLAND	503	385
			CONTRACT NO. 64815		
FED. ROAD DIST. NO. -		ILLINOIS	FED. AID PROJECT		




INFRASTRUCTURE
ENGINEERING | INCORPORATED
33 West Monroe | Suite 1540 | Chicago, IL 60603
P 312.425.9560 | F 312.425.9564 | www.infrastructure-eng.com


STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION




PARTIAL FOOTING PLAN




SECTION C-C
SECTION E-E




SECTION B-B




SECTION J-J



SOUTH WING WALL ELEVATION
Showing Dimensions




SOUTH WING WALL ELEVATION



SECTION K-K

Notes:
See Sheet 51 of 77 for Bill of Material.
Quantity of concrete in end post included
with Concrete Superstructure on sheet 22 of 77.

* Epoxy grout n503(E), p540(E), s506(E), v503(E), w540(E) bars, and bar splicer in 9" (min.) drilled holes. See Section 584 of the Standard Specifications. Cost of hole drilling and epoxy grouting are included with "Reinforcement Bars, Epoxy Coated".



SECTION D-D

PILE DATA

Type: HP8x36 with Pile Shoes
Nominal Required Bearing: 286 kips
Allowable Resistance Available: 95 kips
Est. Length: 37'
No. Production Piles: 3
No. Test Piles: 0

E.F. = Each Face
I.F. = Inside Face
O.F. = Outside Face

ABUTMENT C FOOTING WIDENING AND SOUTH WING WALL
STRUCTURE NO. 081-0024 (W.B.)
STRUCTURE NO. 081-0025 (E.B.)

DESIGNED	LAN
CHECKED	MMB
DRAWN	LAN
CHECKED	MMB

SHEET NO. 52	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	280	81-1(VB-1)R	ROCK ISLAND	503	386
	77 SHEETS		CONTRACT NO. 64815		
FED. ROAD DIST. NO. - ILLINOIS FED. AID PROJECT					

End Post shall be poured after bridge parapet is in place. Form top surface to match parapet grade.

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

BILL OF MATERIAL

NORTH WING WALL ELEVATION
Showing Dimensions

VIEW F-F

NORTH WING WALL ELEVATION
Showing Reinforcement

SECTION G-G

SECTION H-H

Notes:
Quantity of concrete in end post included with Concrete Superstructure on sheet 22 of 77.
For details of Bar Splicers, see sheet 71 of 77.

*Epoxy grout n544(E) bars in 1'-3" (min.) drilled holes. See Section 584 of the Standard Specifications. Cost of hole drilling and epoxy grouting are included with "Reinforcement Bars, Epoxy Coated".

E.F. = Each Face
I.F. = Inside Face
O.F. = Outside Face

Porous Granular Embankment, Special	Cu. Yd.	89
Structure Excavation	Cu. Yd.	117
Concrete Structures	Cu. Yd.	16.8
Reinforcement Bars, Epoxy Coated	Pound	3,820
Furnishing Steel Piles, HP8x36	Foot	111
Driving Piles	Foot	111
Pile Shoes	Each	3
Concrete Encasement	Cu. Yd.	0.6
Concrete Sealer	Sq. Ft.	91
Geocomposite Wall Drain	Sq. Yd.	43
Pipe Underdrains for Structures 4"	Foot	41
Bar Splicers	Each	42

ABUTMENT C NORTH WINGWALL
STRUCTURE NO. 081-0024 (W.B.)
STRUCTURE NO. 081-0025 (E.B.)

SHEET NO. 51	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	280	81-1(VB-1)R	ROCK ISLAND	503	387
	77 SHEETS			CONTRACT NO. 64815	
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT					




INFRASTRUCTURE
ENGINEERING | INCORPORATED
33 West Monroe | Suite 1540 | Chicago, IL 60603
P 312.425.9560 | F 312.425.9564 | www.infrastructure-eng.com

DESIGNED LAN
CHECKED MMB
DRAWN LAN
CHECKED MMB

SHEET NO. 52 77 SHEETS	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	280	81-1(VB-1)R	ROCK ISLAND	503	388
				CONTRACT NO. 64815	
FED. ROAD DIST. NO. _ ILLINOIS FED. AID PROJECT					

→ A



SECTION A-A

* Epoxy grout h500(E), h515(E), h516(E), p500(E), s531(E), v503(E), and w500(E) bars in 9" (min.) drilled holes.
See Section 584 of the Standard Specifications.
Cost of hole drilling and epoxy grouting are included with "Reinforcement Bars, Epoxy Coated".

** Elevation at Back of Abutment
B.F. = Back Face
E.F. = Each Face
F.F. = Front Face

Notes:



Hatched area to be poured after superstructure false work has been removed. Quantity of concrete included with Concrete Superstructure.
Space reinforcement in cap to miss anchor bolts.
For Concrete Encasement details, see sheet 70 of 77.
Reinforcement bars that are to be grouted into existing concrete shall be spaced at least 6" (unless noted) from the edge of existing concrete and shall be embedded into the existing concrete a minimum of 9".
Contractor shall avoid drilling into existing reinforcement.
See Sheet 54 of 77 for Footing Plan, South Wing Wall, and Secs. B-B, C-C, D-D, & E-E.
See Sheet 55 of 77 for North Wing Wall and Bill of Material.

ABUTMENT D WIDENING
STRUCTURE NO. 081-0024 (W.B.)
STRUCTURE NO. 081-0025 (E.B.)

SHEET NO.53 77 SHEETS	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	280	81-1(VB-1)R	ROCK ISLAND	503	389
			CONTRACT NO. 64815		
FED. ROAD DIST. NO. - ILLINOIS FED. AID PROJECT					

**INFRASTRUCTURE
ENGINEERING** | INCORPORATED
33 West Monroe | Suite 1540 | Chicago, IL 60603
P 312.425.9560 | F 312.425.9564 | www.infrastructure-eng.com


SECTION F-F



TOP VIEW

DESIGNED	LAN
CHECKED	MMB
DRAWN	LAN
CHECKED	MMB


STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION




PARTIAL FOOTING PLAN

PILE DATA


Type: HP8x36 with Pile Shoes
Nominal Required Bearing: 286 kips
Allowable Resistance Available: 95 kips
Est. Length: 30'
No. Production Piles: 3
No. Test Piles: 0




SOUTH WING WALL ELEVATION
Showing Dimensions



SECTION K-K




SECTION C-C
SECTION E-E



SECTION B-B

SECTION J-J



SECTION D-D

Notes:
See Sheet 55 of 77 for Bill of Material.
Quantity of concrete in end post included
with Concrete Superstructure on sheet 22 of 77.

* Epoxy grout n533(E), p500(E), s531(E), v503(E),
w500(E) bars, and bar splicer in 9" (min.) drilled holes.
See Section 584 of the Standard Specifications. Cost
of hole drilling and epoxy grouting are included with
"Reinforcement Bars, Epoxy Coated".

ABUTMENT D FOOTING WIDENING
AND SOUTH WING WALL
STRUCTURE NO. 081-0024 (W.B.)
STRUCTURE NO. 081-0025 (E.B.)


DESIGNED	LAN
CHECKED	MMB
DRAWN	LAN
CHECKED	MMB




INFRASTRUCTURE
ENGINEERING | INCORPORATED
33 West Monroe | Suite 1540 | Chicago, IL 60603
P 312.425.9560 | F 312.425.9564 | www.infrastructure-eng.com

SHEET NO.	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
54	280	81-1(VB-1)R	ROCK ISLAND	503	390
77 SHEETS					
CONTRACT NO. 64815					
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT					


STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION




NORTH WING WALL ELEVATION
Showing Dimensions



NORTH WING WALL ELEVATION
Showing Reinforcement



SECTION G-G




SECTION H-H

Notes:
Quantity of concrete in end post included with
Concrete Superstructure on sheet 22 of 77.
For details of Bar Splicers, see sheet 71 of 77.


*Epoxy grout n534(E) bars in 1'-3" (min.) drilled holes.
See Section 584 of the Standard Specifications.
Cost of hole drilling and epoxy grouting are
included with "Reinforcement Bars, Epoxy Coated".

E.F. = Each Face
I.F. = Inside Face
O.F. = Outside Face


BAR V501(E)




**BARS h503(E), h515(E),
& h516(E)**



**BARS n530(E)
and n532(E)**




BAR h505(E)



**BARS n531(E)
and v504(E)**




**BARS h508(E), h511(E),
h513(E), and v507(E)**




**BARS s530(E), s531(E),
v500(E), and v503(E)**




BAR s501(E)



BAR u501(E)




BAR w500(E)




Order bars full length. Cut to fit
as shown and place in the bottom
of the footing. Use remainder of
bars in the top of the footing.

**BARS u500(E)
and u502(E)**



BAR v508(E)



BILL OF MATERIAL

Bar	No.	Size	Length	Shape
h500(E)	7	#5	4'-11"	
h501(E)	9	#5	5'-3"	
h502(E)	4	#6	45'-11"	
h503(E)	12	#5	8'-5"	
h504(E)	4	#4	8'-8"	
h505(E)	10	#5	8'-10"	
h506(E)	4	#5	8'-0"	
h507(E)	3	#4	11'-10"	
h508(E)	1	#4	11'-3"	
h509(E)	4	#4	12'-0"	
h510(E)	3	#4	10'-11"	
h511(E)	10	#4	11'-1"	
h512(E)	13	#4	10'-4"	
h513(E)	12	#5	11'-3"	
h514(E)	12	#5	12'-0"	
h515(E)	3	#5	4'-2"	
h516(E)	3	#5	5'-8"	
n530(E)	6	#5	5'-10"	
n531(E)	10	#6	17'-6"	
n532(E)	6	#6	8'-9"	
n533(E)	2	#5	3'-9"	
n534(E)	16	#9	8'-1"	
p500(E)	3	#7	7'-0"	
p501(E)	6	#7	14'-4"	
s501(E)	14	#4	9'-5"	
s530(E)	6	#4	8'-5"	
s531(E)	2	#4	6'-11"	
t500(E)	12	#5	9'-9"	
u500(E)	4	#5	9'-6"	
u501(E)	12	#5	7'-5"	
u502(E)	12	#5	8'-1"	
v500(E)	14	#5	3'-9"	
v501(E)	14	#4	4'-8"	
v502(E)	10	#4	6'-5"	
v503(E)	33	#5	4'-2"	
v504(E)	42	#4	3'-3"	
v506(E)	26	#6	7'-1"	
v507(E)	6	#6	7'-1"	
v508(E)	20	#6	7'-2"	
v539(E)	11	#5	6'-8"	
w500(E)	7	#6	9'-4"	
Porous Granular Embankment, Special	Cu. Yd.	100		
Structure Excavation	Cu. Yd.	125		
Concrete Structures	Cu. Yd.	17.7		
Reinforcement Bars, Epoxy Coated	Pound	3820		
Furnishing Steel Piles, HPBx36	Foot	90		
Driving Piles	Foot	90		
Pile Shoes	Each	3		
Concrete Encasement	Cu. Yd.	0.6		
Concrete Sealer	Sq. Ft.	99		
Geocomposite Wall Drain	Sq. Yd.	47		
Pipe Underdrains for Structures 4"	Foot	46		
Bar Splicers	Each	47		

**ABUTMENT D NORTH WING WALL
STRUCTURE NO. 081-0024 (W.B.)
STRUCTURE NO. 081-0025 (E.B.)**


DESIGNED	LAN
CHECKED	MMB
DRAWN	LAN
CHECKED	MMB



**INFRASTRUCTURE
ENGINEERING** INCORPORATED
33 West Monroe | Suite 1540 | Chicago, IL 60603
P 312.425.9560 | F 312.425.9564 | www.infrastructure-eng.com

SHEET NO.	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
77 SHEETS	280	81-1(VB-1)R	ROCK ISLAND	503	391
CONTRACT NO. 64815					
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT					

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION



TYPICAL ABUTMENT DRAINAGE DETAIL

(Dimensions at Right Angle)
*Included in the cost of Pipe Underdrains for Structures.

Note:
All drainage system components shall extend to each wingwall except an outlet pipe shall extend until intersecting with the side slopes. The pipes shall drain into concrete headwalls (See Article 601.05 of the Standard Specifications and Highway Standard 601101).

ABUTMENT DRAINAGE
STRUCTURE NO. 081-0024 (W.B.)
STRUCTURE NO. 081-0025 (E.B.)

DESIGNED	-
CHECKED	-
DRAWN	ASJ
CHECKED	SPK




**INFRASTRUCTURE
ENGINEERING** | INCORPORATED
33 West Monroe | Suite 1540 | Chicago, IL 60603
P 312.425.9580 | F 312.425.9584 | www.infrastructure-eng.com

SHEET NO. 56 77 SHEETS	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	280	81-1(VB-1)R	ROCK ISLAND	503	392
SN 081-0024 (WB), 0025 (EB)		CONTRACT NO. 64815			
FED. ROAD DIST. NO. -		ILLINOIS	FED. AID PROJECT		

--	--	--	--	--

A schematic diagram of a vertical structure, possibly a chimney or tower. The structure is represented by a dashed outline. At the top, there is a horizontal section with a width of 1.0' and a height of 1.0', indicated by a dimension line and the text "1.0' x 1.0'". This section contains a grid of horizontal lines, suggesting a series of internal components or a stack of plates. The main body of the structure is a long, narrow vertical cylinder.



ITEM	UNIT	QUANTITY
Epoxy Crack Injection	Foot	12
Structural Repair of Concrete (Depth Equal to or Less Than 5 Inches)	Sq. Ft.	1


SHEET NO. 57 77 SHEETS	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	280	81-1(VB-1)R	ROCK ISLAND	503	393
				CONTRACT NO. 64815	
FED. ROAD DIST. NO. _ ILLINOIS FED. AID PROJECT					

Indicates limits of Structural Repair of Concrete
(Depth Equal to or Less Than 5 Inches)

Indicates limits of Epoxy Crack Injection

DESIGNED
CHECKED
DRAWN <i>ASJ</i>
CHECKED <i>SPK</i>


STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION



PARTIAL TOP PLAN

BAR n550(E)


BAR h553(E)




END VIEW

PARTIAL ELEVATION
(Looking East)

**BARS s550(E)
& u550(E)**



SECTION A-A



BILL OF MATERIAL

Bar	No.	Size	Length	Shape
h550(E)	6	#4	7'-4"	
h551(E)	56	#4	14'-7"	
h552(E)	2	#4	8'-5"	
h553(E)	2	#4	16'-2"	
h554(E)	80	#5	4'-2"	
n550(E)	29	#6	9'-5"	
n551(E)	4	#6	7'-9"	
p550(E)	5	#6	7'-4"	
s550(E)	9	#4	7'-3"	
t550(E)	16	#8	8'-0"	
u550(E)	33	#4	13'-10"	
v550(E)	19	#6	29'-3"	
v551(E)	22	#6	25'-10"	
w550(E)	9	#5	14'-7"	
w551(E)	18	#5	4'-2"	
Structure Excavation		Cu. Yd.	109	
Concrete Structures		Cu. Yd.	55.4	
Reinforcement Bars, Epoxy Coated		Pound	4,060	

Notes:

Space reinforcement in cap to miss anchor bolts.
Allowable soil bearing pressure is 7,500 psf on sound rock.
Epoxy grout h554(E), n551(E) and w551(E) bars in 9" (min) drilled holes. See Section 584 of the Standard Specifications.
Cost of hole drilling and epoxy grouting is included with Reinforcement Bars, Epoxy Coated.
Reinforcement bars that are to be grouted into existing concrete shall be spaced at least 6" from the edge of existing concrete.
Contractor shall avoid drilling into existing reinforcement.

PIER 1 WIDENING
STRUCTURE NO. 081-0024 (W.B.)
STRUCTURE NO. 081-0025 (E.B.)

DESIGNED	LAN
CHECKED	SPK
DRAWN	LAN
CHECKED	SPK




**INFRASTRUCTURE
ENGINEERING** INCORPORATED
33 West Monroe | Suite 1540 | Chicago, IL 60603
P 312.425.9560 | F 312.425.9564 | www.infrastructure-eng.com

SHEET NO.	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
77 SHEETS	280	81-1(VB-1)R	ROCK ISLAND	503	394
CONTRACT NO. 64815					
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT					


STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION




TOP PLAN




WEST ELEVATION
(Looking East)



NORTH ELEVATION
(Looking South)



SOUTH ELEVATION
(Looking North)



EAST ELEVATION
(Looking West)

BILL OF MATERIAL

ITEM	UNIT	QUANTITY
Epoxy Crack Injection	Foot	20

PIER 2 REPAIRS
STRUCTURE NO. 081-0024 (W.B.)
STRUCTURE NO. 081-0025 (E.B.)

DESIGNED	
CHECKED	
DRAWN	ASJ
CHECKED	SPK

Note:
Repair of the existing pier shall include but not be limited to the areas shown. The actual areas to be repaired will be determined by the Engineer at the time of construction.

~~~~~ Indicates limits of Epoxy Crack Injection



**INFRASTRUCTURE  
ENGINEERING** | INCORPORATED  
33 West Monroe | Suite 1540 | Chicago, IL 60603  
P 312.425.9560 | F 312.425.9564 | www.infrastructure-eng.com

|                               |                                                 |             |             |                 |              |
|-------------------------------|-------------------------------------------------|-------------|-------------|-----------------|--------------|
| SHEET NO. 59<br><br>77 SHEETS | F.A.I.<br>RTE.                                  | SECTION     | COUNTY      | TOTAL<br>SHEETS | SHEET<br>NO. |
|                               | 280                                             | 81-1(VB-1)R | ROCK ISLAND | 503             | 395          |
|                               | CONTRACT NO. 64815                              |             |             |                 |              |
|                               | FED. ROAD DIST. NO. _ ILLINOIS FED. AID PROJECT |             |             |                 |              |

P:\P-05\1719\DCGN\Sheets\Icwa Interstate RR Final Plans\0810024-64815-060-Pier\_2-Widen.dgn




Diagram of a rectangular box with dimensions 2'-2" by 2'-10". The top edge is labeled S550(E) on the left and 2'-7" on the right. The right edge is labeled U550(E) on the right and 5'-10" on the left. The bottom edge is labeled 2'-2" on the left and 2'-11" on the right. The left edge is labeled U550(E) on the left and 5'-10" on the right.

Figure 1 is a technical drawing showing a detail of Pier 2. It illustrates the location of the existing and proposed pile caps. The drawing includes dimensions for the pier height (2'-6") and the vertical spacing of the pile caps (1'-3" each). It also shows the horizontal spacing between the existing and proposed pile caps (9"). Labels indicate the existing pile cap (h551(E)), the existing pile cap (v553(E)), the proposed pile cap (h554(E)), and a note about removing the existing chamfer (Chip to remove existing chamfer typ.).

**PARTIAL ELEVATION**  
(Looking East)

14'-11"

9" min.

16-#9  $\pm$ 551 (E) bars at 1'-0" cfs.

6" min. typ.

8'-6"

4'-3"

4'-3"

9-#5 w550 (E) bars at 1'-0" cfs.

h551 (E)

h554 (E)

9-#5 w551 (E) bars at 12" cfs. top and bottom

h552 (E)

3'-0"

2'-6"

3'-0"

⊙ Pier 2 footing




33 West Monroe | Suite 1540 | Chicago, IL 60603  
P 312.425.9560 | F 312.425.9564 | [www.infrastructure-eng.com](http://www.infrastructure-eng.com)

| Bar                  | No. | Size | Length  | Shape                                                                                 |
|----------------------|-----|------|---------|---------------------------------------------------------------------------------------|
| h550 (E)             | 6   | #4   | 7'-4"   |    |
| h551 (E)             | 56  | #4   | 14'-7"  |    |
| h552 (E)             | 2   | #4   | 8'-5"   |    |
| h553 (E)             | 2   | #4   | 16'-2"  |    |
| h554 (E)             | 80  | #5   | 4'-2"   |    |
| n552 (E)             | 29  | #7   | 9'-8"   |    |
| n553 (E)             | 4   | #7   | 7'-10"  |    |
| p550 (E)             | 5   | #6   | 7'-4"   |    |
| s550 (E)             | 9   | #4   | 7'-3"   |    |
| t551 (E)             | 16  | #9   | 8'-0"   |    |
| u550 (E)             | 33  | #4   | 13'-10" |    |
| v552 (E)             | 19  | #6   | 28'-11" |  |
| v553 (E)             | 22  | #6   | 25'-7"  |  |
| w550 (E)             | 9   | #5   | 14'-7"  |  |
| w551 (E)             | 18  | #5   | 4'-2"   |  |
| Structure Excavation |     |      | Cu. Yd. | 89                                                                                    |
| Concrete Structures  |     |      | Cu. Yd. | 55.1                                                                                  |
| Reinforcement Bars,  |     |      | Pound   | 4,320                                                                                 |
| Epoxy Coated         |     |      |         |                                                                                       |


Space reinforcement in cap to miss anchor bolts.  
Allowable soil bearing pressure is 7,500 psf on sound rock.  
Epoxy grout h554(E), h553(E) and w551(E) bars in 9" (min) drilled holes. See Section 584 of the Standard Specifications.  
Cost of hole drilling and epoxy grouting is included with Reinforcement Bars, Epoxy Coated.  
Reinforcement bars that are to be grouted into existing concrete shall be spaced at least 6" from the edge of existing concrete.  
Contractor shall avoid drilling into existing reinforcement.

|                                                 |                |             |             |                    |              |
|-------------------------------------------------|----------------|-------------|-------------|--------------------|--------------|
| SHEET NO. 60<br><br>77 SHEETS                   | F.A.I.<br>RTE. | SECTION     | COUNTY      | TOTAL<br>SHEETS    | SHEET<br>NO. |
|                                                 | 280            | 81-1(VB-1)R | ROCK ISLAND | 503                | 396          |
|                                                 |                |             |             | CONTRACT NO. 64815 |              |
| FED. ROAD DIST. NO. - ILLINOIS FED. AID PROJECT |                |             |             |                    |              |


STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION




TOP PLAN



WEST ELEVATION  
(Looking East)



SOUTH ELEVATION  
(Looking North)



EAST ELEVATION  
(Looking West)

BILL OF MATERIAL

| ITEM                  | UNIT    | QUANTITY |
|-----------------------|---------|----------|
| Concrete Removal      | Cu. Yd. | 0.1      |
| Epoxy Crack Injection | Foot    | 21       |

PIER 3 CONCRETE REMOVAL & REPAIRS  
STRUCTURE NO. 081-0024 (W.B.)  
STRUCTURE NO. 081-0025 (E.B.)

|             |
|-------------|
| DESIGNED    |
| CHECKED     |
| DRAWN ASJ   |
| CHECKED SPK |

Note:  
Repair of the existing pier shall include but not be limited to the areas shown. The actual areas to be repaired will be determined by the Engineer at the time of construction.


 Indicates limits of Concrete Removal  
 Indicates limits of Epoxy Crack Injection




**INFRASTRUCTURE  
ENGINEERING** | INCORPORATED  
33 West Monroe | Suite 1540 | Chicago, IL 60603  
P 312.425.9560 | F 312.425.9564 | www.infrastructure-eng.com

|                                                 |             |             |             |              |           |
|-------------------------------------------------|-------------|-------------|-------------|--------------|-----------|
| SHEET NO. 61                                    | F.A.I. RTE. | SECTION     | COUNTY      | TOTAL SHEETS | SHEET NO. |
| 77 SHEETS                                       | 280         | 81-1(VB-1)R | ROCK ISLAND | 503          | 397       |
| CONTRACT NO. 64815                              |             |             |             |              |           |
| FED. ROAD DIST. NO. _ ILLINOIS FED. AID PROJECT |             |             |             |              |           |

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION




SECTION C-C




PARTIAL TOP PLAN

See Pier 3 Layout on Sheet 1.



SECTION B-B




BARS h583(E), h584(E),  
h585(E), h586(E), h587(E) & h588(E)

BILL OF MATERIAL


| Bar                              | No. | Size    | Length  | Shape |
|----------------------------------|-----|---------|---------|-------|
| h554(E)                          | 28  | #5      | 4'-2"   |       |
| h580(E)                          | 44  | #5      | 6'-11"  |       |
| h581(E)                          | 3   | #4      | 7'-0"   |       |
| h582(E)                          | 3   | #4      | 6'-10"  |       |
| h583(E)                          | 23  | #4      | 14'-10" |       |
| h584(E)                          | 23  | #4      | 14'-6"  |       |
| h585(E)                          | 1   | #4      | 11'-5"  |       |
| h586(E)                          | 1   | #4      | 11'-1"  |       |
| h587(E)                          | 2   | #4      | 16'-0"  |       |
| p580(E)                          | 5   | #6      | 6'-11"  |       |
| s550(E)                          | 8   | #4      | 7'-3"   |       |
| sp580                            | 1   | #4      | 6'-8"   |       |
| u551(E)                          | 29  | #4      | 8'-2"   |       |
| v580                             | 14  | #8      | 6'-8"   |       |
| v581(E)                          | 12  | #6      | 8'-0"   |       |
| v582(E)                          | 17  | #6      | 27'-6"  |       |
| v583(E)                          | 11  | #6      | 45'-1"  |       |
| Structure Excavation             |     | Cu. Yd. | 11      |       |
| Concrete Structures              |     | Cu. Yd. | 37.9    |       |
| Reinforcement Bars, Epoxy Coated |     | Pounds  | 2,800   |       |
| Reinforcement Bars               |     | Pounds  | 410     |       |
| Drilled Shaft in Soil            |     | Cu. Yd. | 4.4     |       |
| Drilled Shaft in Rock            |     | Cu. Yd. | 1.5     |       |
| Temporary Soil Retention System  |     | Sq. Ft. | 94      |       |

**\*\* BAR v583(E)**


Order bars full length. Cut to fit as shown and place on one face of the pier. Use remainder of bars on the opposite face.



BAR h587(E)



BARS s550(E),  
and u551(E)



SECTION A-A

Notes:  
Space reinforcement in cap to miss anchor bolts.  
Allowable soil bearing pressure is 9,000 psf on sound rock.  
Epoxy grout h554(E) and h580(E) bars in 9" (min) drilled holes.  
See Section 584 of the Standard Specifications. Cost of hole drilling and epoxy grouting is included with Reinforcement Bars, Epoxy Coated.  
Reinforcement bars that are to be grouted into existing concrete shall be spaced at least 6" from the edge of existing concrete. Contractor shall avoid drilling into existing reinforcement.  
Minimum lap for spirals = 2'-0"  
\*\*\*Length is height of spiral.

PIER 3 WIDENING  
STRUCTURE NO. 081-0024 (W.B.)  
STRUCTURE NO. 081-0025 (E.B.)

|          |     |
|----------|-----|
| DESIGNED | LAN |
| CHECKED  | SPK |
| DRAWN    | ASJ |
| CHECKED  | SPK |

\* The quantities and reinforcement detailing are based on the top of shaft and the estimated top of rock elevations shown and may change based on the actual top of rock elevation encountered and final top of shaft elevation.




**INFRASTRUCTURE  
ENGINEERING** INCORPORATED  
33 West Monroe | Suite 1540 | Chicago, IL 60603  
P 312.425.9560 | F 312.425.9564 | www.infrastructure-eng.com


|              |                       |                     |                    |                    |               |
|--------------|-----------------------|---------------------|--------------------|--------------------|---------------|
| SHEET NO. 62 | F.A.I. RTE. 280       | SECTION 81-1(VB-1)R | COUNTY ROCK ISLAND | TOTAL SHEETS 503   | SHEET NO. 398 |
| 77 SHEETS    |                       |                     |                    | CONTRACT NO. 64815 |               |
|              | FED. ROAD DIST. NO. 1 | ILLINOIS            | FED. AID PROJECT   |                    |               |




STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION




TOP PLAN




NORTH ELEVATION  
(Looking South)



WEST ELEVATION  
(Looking East)



SOUTH ELEVATION  
(Looking North)



EAST ELEVATION  
(Looking West)

BILL OF MATERIAL

| ITEM                  | UNIT | QUANTITY |
|-----------------------|------|----------|
| Epoxy Crack Injection | Foot | 7        |

PIER 4 REPAIRS  
STRUCTURE NO. 081-0024 (W.B.)  
STRUCTURE NO. 081-0025 (E.B.)

|             |
|-------------|
| DESIGNED    |
| CHECKED     |
| DRAWN ASJ   |
| CHECKED SPK |

Note:  
Repair of the existing pier shall include but not be limited to the areas shown. The actual areas to be repaired will be determined by the Engineer at the time of construction.

~~~~~ Indicates limits of Epoxy Crack Injection








**INFRASTRUCTURE
ENGINEERING** | INCORPORATED
33 West Monroe | Suite 1540 | Chicago, IL 60603
P 312.425.9560 | F 312.425.9564 | www.infrastructure-eng.com

| | | | | | |
|---|--------------------|-------------|-------------|-----------------|--------------|
| SHEET NO.63


77 SHEETS | F.A.I.
RTE. | SECTION | COUNTY | TOTAL
SHEETS | SHEET
NO. |
| | 280 | 81-1(VB-1)R | ROCK ISLAND | 503 | 399 |
| | CONTRACT NO. 64815 | | | | |
| FED. ROAD DIST. NO. _ ILLINOIS FED. AID PROJECT | | | | | |

1719 7/22/2012 12:40:58 PM P:\5 05\1719\Draw Sheets\New Interstate RR Final Plans\0810024-64815-063-Plan-4-Repair.dgn


STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION



BAR n552(E)




BAR h558(E)



BARS s550(E)

u550(E)



SECTION A-A

BILL OF MATERIAL

| Bar | No. | Size | Length | Shape |
|----------------------------------|-----|------|---------|-------|
| h554(E) | 80 | #5 | 4'-2" | |
| h555(E) | 6 | #4 | 6'-4" | |
| h556(E) | 56 | #4 | 12'-8" | |
| h557(E) | 2 | #4 | 6'-6" | |
| h558(E) | 2 | #4 | 15'-6" | |
| n556(E) | 4 | #6 | 7'-10" | |
| n557(E) | 25 | #6 | 9'-6" | |
| p551(E) | 5 | #6 | 6'-4" | |
| s550(E) | 8 | #4 | 7'-3" | |
| t550(E) | 14 | #8 | 8'-0" | |
| u550(E) | 33 | #4 | 13'-10" | |
| v556(E) | 22 | #6 | 25'-9" | |
| v557(E) | 17 | #6 | 29'-0" | |
| w551(E) | 18 | #5 | 4'-2" | |
| w552(E) | 9 | #5 | 12'-8" | |
| Structure Excavation | | | Cu. Yd. | 95 |
| Concrete Structures | | | Cu. Yd. | 49.2 |
| Reinforcement Bars, Epoxy Coated | | | Pound | 3,760 |

Notes:
Space reinforcement in cap to miss anchor bolts.
Allowable soil bearing pressure is 7,500 psf on sound rock.
Epoxy grout h554(E) n556(E) and w551(E) bars in 9" (min) drilled holes. See Section 584 of the Standard Specifications.
Cost of hole drilling and epoxy grouting is included with Reinforcement Bars, Epoxy Coated.
Reinforcement bars that are to be grouted into existing concrete shall be spaced at least 6" from the edge of existing concrete.
Contractor shall avoid drilling into existing reinforcement.

PIER 4 WIDENING
STRUCTURE NO. 081-0024 (W.B.)
STRUCTURE NO. 081-0025 (E.B.)

| | |
|----------|-----|
| DESIGNED | LAN |
| CHECKED | SPK |
| DRAWN | LAN |
| CHECKED | SPK |

INFRASTRUCTURE ENGINEERING INCORPORATED
33 West Monroe | Suite 1540 | Chicago, IL 60603
P 312.425.9560 | F 312.425.9564 | www.infrastructure-eng.com

| SHEET NO. | F.A.I. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
|---|-------------|-------------|-------------|--------------|-----------|
| 77 SHEETS | 280 | 81-1(VB-1)R | ROCK ISLAND | 503 | 400 |
| CONTRACT NO. 64815 | | | | | |
| FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT | | | | | |