

SUMMARY OF QUANTITIES				ROADWAY FAP 657 (IL 164) 80% FEDERAL 20% STATE	STRUCTURE SN 036-0370 80% FEDERAL 20% STATE
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE	
				ROADWAY 0004	BRIDGE 0011
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	600	600	
78001110	* PAINT PAVEMENT MARKING - LINE 4"	FOOT	1580	1580	
78100100	* RAISED REFLECTIVE PAVEMENT MARKER	EACH	6	6	
78100105	* RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	3	3	
78200410	* GUARDRAIL MARKERS, TYPE A	EACH	16	16	
78201000	* TERMINAL MARKER - DIRECT APPLIED	EACH	4	4	
78300100	PAVEMENT MARKING REMOVAL	SO FT	647	647	
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	9	9	
X2070304	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	91		91
X4401198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SO YD	748	748	
X5020501	UNDERWATER STRUCTURE EXCAVATION PROTECTION - LOCATION 1	EACH	1		1
X6650202	WOVEN WIRE FENCE REMOVAL	FOOT	235	235	
X7016500	TEMPORARY BRIDGE TRAFFIC SIGNALS (SPECIAL)	EACH	1	1	
Z0001002	GUARDRAIL AGGREGATE EROSION CONTROL	TON	200	200	
Z0001900	ASBESTOS BEARING PAD REMOVAL	EACH	32		32
Z0004552	APPROACH SLAB REMOVAL	SO YD	194	194	
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1	
Z0026407	TEMPORARY SHEET PILING	SO FT	928		928
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON- REDIRECTIVE), TEST LEVEL 3	EACH	2	2	
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON- REDIRECTIVE), TEST LEVEL 3	EACH	2	2	
Z0034105	MATERIAL TRANSFER DEVICE	TON	221	221	
Z0046304	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	135		135

* SPECIALTY ITEM

FILE NAME *	USER NAME = rmbrodle	DESIGNED - RMB	REVISED -
S:\237\2008\2370000\11\1645mthCreek\CA\DW\CADD Sheets\0468761-sht-500.dgn	DRAWN - WLL	REVISIONS	REVISED -
PLOT SCALE = 48.0000' / IN.	CHECKED - RJA	DATE	REVISED -
PLOT DATE = 10/23/2010			

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

IL 164 OVER SMITH CREEK
SUMMARY OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
657	116-C)BR-1	HENDERSON	56	4
ILLINOIS FED. AID PROJECT			CONTRACT NO. 68761	