

SCHEDULE OF QUANTITIES

40200800 AGGREGATE SURFACE COURSE, TYPE B						
SIDE	STATION	LENGTH (FOOT)	WIDTH (FOOT)	DEPTH (INCHES)	AREA (CU YD)	QUANTITY (TON)
LT	241+29.30	35.0	25.0	2½	6.81	12.3
LT	242+02.50	35.0	17.0	2½	4.63	8.3
TOTAL =						20.6
USE =						21.0

48101500 AGGREGATE SHOULDERS, TYPE B 6"						
SIDE	STATION	TO	STATION	LENGTH (FOOT)	WIDTH (FOOT)	(SQ YD)
LT	164+00.00	TO	164+80.00	80.0	4.0	35.6
RT	164+00.00	TO	164+80.00	80.0	4.0	35.6
LT	241+43.00	TO	241+87.00	44.0	4.0	19.6
RT	241+43.00	TO	241+87.00	44.0	4.0	19.6
LT	352+18.00	TO	352+82.00	64.0	4.0	28.4
RT	352+18.00	TO	352+82.00	64.0	4.0	28.4
TOTAL =						167.1
USE =						167.0

PAVEMENT MARKING SCHEDULE																
LOCATION	SIDE	78001110						70300100				70301000				
		PAVEMENT MARKING LINE, 4"						SHORT TERM PAVEMENT MARKING				WORK ZONE PAVEMENT MARKING REMOVAL				
		STATION	TO	STATION	(FEET)	(WHITE) (FOOT)	(YELLOW) (FOOT)	STATION	TO	STATION	LENGTH (FOOT)	STATION	TO	STATION	(FOOT)	AREA (SQ FT)
S.N. 074-2007	LT	164+00.00	TO	164+80.00	80.0	80.0	20.0	164+00.00	TO	164+80.00	8.0	164+00.00	TO	164+80.00	8.0	2.6
	RT	164+00.00	TO	164+80.00	80.0	80.0										
S.N. 074-8606	LT	241+43.00	TO	241+87.00	44.0	44.0	10.0	241+43.00	TO	241+87.00	4.0	241+43.00	TO	241+87.00	4.0	1.3
	RT	241+43.00	TO	241+87.00	44.0	44.0										
S.N. 074-2006	LT	352+18.00	TO	352+82.00	64.0	64.0	20.0	352+18.00	TO	352+82.00	8.0	352+18.00	TO	352+82.00	8.0	2.6
	RT	352+18.00	TO	352+82.00	64.0	64.0										
TOTAL =											376.0	50.0			6.6	
USE =											376.0	50.0			7.0	

PROPOSED GUARDRAIL SCHEDULE												
LOCATION	SIDE	APP/DEP	63100169				78201000	63000001				78200410
			TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) FLARED				TERMINAL MARKER DIR. APPLIED	STEEL PLATE BEAM GUARDRAIL TYPE A, 6 FOOT POSTS				GUARDRAIL MARKERS, TYPE A
			STATION	TO	STATION	(EACH)	(EACH)	STATION	TO	STATION	LENGTH (FOOT)	EACH
S.N. 074-2006	RT	APP	350+47.50	TO	350+97.50	1.0	1.0	350+97.50	TO	352+97.50	200.0	4.0
	RT	DEP	352+97.50	TO	353+47.50	1.0	1.0					
	LT	APP	351+62.50	TO	352+12.50	1.0	1.0	352+12.50	TO	354+12.50	200.0	4.0
	LT	DEP	354+12.50	TO	354+62.50	1.0	1.0					
TOTALS =						4.0	4.0			400.0	8.0	
USE =						4.0	4.0			400.0	8.0	

Z0038700 PERM. BENCHMARKS		
LOCATION	BENCHMARKS (EACH)	
S.N. 074-2007	1.0	
S.N. 074-8606	1.0	
S.N. 074-2006	1.0	
TOTAL =		3.0
USE =		3.0