

EARTH EXCAVATION SCHEDULE

LOCATION STATION TO STATION	SIDE	20200100		20400800	
		EARTH EXCAVATION	EARTH EXCAVATION ADJUSTED (25%)	EMBANKMENT	EARTHWORK BALANCE
CU YD					
FAP 685 (IL 9) - STAGE 2					
1212+50 1227+50	RT	3825	2869	3816	(947)
SUB-TOTAL STAGE 2		3825	2869	3816	(947)
FAP 685 (IL 9) - STAGE 3					
1212+50 1219+25	LT	542	407	1362	(955)
1220+20 1224+50	LT	165	124	1215	(1091)
SUB-TOTAL STAGE 3		707	531	2577	(2046)
FAP 685 (IL 9) - MISCELLANEOUS					
1102+00 1110+00	LT	650	486	0	486
1150+75 1152+40	RT	0	0	350	(350)
1151+75 1153+30	LT	0	0	350	(350)
1171+25 1173+85	LT	0	0	200	(200)
SUB-TOTAL MISCELLANEOUS		650	486	900	(414)
TOTALS		5182	3886	7293	(3407)
USE		5185	3886	7293	(3410)

EARTH EXCAVATION (WIDENING)

STATION TO STATION	WIDTH	CU YD
FAP 685 (IL 9) - STAGE 1		
1216+00 1219+15	LT	39
1220+20 1223+50	LT	38
FAP 685 (IL 9) - STAGE 2		
1215+00 1218+60	RT	46
1220+30 1224+00	RT	45
FAP 685 (IL 9) - STAGE 3		
1218+10 1218+60	LT	5
1220+30 1221+60	LT	11
TOTAL		184

NOTE: THIS SCHEDULE USED FOR HOT-MIX ASPHALT WIDENING.

EXCAVATING AND GRADING EXISTING SHOULDER

STATION TO STATION	WIDTH	UNIT
FAP 685 (IL 9)		
1171+25 1173+82	LT	2.6
1190+00 1200+94	RT	10.9
1193+20 1194+39	LT	1.2
1207+20 1209+27	RT	2.1
1207+10 1209+17	LT	2.1
1224+00 1232+47	RT	8.5
1232+05 1234+62	LT	2.6
TOTAL		29.9
USE		30

NOTE: THIS SCHEDULE USED FOR HOT-MIX ASPHALT SHOULDERS.

TREE REMOVAL, ACRES

STATION TO STATION	SIDE	WIDTH	ACRE
FAP 685 (IL 9)			
1218+50 1222+00	LT	10	0.08
1218+75 1224+00	RT	75	0.90
1224+00 1224+75	RT	50	0.09
1225+25 1232+00	RT	40	0.62
TOTAL			1.69
USE			1.7

SEEDING SCHEDULE

STATION TO STATION	SIDE	WIDTH	SEEDING CLASS 2 ACRE	FERTILIZER NUTRIENTS			MULCH METHOD 2 ACRE	AGRICULTURAL LIMESTONE TON
				NITROGEN	PHOSPHORUS	POTASSIUM		
				POUND				
FAP 685 (IL 9)								
1102+00 1110+00	LT	30	0.55	49.6	49.6	49.6	0.55	1.1
1150+75 1152+40	RT	30	0.11	10.2	10.2	10.2	0.11	0.2
1151+75 1153+30	LT	30	0.11	9.6	9.6	9.6	0.11	0.2
1171+25 1173+85	LT	20	0.12	10.7	10.7	10.7	0.12	0.2
1212+50 1213+00	RT	30	0.03	3.1	3.1	3.1	0.03	0.1
1213+00 1218+00	RT	70	0.80	72.3	72.3	72.3	0.80	1.6
1218+00 1218+75	RT	80	0.14	12.4	12.4	12.4	0.14	0.3
1220+10 1224+00	RT	50	0.45	40.3	40.3	40.3	0.45	0.9
1224+00 1224+85	RT	20	0.04	3.5	3.5	3.5	0.04	0.1
1212+35 1213+00	LT	25	0.04	3.4	3.4	3.4	0.04	0.1
1213+00 1219+00	LT	70	0.96	86.8	86.8	86.8	0.96	1.9
1220+30 1222+00	LT	65	0.25	22.8	22.8	22.8	0.25	0.5
1222+00 1223+10	LT	50	0.13	11.4	11.4	11.4	0.13	0.3
1223+10 1224+50	LT	30	0.10	8.7	8.7	8.7	0.10	0.2
TOTALS			3.83	344.8	344.8	344.8	3.83	7.7
USE			4.00	360	360	360	4.00	8

RIPRAP SCHEDULE

STATION TO STATION	SIDE	WIDTH	28100707	28200200
			STONE DUMPED CLASS A4	FILTER FABRIC
SQ YD				
FAP 685 (IL 9)				
1188+65 1188+85	RT	10.0	22.2	22.2
1212+33 1213+15	LT	13.0	124.2	124.2
1212+52 1213+65	RT	13.0	167.6	167.6
1220+10 1224+90	RT	VARIES	1855.0	1855.0
1220+31 1222+07	LT	16.0	289.8	289.8
1225+21 1232+56	RT	VARIES	2000.0	2000.0
1226+30 1226+40	LT	12.5	13.9	13.9
1232+05 1234+60	LT	30.0	850.0	850.0
TOTALS			5322.6	5322.6
USE			5323	5323

NOTE: SEE STRUCTURE PLANS FOR ADDITIONAL FILTER FABRIC AND STONE RIPRAP, CLASS A4 QUANTITIES.

EROSION CONTROL BLANKET

STATION TO STATION	SIDE	WIDTH	25100630
SQ YD			
FAP 685 (IL 9)			
1213+65 1215+50	RT	12	246.7
1218+00 1218+97	LT	12	129.3
1222+70 1224+50	LT	12	240.0
TOTAL			616.0
USE			616

EROSION CONTROL SCHEDULE

ITEM	UNIT	TOTAL
TEMPORARY EROSION CONTROL SEEDING	POUND	800
PERIMETER EROSION BARRIER	FOOT	500
INLET AND PIPE PROTECTION	EACH	4
AGGREGATE (EROSION CONTROL)	TON	100

THE SCHEDULE FOR EROSION CONTROL IS AN ESTIMATED QUANTITY. IT MAY BE REDUCED, INCREASED, OR DELETED BY THE ENGINEER BASED ON ACTUAL FIELD CONDITIONS. NO WORK INVOLVING THIS ESTIMATED QUANTITY SHALL BE PERFORMED WITHOUT THE DIRECTION AND APPROVAL OF THE ENGINEER.