


Note A:  
For detail of Temporary Bracing for Stage I Construction, see sheet 16 of 23.

**FRAMING PLAN**



\* Use  $1\frac{3}{16}$ " x  $1\frac{3}{4}$ " slotted holes in  $\frac{1}{2}$ " x 6" Connecting PL in diaphragm at location "A", and  $1\frac{3}{16}$ " x  $2\frac{1}{8}$ " slotted holes in  $\frac{1}{2}$ " x 6" Connecting PL in diaphragm at location "B". Provide  $\frac{5}{16}$ " plate washer for slotted holes. Bolts shall be finger-tightened prior to the deck pour for Stage II Construction and then be fully tightened after completion of the pour. Bolts shall start at the bottom of the slot.

Note:  
All cross frames or diaphragms shall be installed as steel is erected and secured with erection pins and bolts except as otherwise noted. Individual cross frames or diaphragms at supports may be temporarily disconnected to install bearing anchor rods.

FILE NAME =	USER NAME =	DESIGNED RJP	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	FRAMING PLAN STRUCTURE NO. 034-0528	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	CHECKED ADL	REVISIED -	685			(117,118)RS-4,119RS-1; 118B-1	HANCOCK	101	56	
PLOT SCALE =	DRAWN RJP	REVISIED -		SHEET NO. 14 OF 23 SHEETS		CONTRACT NO. 72B05		ILLINOIS FED. AID PROJECT		
PLOT DATE =	CHECKED ADL	REVISIED -				Klingner & Associates P.C.				