			TOTAL	URBAN ANDREW ROAD 100% State 0005	RURAL IL 124 100% State 0005	RURAL Shoulder 100% State 0021
20200600	EXCAVATING AND GRADING EXISTING SHOULDER	UNIT	566	78	488	
35800100	PREPARATION OF BASE	SQ YD	2,079	551	1,528	
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	130	27	103	
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	29.4	6.7	22.7	
40600300	AGGREGATE (PRIME COAT)	TON	147.8	28.3	119.5	
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	3143.8	624	2519.8	
40600895	CONSTRUCTING TEST STRIP	EACH	1	0.5	0.5	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	1065.3	704	361.3	
40600990	TEMPORARY RAMP	SQ YD	40	26.7	13.3	
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	8338.1	1475.4	6862.7	
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	578	185	393	
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	210.9	190	20.9	
44004250	PAVED SHOULDER REMOVAL	SQ YD	200		200	
48203023	HOT-MIX ASPHALT SHOULDERS, 6 1/2"	SQ YD	24410.6			24410.6
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	535			535
*63000001	STEEL PLATE BEAM GUARD RAIL, TYPE A, 6 FOOT POSTS	FOOT	75		75	
*63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	16		16	
63200310	GUARDRAIL REMOVAL	FOOT	1275		1275	
64200105	SHOULDER RUMBLE STRIPS	FOOT	48958		48958	

1 Rev. 1-10-11

*Specialty Items

Rev.

FILE NAME = c:\pw_work\pwidot\laughlinrl\d0217723\D672D56-sht-S00.dgn	USER NAME = laughlinrl	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 100.0000 ' / in.	CHECKED -	REVISED -
	PLOT DATE = Oct-26-2010 07:06:09AM	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: | SHEET NO. OF SHEETS | STA. TO STA.

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
618	(B)RS-4, (0-15D)RS-2	SANGAMON	32	3

CONTRACT NO. 72D56

ILLINOIS FED. AID PROJECT