

SUMMARY OF QUANTITIES			90% FED. / 10% STATE	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	CLAY COUNTY	EFFINGHAM COUNTY	
				0004	0004	0014
20800150	TRENCH BACKFILL	CU YD	5.5		5.5	
31101810	SUB-BASE GRANULAR MATERIAL, TYPE B 12"	SQ YD	14032	1737	12295	
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	23886	1710	22176	
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	671		671	
40600895	CONSTRUCTING TEST STRIP	EACH	2	0.1	1.9	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	772	213	559	
40600990	TEMPORARY RAMP	SQ YD	265	31	234	
40603090	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N90	TON	10847	1237	9610	
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	3087	396	2691	
40603153	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, STONE MATRIX ASPHALT, N80	TON	8684	431	8253	
40603245	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N105	TON	8449	420	8029	
40603315	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N70	TON	1343		1343	
40603550	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N105	TON	600		600	
40702006	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 16 1/4"	SQ YD	14032	1737	12295	
44000100	PAVEMENT REMOVAL	SQ YD	14032	1737	12295	
44000151	HOT-MIX ASPHALT SURFACE REMOVAL, 1/2"	SQ YD	75089		75089	
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	34869	356	34513	
44000173	HOT-MIX ASPHALT SURFACE REMOVAL, 6"	SQ YD	24544	2431	22113	
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	30		30	
44004250	PAVED SHOULDER REMOVAL	SQ YD	17636	3770	13866	
44201811	CLASS D PATCHES, TYPE I, 14 INCH	SQ YD	20		20	
44201815	CLASS D PATCHES, TYPE II, 14 INCH	SQ YD	400		400	
44201819	CLASS D PATCHES, TYPE III, 14 INCH	SQ YD	380		380	
44201821	CLASS D PATCHES, TYPE IV, 14 INCH	SQ YD	320		320	
48101200	AGGREGATE SHOULDERS, TYPE B	TON	2104	210	1894	
48203049	HOT-MIX ASPHALT SHOULDERS, 13"	SQ YD	17636	3770	13866	
48203100	HOT-MIX ASPHALT SHOULDERS	TON	8659	594	8065	
50102400	CONCRETE REMOVAL	CU YD	26.5			26.5
50157300	PROTECTIVE SHIELD	SQ YD	476			476
50300100	FLOOR DRAINS	EACH	40			40
50300255	CONCRETE SUPERSTRUCTURE	CU YD	26.6			26.6

SUMMARY OF QUANTITIES			90% FED. / 10% STATE	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	CLAY COUNTY	EFFINGHAM COUNTY	
				0004	0004	0014
50300260	BRIDGE DECK GROOVING	SQ YD	1587			1587
50300300	PROTECTIVE COAT	SQ YD	1689			1689
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	3640			3640
50800515	BAR SPLICERS	EACH	56			56
52000110	PREFORMED JOINT STRIP SEAL	FOOT	177			177
54213660	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"	EACH	1		1	
54390130	INSERTION CULVERT LINER 16"	FOOT	54	8	46	
550A0070	STORM SEWERS, CLASS A, TYPE 1 15"	FOOT	42		42	
60100078	SHOULDER REMOVAL AND REPLACEMENT 12 1/2"	FOOT	17,827	1553	16,274	
60100073	SHOULDER REMOVAL AND REPLACEMENT 10"	FOOT	6.7		6.7	
60107700	PIPE UNDERDRAINS 6"	FOOT	27572	3000	24572	
60108200	PIPE UNDERDRAINS 6" (SPECIAL)	FOOT	1349	190	1159	
60237000	INLETS, TYPE A, TYPE 15 FRAME AND LID	EACH	1		1	
60600096	CLASS SI CONCRETE (OUTLET PROTECTOR)	CU YD	85.5	12	73.5	
60608600	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.06	FOOT	30		30	
60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SQ FT	240		240	
* 63000001	STEEL PLATE BEAM GUARD RAIL, TYPE A, 6 FOOT POSTS	FOOT	2312.5	262.5	2050	
* 63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	1		1	
* 63100089	TRAFFIC BARRIER TERMINAL, TYPE 6B	EACH	3	1	2	
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	7	1	6	
* X6310218	TRAFFIC BARRIER TERMINAL, TYPE 6 (SPECIAL)	EACH	5		5	
63200310	GUARDRAIL REMOVAL	FOOT	2950	375	2575	
63400105	GUARD POSTS	EACH	72	6	66	
63500105	DELINEATORS	EACH	164	5	159	
X6350120	DELINEATOR REMOVAL	EACH	124	5	119	
64200105	SHOULDER RUMBLE STRIPS	FOOT	58836	3786	55050	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	9	1	8	
67100100	MOBILIZATION	L SUM	1	0.05	0.95	
70100207	TRAFFIC CONTROL AND PROTECTION, STANDARD 701402	EACH	8	2	4	2
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	2		2	
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1		1	

FILE NAME =	USER NAME = teasleyck	DESIGNED -	REVISED -
ci:\pw_work\pwidot\teasleyck\d0148697\0774417-sht-soq.dgn		DRAWN -	REVISED -
PLOT SCALE = 100.0000' / IN.		CHECKED -	REVISED -
PLOT DATE = 10/22/2010		DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57	(13-1)R&(25-6-1)R	.	44	3
CONTRACT NO. 74417				
ILLINOIS FED. AID PROJECT				

• Clay, Effingham