

## INDEX OF SHEETS

<u>SHEET NO.</u>	<u>DESCRIPTION</u>
1	TITLE SHEET
2	INDEX OF SHEETS, GENERAL NOTES, LOCATION DESCRIPTIONS
3	SUMMARY OF QUANTITIES
4-12	EXISTING STRUCTURE PLANS

THE FOLLOWING STANDARDS ARE A PART OF THESE PLANS AND ARE INCLUDED AFTER SHEET NO. 12.

STANDARD	701001-02	TYPICAL APPLICATION OF TRAFFIC CONTROL DEVICES
STANDARD	701006-03	TYPICAL APPLICATION OF TRAFFIC CONTROL DEVICES
STANDARD	701101-02	TYPICAL APPLICATION OF TRAFFIC CONTROL DEVICES
STANDARD	701106-02	TYPICAL APPLICATION OF TRAFFIC CONTROL DEVICES
STANDARD	701400-05	TYPICAL APPLICATION OF TRAFFIC CONTROL DEVICES
STANDARD	701406-06	TYPICAL APPLICATION OF TRAFFIC CONTROL DEVICES
STANDARD	701901-01	TYPICAL APPLICATION OF TRAFFIC CONTROL DEVICES

## GENERAL NOTES

THIS SECTION SHALL BE CONSTRUCTED IN ACCORDANCE WITH THE PLANS, THE "STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION" ADOPTED JANUARY 1, 2007; THE SUPPLEMENTAL SPECIFICATIONS, THE RECURRING SPECIAL PROVISIONS, AND THE SPECIAL PROVISIONS INCLUDED IN THE PROPOSAL.

THE PROPOSED PROJECT IS LOCATED AT 3 LOCATIONS ON I-57 IN COLES COUNTY.

THE WORK INCLUDED IN THIS SECTION CONSISTS OF CLEANING AND PAINTING BRIDGES AT 3 LOCATIONS AS SPECIFIED IN THE PLANS AND SPECIAL PROVISIONS.

THE STRUCTURAL STEEL SHALL BE CLEANED AND PAINTED AS SPECIFIED IN THE SPECIAL PROVISIONS.

ALL DECK DRAINS SHALL BE PAINTED ACCORDING TO THE REQUIREMENTS OF PAINT SYSTEM 1 - OZ/E/U. ANY DAMAGE CAUSED BY THE CONTRACTOR SHALL BE REPAIRED AT THEIR OWN EXPENSE AND NO ADDITIONAL COMPENSATION WILL BE ALLOWED.

ALL TRASH AND PAINTING DEBRIS, EXCLUDING WASTE BARRELS OR ROLL-OFF DUMPSTERS, SHALL BE REMOVED BEFORE BEGINNING WORK AT ANOTHER LOCATION.

ONLY STRUCTURAL STEEL IS TO BE PAINTED. ALL OTHER SURFACES WILL BE PROTECTED FROM BEING PAINTED. ALL PAINT AND OVERSPRAY WILL BE REMOVED AT THE CONTRACTOR'S EXPENSE.

THE SSPC QP1 AND QP2 PAINTING CONTRACTOR CERTIFICATION WILL BE REQUIRED FOR THIS PROJECT.

## BRIDGE INFORMATION & LOCATIONS

LOCATION #1

ROUTE: FAI 57  
MARKED: I-57  
SECTION: 15-24HB-1  
STATION: 1197+38.95  
STRUCTURE NUMBER: 015-0033

TYPE OF BRIDGE: Wide Flange I Beams-4 Spans (5 Beams)  
LOCATION: East of Humboldt  
FEATURE CARRIED/SPANNED: CH 16 over I-57

COLOR OF THE FINISH COAT SHALL BE GRAY, MUNSELL 5B 7/1.

Cleaning and painting of the existing structural steel shall be as specified in the special provision for "Cleaning and Painting Existing Steel Structures". All structural steel, including beams, bearings and diaphragms, shall be cleaned by SSPC-SP10-Near White Metal Blast Cleaning.

The designated areas cleaned per Near White Metal Blast Cleaning - SSPC-SP10 shall be painted according to the requirements of Paint System 1 - OZ/E/U.

One air monitor will be required at this location.

LOCATION #2

ROUTE: FAI 57  
MARKED: I-57  
SECTION: 15-25HB  
STATION: 1281+52.63  
STRUCTURE NUMBER: 015-0045

TYPE OF BRIDGE: Wide Flange I Beams-4 Spans (5 Beams)  
LOCATION: 2 Miles South of the Douglas County Line  
FEATURE CARRIED/SPANNED: TR 23 over I-57

COLOR OF THE FINISH COAT SHALL BE GRAY, MUNSELL 5B 7/1 FOR ALL BEAMS.

Cleaning and painting of the existing structural steel shall be as specified in the special provision for "Cleaning and Painting Existing Steel Structures". All structural steel, including beams, bearings and diaphragms, shall be cleaned by SSPC-SP10-  
Near White Metal Blast Cleaning.

The designated areas cleaned per Near White Metal Blast Cleaning - SSPC-SP10 shall be painted according to the requirements of Paint System 1 - OZ/E/U.

Two air monitors will be required at this location.

LOCATION #3

ROUTE: FAI 57  
MARKED: I 57  
SECTION: 15, 21-25HB-1  
STATION: 1386+91  
STRUCTURE NUMBER: 015-0063

TYPE OF BRIDGE: Wide Flange I Beams-4 Spans (5 Beams)  
LOCATION: Coles/Douglas County Line  
FEATURE CARRIED/SPANNED: TR 13 over I-57

COLOR OF THE FINISH COAT SHALL BE GRAY, MUNSELL 5B 7/1 FOR ALL BEAMS.

Cleaning and painting of the existing structural steel shall be as specified in the special provision for "Cleaning and Painting Existing Steel Structures". All structural steel, including beams, bearings and diaphragms, shall be cleaned by SSPC-SP10-Near White Metal Blast Cleaning.

The designated areas cleaned per Near White Metal Blast Cleaning - SSPC-SP10 shall be painted according to the requirements of Paint System 1 - QZ/E/U.

Two air monitors will be required at this location.

				• D7 BRIDGE PAINTING 2011-1													
FILE NAME =	USER NAME = swrtzrw	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION				INDEX OF SHEETS				F.A.I.	SECTION	COUNTY	TOTAL	SHEET	
c:\pwwork\pwidist\swrtzrw\d8209782\d774456-sht-index.dgn	DRAWN -	REVISED -	REVISED -					GENERAL NOTES & LOCATIONS				57	*	COLES	12	2	
PLOT SCALE = 40.0000' / IN.	CHECKED -	REVISED -	REVISED -					CONTRACT NO. 74496									
PLOT DATE = 10/1/2010	DATE -	REVISED -	REVISED -														
								SCALE: NA	SHEET NO. 1	OF 1	SHEETS	STA.	TO STA.	ILLINOIS DEPT. OF TRANSPORTATION PROJECT			