

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES

90% FED.
 10% STATE
 TOTAL
 QUANTITIES

CONSTRUCTION TYPE CODE

CODE NO	ITEM	UNIT	0005	0011	0021	0021	0005
44004250	PAVED SHOULDER REMOVAL	SQ YD	3343	3343			
44200569	CLASS A PATCHES, TYPE III, 11 INCH	SQ YD	25	25			
44200571	CLASS A PATCHES, TYPE IV, 11 INCH	SQ YD	586	586			
44200970	CLASS B PATCHES, TYPE II, 10 INCH	SQ YD	495	213			282
44200974	CLASS B PATCHES, TYPE III, 10 INCH	SQ YD	18	18			
44200976	CLASS B PATCHES, TYPE IV, 10 INCH	SQ YD	387	387			
44213200	SAW CUTS	FOOT	5819	3850			1969
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	4028	4028			
48100500	AGGREGATE SHOULDERS, TYPE A 6"	SQ YD	745	745			
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	183	47			136
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	3685	3685			
48203100	HOT-MIX ASPHALT SHOULDERS	TON	844	171			673
50102400	CONCRETE REMOVAL	CU YD	23.2	23.2			
50104650	SLOPE WALL REMOVAL	SQ YD	372.7	372.7			
50104720	REMOVAL OF EXISTING CONCRETE DECK	EACH	1	1			
50157300	PROTECTIVE SHIELD	SQ YD	106	106			
50200100	STRUCTURE EXCAVATION	CU YD	332	332			
50300225	CONCRETE STRUCTURES	CU YD	190.5	190.5			
50300255	CONCRETE SUPERSTRUCTURE	CU YD	225.5	225.5			
50300260	BRIDGE DECK GROOVING	SQ YD	513	513			
50300300	PROTECTIVE COAT	SQ YD	648	648			
XX008423	PRECAST CONCRETE LAGGING	SQ FT	863	863			
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1	1			
50500505	STUD SHEAR CONNECTORS	EACH	1,790	1,790			
Z0007118	UNTREATED TIMBER LAGGING	SQ FT	1049	1049			
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	87,270	87,270			
50800515	BAR SPLICERS	EACH	32	32			
50901730	BRIDGE FENCE RAILING	FOOT	223	223			
51200957	FURNISHING METAL SHELL PILES 12" X 0.250"	FOOT	1068	1068			
Z0026402	FURNISHING SOLDIER PILES (HP SECTION)	FOOT	1,517	1,517			
51202305	DRIVING PILES	FOOT	1,068	1,068			
51203200	TEST PILE METAL SHELLS	EACH	3	3			
51500100	NAME PLATES	EACH	1	1			
52100010	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	4	4			
52100520	ANCHOR BOLTS, 1"	EACH	14	14			
52100530	ANCHOR BOLTS, 1 1/4"	EACH	12	12			

FILE NAME =
 USER NAME = burnsdeem
 DESIGNED -
 DRAWN -
 PLOT SCALE = 50.0000' / IN.
 PLOT DATE = 8/11/2010

REVISED -
 REVISED -
 REVISED -
 REVISED -

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
 SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
64	82-5K-2	ST CLAIR	162	6
CONTRACT NO. 76D59				
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				