

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES

90% FED.
 10% STATE
 TOTAL
 QUANTITIES

CONSTRUCTION TYPE CODE

CODE NO	ITEM	UNIT	QUANTITIES	0005	0011	0021	0021	0005
81603035	UNIT DUCT, 600V, 2-1C NO. 6, 1/C NO. 6 GROUND, (XLP-TYPE USE), 1" DIA. POLYETHYLENE	FOOT	1581			1581		
81603065	UNIT DUCT, 600V, 2-1C NO. 2, 1/C NO. 2 GROUND, (XLP-TYPE USE), 1 1/4" DIA. POLYETHYLENE	FOOT	2218			2218		
81702415	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 3-1/C NO. 6	FOOT	60			60		
81800190	AERIAL CABLE, 2-1/C NO. 2 WITH MESSENGER WIRE	FOOT	2500			2500		
81800200	AERIAL CABLE, 2-1/C NO. 4 WITH MESSENGER WIRE	FOOT	3500			3500		
81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	5623			4772	851	
82102400	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 400 WATT	EACH	4			4		
83057220	LIGHT POLE, WOOD, 40 FOOT, CLASS 4	EACH	6			6		
83057440	LIGHT POLE, WOOD, 80 FOOT, CLASS 4	EACH	4			4		
83060550	LIGHT POLE, GALVANIZED STEEL, 50 FT. M. H., 15 FT. MAST ARM	EACH	4			4		
83600300	LIGHT POLE FOUNDATION, 30" DIAMETER	FOOT	85			85		
83800205	BREAKAWAY DEVICE, TRANSFORMER BASE, 15 INCH BOLT CIRCLE	EACH	4			4		
84200804	REMOVAL OF POLE FOUNDATION	EACH	9			9		
84400105	RELOCATE EXISTING LIGHTING UNIT	EACH	9			9		
87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	2419				2419	
87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	4591				4591	
87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	9106				9106	
87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2 C	FOOT	60				60	
87502700	TRAFFIC SIGNAL POST, ALUMINUM 16 FT.	EACH	3				3	
87700150	STEEL MAST ARM ASSEMBLY AND POLE, 22 FT.	EACH	1				1	
87700260	STEEL MAST ARM ASSEMBLY AND POLE, 44 FT.	EACH	1				1	
87700280	STEEL MAST ARM ASSEMBLY AND POLE, 48 FT.	EACH	1				1	
87800100	CONCRETE FOUNDATION, TYPE A	FOOT	9				9	
87800200	CONCRETE FOUNDATION, TYPE D	FOOT	7				7	
87800400	CONCRETE FOUNDATION, TYPE E 30-INCH DIAMETER	FOOT	10				10	
87800415	CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	FOOT	26				26	
87900200	DRILL EXISTING HANDHOLE	EACH	9				9	
88020160	SIGNAL HEAD, POLYCARBONATE, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	7				7	

**Specialty Items*

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
64	82-5K-2	ST CLAIR	162	10

CONTRACT NO. 76D59

FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT

FILE NAME =	USER NAME = burnsideem	DESIGNED -	REVISED -
ca:\pw_work\paw\dot\burnsideem\d0166363\d076e99-sh-tr-plan.dgn		DRAWN -	REVISED -
		PLOT SCALE = 50.0000' / IN.	CHECKED -
		PLOT DATE = 8/11/2010	DATE -

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.