

RESURFACING SCHEDULE					
LOCATION		BITUMINOUS MATERIALS (PRIME COAT)	AGGREGATE (PRIME COAT)	LEVELING BINDER (MACHINE METHOD) IL-9.5FG, N90, 1"	POLYMERIZED HMA SURFACE COURSE, 1 1/2"
LOCATION		(TON)	(TON)	(TON)	(TON)
RAMP "A"					
0+89	TO 10+67.1	1.1	5.2	98	146
RAMP "B"					
6+80	TO 14+27.74	1.1	5.5	102	154
RAMP "C"					
4+78.5	TO 13+09.61	1.0	4.4	83	124
RAMP "D"					
1+93	TO 10+14	0.9	4.4	82	123
RAMP "E"					
2+55.5	TO 10+51.7	1.0	4.6	86	129
TOTAL:		5.1	24.1	451	676

SHOULDER RESURFACING SCHEDULE					
LOCATION		BITUMINOUS MATERIALS (PRIME COAT)	AGGREGATE (PRIME COAT)	AGGREGATE WEDGE SHOULDER, TYPE B	HMA SHOULDERS, 2 1/2"
LOCATION		(TON)	(TON)	(TON)	(TON)
RAMP "A"					
0+89	TO 10+67.1	0.7	3.3	31.7	152
RAMP "B"					
6+80	TO 14+27.74	0.5	2.5	24.2	118
RAMP "C"					
4+78.5	TO 13+09.61	0.6	2.8	26.9	129
RAMP "D"					
1+93	TO 10+14	0.6	2.7	26.6	128
RAMP "E"					
2+55.5	TO 10+51.7	0.7	3.1	25.8	146
TOTAL:		3.0	14.4	136.0	673

TEMPORARY RAMPS	
LOCATION	TEMPORARY RAMPS (SQ YD)
RAMP "A"	
10+67.1	8.9
RAMP "B"	
6+80	9.4
RAMP "C"	
4+78.5	8.9
RAMP "D"	
10+14	8.9
RAMP "E"	
10+51.7	8.9
TOTAL:	45

PAVEMENT MARKING SCHEDULE									
LOCATION			TEMPORARY PAVEMENT MARKING		PREFORMED PLASTIC PAVEMENT MARKING, TYPE B-INLAID		SHORT-TERM PAVEMENT MARKING (3 LIFTS) (WHITE)	SHORT-TERM PAVEMENT MARKING (3 LIFTS) (YELLOW)	WORKZONE PAVEMENT MARKING REMOVAL
			LINE, 4" SOLID (WHITE)	LINE, 4" SOLID (YELLOW)	LINE, 4" SOLID (WHITE)	LINE, 4" SOLID (YELLOW)			
STA	TO	STA	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	SQ FT
RAMP "A"									
0+89	TO	10+67.1	978	978	978	978	267	267	59
RAMP "B"									
6+80	TO	14+27.74	748	748	748	748	204	204	45
11+90	TO	14+27.74	233		233		64		7
RAMP "C"									
4+78.5	TO	13+09.61	831	831	831	831	227	227	50
RAMP "D"									
1+93	TO	10+14	821	821	821	821	224	224	50
RAMP "E"									
2+55.5	TO	10+51.7	796	796	796	796	217	217	48
SUB TOTAL:			4407	4174	4407	4174	1202	1138	260
TOTAL:			8581		8581		2340		260

PCC SURFACE REMOVAL - BUTT JOINTS	
LOCATION	BUTT JOINTS (SQ YD)
RAMP "A"	
10+67.1	53
RAMP "B"	
6+80	57
RAMP "C"	
4+78.5	53
RAMP "D"	
10+14	53
RAMP "E"	
10+51.7	53
TOTAL:	270

FILE NAME =	USER NAME = burnsideem	DESIGNED -	REVISED -
ct:\p\work\p\sidot\burnsideem\d0166363\876d59-sh-t-plan2.dgn		DRAWN -	REVISED -
		CHECKED -	REVISED -
		DATE -	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: \_\_\_\_\_ SHEET NO. \_\_\_ OF \_\_\_ SHEETS STA. \_\_\_\_\_ TO STA. \_\_\_\_\_

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
64	82-5k-2	ST. CLAIR	162	121
CONTRACT NO. 76D59				
FED. ROAD DIST. NO. - ILLINOIS FED. AID PROJECT				