
LEGEND



SUMMARY OF QUANTITIES - NIU FAR WEST CAMPUS ROADWAY EXPANSION						
ELECTRIC SERVICE INSTALLATION	EACH	1				
LUMINAIRE, (SPECIAL)	EACH	88				
LIGHT POLE, ALUMINUM 30 FT. M.H., 8FT MAST ARM	EACH	88				
CONDUIT IN TRENCH, 1" DIA., PVC	FOOT	14,630				
CONDUIT IN TRENCH, 2" DIA. , PVC	FOOT	25				
CONDUIT PUSHED, 1" DIA., GALVANIZED STEEL	FOOT	575				
ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C, NO. 10	FOOT	75,615				
ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C, NO. 4	FOOT	1,915				
ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C, NO. 3/0	FOOT	130				
ELECTRIC CABLE IN CONDUIT, 15KV (EPR-TYPE) 1/C, NO.2/0	FOOT	5,745				
TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	16,655				
ELECTRIC MANHOLE, 6FT X 10FT X 7FT, WITH 30IN. FRAME AND						
COVER	EACH	5				
TRANSFORMER, 13.2KV - 480/277V, 75 KVA	EACH	2				
LIGHTING CONTROLLER, BASE MOUNTED, 480 VOLT, 200 AMP	EACH	2				
LIGHT POLE FOUNDATION	EACH	88				
CONDUIT ENCASED, CONCRETE, 5" DIA., PVC, 2 WIDE X 1 HIGH	FOOT	1,860				
CONDUIT ENCASED, REINFORCED CONCRETE, 5" DIA., PVC 2						
WIDE X 1 HIGH	FOOT	290				
CONDUIT ENCASED, REINFORCED CONCRETE, 5" DIA., PVC 3						
WIDE X 2 HIGH	FOOT	210				

## LIGHTING GENERAL NOTES:


- IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO MARK THE PROPOSED LOCATIONS OF ALL LIGHT POLES FOR EXAMINATION AND CONFIRMATION WITH THE ENGINEER AT THE PRE CONSTRUCTION INSPECTION. THE EXACT LOCATIONS OF ALL ITEMS SHALL BE CONFIRMED WITH THE ENGINEER PRIOR TO STARTING WORK.
- THE CONTRACTOR SHALL MAKE SPECIAL NOTE OF THE SPECIFIED REQUIREMENTS FOR BURIED WARNING TAPE, SPECIFIED AS PART OF THE "TRENCH AND BACKFILL FOR ELECTRICAL WORK". THE INSTALLATION OF THE TAPE SHALL BE INSPECTED BY THE ENGINEER PRIOR TO BACKFILLING OR DURING PLOWING OPERATIONS, AS APPLICABLE.

## PLAN KEYED NOTES:

- 1 PROVIDE 4#10, #10G., 1"C.
- 2 PROVIDE 2#10, #10G., 1"C.
- 3 EXTEND DUCT 5'-0" PAST BACK OF CURB. EXTEND PVC CONDUITS 1'-0" BEYOND CONCRETE ENCASEMENT AND CAP FOR FUTURE EXTENSION. EXTEND REBAR 1'-0" BEYOND CONCRETE ENCASEMENT AND WRAP WITH TAPE (6-5"C.).

THE LOCATION, SIZE AND TYPE OF MATERIAL OF EXISTING UNDERGROUND UTILITIES INDICATED ON THE PLANS IS NOT REPRESENTED AS BEING ACCURATE, SUFFICIENT OR COMPLETE. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO DETERMINE THE ACTUAL LOCATION OF ALL SUCH FACILITIES, INCLUDING THE SERVICE CONNECTIONS TO UNDERGROUND UTILITIES. PRIOR TO CONSTRUCTION THE CONTRACTOR SHALL NOTIFY THE UTILITY COMPANIES OF HIS OPERATIONAL PLANS AND SHALL OBTAIN FROM THE RESPECTIVE UTILITY COMPANIES DETAILED INFORMATION AND ASSISTANCE RELATIVE TO THE LOCATION OF THEIR FACILITIES AND THE WORKING SCHEDULE OF THE COMPANIES FOR REMOVAL OR ADJUSTMENT WHERE REQUIRED. IN THE EVENT AN UNEXPECTED UTILITY INTERFERENCE IS ENCOUNTERED DURING CONSTRUCTION, THE CONTRACTOR SHALL IMMEDIATELY NOTIFY THE UTILITY COMPANY OF JURISDICTION. THE ENGINEER SHALL ALSO BE IMMEDIATELY NOTIFIED. ANY SUCH MAINS AND SERVICES SHALL BE RESTORED TO SERVICE AT ONCE AND PAID FOR BY THE CONTRACTOR AT NO ADDITIONAL COST TO THE CONTRACT.

CONTACT JOINT UTILITY LOCATING INFORMATION FOR EXCAVATING (JULIE) 1-800-892-0123 FOR UTILITY INFORMATION.



FILE NAME = i:\@6jaba\@6RI583\CADO\Road\Sheet\E-I@5.dgn	USER NAME = MWH  PLDT SCALE = AS SHOWN	DESIGNED - PJT  DRAWN - ANC  CHECKED - PJT  DATE - 11/04/10	REVISED - REVISED - REVISED - REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	NORTHERN ILLINOIS UNIVERSITY FAR WEST CAMPUS EXPANSION ROADWAY LIGHTING PLAN  SCALE: AS SHOWN SHEFT NO. 5 OF X SHEETS STA. TO STA.	F.A.P.   SECTION   COUNTY   SHEETS	0.5
1	TEUT DATE * 1170572010	DATE 11704710	NEVISED		SCALLE AS SHOWN SHEET NO. 5 OF A SHEETS STA. 10 STA.	FED. ROAD DIST. NO.   ILLINOIS FED. AID PROJECT	