CODE NUMBER	. Programme and the state of th	UNIT	QUANTITIES
20900110	POROUS GRANULAR BACKFILL	CU YD	38
X2501000	SEEDING, CLASS 2 (SPECIAL)	ACRE	0.1
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	30
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	94.9
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	5100
42400300	PORTLAND CEMENT CONCRETE SIDEWALK 6 INCH	SQ FT	577
42400800	DETECTABLE WARNINGS	SQ FT	66
44000100	PAVEMENT REMOVAL	SQ YD	240.7
44000600	SIDEWALK REMOVAL	SQ FT	6292
56500600	DOMESTIC WATER SERVICE BOXES TO BE ADJUSTED	EACH	5
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	179
60605400	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24 (SPECIAL)	FOOT	328
67100100	MOBILIZATION	LSUM	1
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	LSUM	1
78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	80
and the state of the state			
			1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1
			Part A Test
			24 24
		Augus 1	
			Carlotte C

* SPECIALTY ITEMS

GENERAL NOTES

- 1) THIS SECTION SHALL BE CONSTRUCTED IN ACCORDANCE WITH THE "STANDARD SPECIFICATIONS FOR ROAD & BRIDGE CONSTRUCTION" ADOPTED JANUARY 1, 2007.
- 2) ANY REFERENCE TO STANDARDS THROUGHOUT THE PLANS SHALL BE INTERPRETED TO BE THE LATEST STANDARDS OF THE DEPARTMENT.
- 3) PLAN ELEVATIONS ARE BASED ON U.S.G.S. ELEVATIONS.
- 4) WHERE SECTION OR SUB-SECTION MARKERS ARE ENCOUNTERED, THE ENGINEER SHALL BE NOTIFIED BEFORE SUCH MONUMENTS ARE REMOVED OR COVERED UP. THE CONTRACTOR SHALL PROTECT AND CAREFULLY PRESERVE ALL MONUMENTS UNTIL AN AUTHORIZED SURVEYOR OR AGENT HAS WITNESSED OR OTHERWISE REFERENCED THEIR LOCATIONS.
- 5) THE WORK INCLUDED CONSISTS OF THE CONSTRUCTION OF CURB AND GUTTERS, SIDEWALKS, STORM SEWERS, AND OTHER ITEMS NECESSARY TO COMPLETE THE PROJECT.
- 6) THE STREET WILL REMAIN OPEN TO THRU TRAFFIC DURING CONSTRUCTION. SEE SPECIAL PROVISIONS FOR DETAILS.

- 7) BEFORE WORKING WITH OR AROUND UTILITIES, THE CONTRACTOR SHALL BE RESPONSIBLE FOR CONTACTING THE ILLINOIS ONE-CALL SYSTEM JULIE AT 1-800-892-0123, 48 HOURS (EXCLUDING WEEKENDS AND 'OR HOLIDAYS) PRIOR TO DIGGING. JULIE WILL NOTIFY THI OWNERS/OPERATORS OF UNDERGROUND FACILITIES WHO ARE JULIE MEMBERS OF THE PLANNED DIGGING ACTIVITY. THE FOLLOWING IS A LIST OF UTILITIES:
 - A) ELECTRIC AND GAS AMERENCIPS

P.O. BOX 66878 ST. LOUIS, MO 63166-6878 PHONE: 800-232-2477

B) TELEPHONE - VERIZON

C) WATER AND SEWER - CITY OF PARIS NORTH HIGH STREET

PARIS, IL 61944

D) CABLE TELEVISION - CHARTER COMMUNICATIONS

1 (800) 871-4485

8) THE EXISTING TRAFFIC CONTROL SIGNS WHICH INTERFERE WITH THE CONSTRUCTION OPERATIONS SHALL BE REMOVED AND RESET AS DIRECTED BY THE ENGINEER. THE COST FOR DOING THIS WORK WILL BE CONSIDERED INCIDENTAL TO THE CONTRACT AND NO ADITIONAL COMPENSATION WILL BE ALLOWED.

DESIGN INFORMATION

1) SEEDING

THE FOLLOWING ESTIMATED QUANTITIES ARE BASED ON SEEDING FROM R.O.W. TO R.O.W. WITH APPROPRIATE DEDUCTION FOR PAVEMENT, SHOULDERS, AND DRIVEWAYS, FROM STA. 56+63 TO STA. 59+75.50 AND FROM STA. 9+70.97 TO STA. 11+36.63.

APPLICATION RATES:

90 LBS. / ACRE 90 LBS

2 TON / ACRE MULCH (METHOD 1)

SUMMARY OF SEEDING:

SEEDING, CLASS **2** (SPECIAL) = 9 LBS.

NITROGEN FERTILIZER NUTRIENT = 9 LBS.

PHOSPHORUS FERTILIZER NUTRIENT = 9 LBS.

POTASSIUM FERTILIZER NUTRIENT = 9 LBS.

MULCH (METHOD **1**) = 0.2 TONS

2) AGGREGATE SURFACE COURSE, TYPE B

PLAN QUANTITY INCLUDES AN ALLOWANCE OF 30 TONS TO PROVIDE TEMPORARY PEDESTRIAN ACCESS TO BUSINESSES.

3) THERMOPLASTIC PAVEMENT MARKING - LINE 4"

WHITE - PARKING STALLS-

MAIN STREET - 18 FOOT WOOD STREET SOUTH - 34 FOOT WOOD STREET NORTH - 28 FOOT TOTAL = 80 FOOT

BENCH MARKS

SEE SHEET #4: BCA BENCHMARK 21 ELEVATION: 724.44 FT. CHISELED SQUARE SET ON THE TOP SOUTHWEST CORNER OF CONCRETE BASE FOR TRAFFIC SIGNAL LEVEL WITH CONCRETE SIDEWALK. 22.0 FEET EAST OF THE CENTERLINE OF MAIN STREET AND 40.5 FEET SOUTH OF THE CENTERLINE OF WOOD STREET.

SEE SHEET #5: BCA BENCHMARK ELEVATION: 728.96 CHISELED "X" SET ON THE TOP WEST OF FOUR FIRE HYDRANT CAP BOLTS, 2.5 FEET ABOVE GROUND LEVEL, 2.48 FEET EAST OF "THE CENTERLINE OF MAIN STREET AND 38.5 FEET SOUTH OF THE CENTERLINE OF WASHINGTON STREET.

CONSUI LAN

FRANCIS ASSOCIATES

PROFESSIONAL DESIGN FIRM #184-001406

CONSULTING ENGINEERS LAND SURVEYORS 330 NORTH CENTRAL AVENUE PARIS, ILIO 1055-5306 PH. (217) 465-5306



FRANCIS ASSOC. FILE NO. P-414

GENERAL NOTES & SUMMARY OF QUANTITIES

SHEET NO.

CITY OF PARIS, EDGAR COUNTY

SECTION 06-00063-01-SW DOWNTOWN SIDEWALK MPROVEMENTS - PHASE 2

ONTRACT NO. 91444

HEET 2 OF 7

2 of 7 sheets

DOWNTOWN SIDEWALK IMPROVEMENTS - PHASE 2 CITY OF PARIS, ILLINOIS, EDGAR COUNTY