

SUMMARY OF QUANTITIES				
S.P.	CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY
	20100500	TREE REMOVAL ACRES	ACRE	1.75
	20200100	EARTH EXCAVATION	CU YD	2,416
	20400800	FURNISHED EXCAVATION	CU YD	5,158
	20900110	POROUS GRANULAR BACKFILL	CU YD	360
	58600100	SAND BACKFILL	CU YD	345
	21101505	TOPSOIL EXCAVATION AND PLACEMENT	CU YD	717
	21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	882
	25000305	SEEDING, CLASS 3A	ACRE	1.75
	25000400	NITROGEN FERTILIZER NUTRIENT	POUND	158
	25000500	PHOSPHOROUS FERTILIZER NUTRIENT	POUND	158
	25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	158
	25000700	AGRICULTURAL GROUND LIMESTONE	TON	4
	25100115	MULCH, METHOD 2	ACRE	1.25
	25100630	EROSION CONTROL BLANKET	SQ YD	3,197
	28000200	EARTH EXCAVATION FOR EROSION CONTROL	CU YD	25
	28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	350
	28000305	TEMPORARY DITCH CHECKS	FOOT	60
	28000400	PERIMETER EROSION BARRIER	FOOT	526
	28001000	AGGREGATE (EROSION CONTROL)	TON	53
	28100207	STONE RIPRAP, CLASS A4	TON	414
	28200200	FILTER FABRIC	SQ YD	552
	35100700	AGGREGATE BASE COURSE, TYPE A 8"	SQ YD	249
	40300100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	115
	40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	60
	40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	33
	48101200	AGGREGATE SHOULDERS, TYPE B	TON	62
	X50100205	REMOVAL OF EXISTING STRUCTURES , SPECIAL	EACH	1
	50101500	REMOVAL OF EXISTING SUPERSTRUCTURES	EACH	1
	50104000	BRIDGE RAIL REMOVAL	FOOT	88
	50200100	STRUCTURE EXCAVATION	CU YD	565
	50200300	COFFERDAM EXCAVATION	CU YD	300
	50202901	COFFERDAM (LOCATION - I)	EACH	1
	50300225	CONCRETE STRUCTURES	CU YD	493.1
	50400305	PRECAST PRESTRESSED CONCRETE DECK BEAMS (17" DEPTH)	SQ FT	1,232

	SUMMARY OF QUANTITIES			
S.P.	CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY
	50800105	REINFORCEMENT BARS	POUND	71,440
	50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	490
Δ	50900205	STEEL RAILING , TYPE S1	FOOT	88
	51500100	NAME PLATES	EACH	1
	58100200	WATERPROOFING MEMBRANE SYSTEM	SQ YD	137
	58300100	PORTLAND CEMENT MORTAR FAIRING COURSE	FOOT	264
	59300100	CONTROLLED LOW-STRENGTH MATERIAL	CU YD	224
	60107600	PIPE UNDERDRAINS 4"	FOOT	300
Δ	63000005	STEEL PLATE BEAM GUARD RAIL, TYPE B	FOOT	50
Δ	63100075	TRAFFIC BARRIER TERMINAL, TYPE 5A	EACH	4
	63200310	GUARD RAIL REMOVAL	FOOT	180.0
* Δ	63301000	REMOVE AND RE-ERECT STEEL PLATE BEAM GUARD RAIL	FOOT	104.5
Δ	63302000	REMOVE AND RE-ERECT TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	2
* Δ	X6640535	CHAIN LINK FENCE, 6' ATTACHED TO STRUCTURE	FOOT	370
	67100100	MOBILIZATION	L SUM	1
*	X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1
	72000100	SIGN PANEL - TYPE 1	SQ FT	6.25
	72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	17
Δ	78001120	PAINT PAVEMENT MARKING - LINE 5''	FOOT	282
* Δ	78200410	GUARDRAIL MARKERS, TYPE A	EACH	4
* Δ	78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	1
* Δ	LR631020	TRAFFIC BARRIER TERMINAL, TYPE 1	EACH	1
*	XX007958	DIVERSION STRUCTURE	EACH	1
*	X0301280	PLUG EXISTING DRAINS	EACH	1
*	X0323265	REMOVE EXISTING RIPRAP	SQ YD	40
*	Z0013798	CONSTRUCTION LAYOUT	L SUM	1
*	Z0018905	DRILL AND GROUT BARS	EACH	56
*	XX008370	PVC WATERSTOP, 6"	FOOT	521
*	XX008371	TEMPORARY DRAWDOWN PIPE	EACH	1
*	XX008372	SLUICE GATE	EACH	1

Δ. SPECIALTY ITEMS

FILE NAME = ...\\Sheets\\NiemenvilleTr_S001.dgn	USER NAME = Kristin Timmons	DESIGNED = KLT/JJF	REVISED =	NIEMANVILLE TRAIL MONTGOMERY COUNTY, ILLINOIS	SUMMARY OF QUANTITIES	CONSTRUCTION TYPE CODE: 1009				
		DRAWN = GLD	REVISED =			F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	PLOT SCALE = 50.0000' / IN.	CHECKED = KLT/JJF	REVISED =			8243	09-00134-00-DR	MONTGOMERY	32	3
	PLOT DATE = 3/4/2010	DATE = 3/2/2010	REVISED =			CONTRACT NO. 93537				
				SCALE:	SHEET NO. 3 OF 32 SHEETS	STA.	TO STA.	FED. ROAD DIST. NO. 6 (MONTGOMERY CO. DIST. NO. 6)		