



LEGEND

- DITCH CHECK (TEMPORARY)
- SEDIMENT BASIN
- PERIMETER EROSION BARRIER

34 TONS STONE DUMPED RIPRAP, CLASS A4
(TEMPORARY-FOR FLOW DIVERSION)

EXISTING EARTH MATERIAL
STOCKPILED TO BE USED
AS TOPSOIL

STA. 4+50.00
120' RT.

STA. 5+50.00
120' RT.

STA. 6+00.00
75' RT.

STA. 5+04.00, 56.72' RT.
INV. ELEV. = 658.70

EXISTING R.O.W.

EXISTING R.O.W.

BORING B-1
STA. 4+50±

TEMPORARY DIVERSION CULVERT(S)
STA. 5+04.00, 34.00' LT., INV. ELEV. = 659.70
(SEE TEMPORARY CLEAR WATER DIVERSION SP)
THE DAM CREST SHALL BE ELEV. = 664.50 ABOVE THE
CULVERTS FOR A LENGTH OF 25 FEET ALONG ROAD
CENTERLINE. CREST SECTION SHALL BE TEMPORARY
BACKFILLED WITH A TOP LAYER OF CLASS A3 RIPRAP,
CAPPED WITH AGGREGATE BASE FOR VEHICLE TRAFFIC.
SEE SPECIAL PROVISIONS.

ALL EARTH STORED ON PAVEMENT AND SHOULDER OF NIEMANVILLE TRAIL
(NORTH AND SOUTH OF BRIDGE) SHALL BE REMOVED DURING CONSTRUCTION,
FOLLOWING PLACEMENT OF ROAD CLOSED BARRICADES. (EARTH EXTENDS
BEYOND LIMITS OF PLAN SHEET)

PERIMETER EROSION
BARRIER, 375'

LIMIT OF TREE REMOVAL
AND CLEARING (1.8 ACRES)

STA. 3+75.00
140' RT.

STA. 3+25.00
200' RT.

STA. 2+63.17
219.09' RT.

STA. 2+55.00
250' RT.

STA. 2+35.00
290' RT.

EXISTING EARTH MATERIAL
STOCKPILED TO BE USED
AS TOPSOIL

EXISTING EARTH MATERIAL
STOCKPILED TO BE USED
AS TOPSOIL

BORING B-3
STA. 2+95±

BORING B-2
STA. 2+55±

EXISTING SPILLWAY
TO BE REMOVED
(SHEET 13)

EXISTING BRIDGE SUPERSTRUCTURE
TO BE REMOVED (SHEET 13)

TEMPORARY DRAWDOWN SIPHON
PIPE, 12" DIAM.
(SEE SPECIAL PROVISIONS)

REMOVE EXISTING RIPRAP, 40 SQ. YD.

NIEMANVILLE TRAIL
MONTGOMERY COUNTY, ILLINOIS

NOTES:

TEMPORARY EROSION CONTROL SEEDING TO BE
PERFORMED WITHIN THE LIMITS OF CONSTRUCTION.

WALTON LAKE
NORMAL WATER LEVEL, EL. = 661.70

EXISTING SITE PLAN
F.A.U. ROUTE 8243

SCALE: 1"=20' SHEET NO. 6 OF 32 SHEETS STA. 0+00 TO STA. 6+00

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
8243	09-00134-00-DR	MONTGOMERY	32	6
CONTRACT NO. 93537				

FED. ROAD DIST. NO. 6 ILLINOIS FED. AID PROJECT