

F.A.S.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
800	07-00075-00-NS	WABASH	4	4
FED. ROAD DIST. NO. 7	ILLINOIS	LANCASTER-FRIENDSVILLE RD		
LEC JOB # H081004WB	CONTRACT # 95594			

SCHEDULE OF PAVEMENT MARKINGS

STATION	TO	STATION	LOCATION	LENGTH - FOOT
0+75		158+75	CENTERLINE	3638
			EDGELINE	
0+75		130+35	RT.	12960
130+70		157+70	RT.	2700
158+20		158+75	RT.	55
			EDGELINE	
0+75		48+30	LT.	4755
48+70		89+67	LT.	4097
89+94		130+30	LT.	4036
130+70		157+80	LT.	2710
158+20		158+75	LT.	55
			NO PASSING	
0+75		3+70	LT.	295
87+45		93+03	LT.	558
102+96		131+50	RT.	2854
119+00		144+00	LT.	2500
148+40		158+75	RT.	1035
				TOTAL 42,248

THE ABOVE QUANTITY IS SHOW IN THE PAVEMENT MARKING-LINE 4" IN THE SUMMARY OF QUANTITIES.

SCHEDULE OF PIPE CULVERTS, SPECIAL

STATION	SIZE	LENGTH	END OF CULVERT
48+65	30"	6'	SOUTH
54+67	30"	8'	NORTH
130+53	24"	4'	NORTH

THE ABOVE QUANTITY IS INCLUDED IN THE PIPE CULVERT REMOVAL (SPECIAL) AND THE PIPE CULVERTS, SPECIAL IN THE SUMMARY OF QUANTITIES.

SCHEDULE OF MAILBOX TURNOUTS

STATION	LOCATION	EST. QUANTITY ALLOWED TONS
86+15	RT.	5.0
91+04	RT.	3.7
101+96	RT.	5.0
110+93	RT.	5.0
136+56	LT.	5.9
144+66	LT.	3.8
		28.4

THE ABOVE QUANTITY IS INCLUDED IN THE HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N70 IN THE SUMMARY OF QUANTITIES.

SCHEDULE OF AGGREGATE SHOULDER STONE IN TANGENT

STATION	TO	STATION	LOCATION	ALLOWED TONS EST. QUANTITY
0+75		158+75	LT.	758.8
0+75		158+75	RT.	1027.5
				TOTAL 1786.3

THE ABOVE QUANTITY IS FOR THE ENTIRE SECTION AND IS INCLUDED IN THE QUANTITY FOR AGGREGATE SHOULDERS, TYPE B IN THE SUMMARY OF QUANTITIES.

SCHEDULE OF PRIVATE AND FIELD ENTRANCES

STATION	LOCATION	BC SC SUPER "C" N50 (IN TONS)
7+19	LT.	2.7
25+08	LT.	2.4
25+09	RT.	3.2
36+06	LT.	2.5
41+22	LT.	2.0
43+48	RT.	2.6
48+55	RT.	1.7
51+22	LT.	2.1
51+23	RT.	2.0
62+12	RT.	2.0
65+56	LT.	2.0
65+57	RT.	2.3
70+38	RT.	2.5
81+76	LT.	2.2
85+39	RT.	3.1
86+78	RT.	1.9
91+23	RT.	2.2
93+23	RT.	3.1
94+07	LT.	3.6
98+38	RT.	2.1
99+48	LT.	3.3

THE ABOVE QUANTITY IS INCLUDED IN THE HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N70 IN THE SUMMARY OF QUANTITIES.

SCHEDULE OF PRIVATE AND FIELD ENTRANCES

STATION	LOCATION	BC SC SUPER "C" N50 (IN TONS)
99+48	LT.	3.3
100+16	LT.	2.2
101+05	LT.	5.5
101+25	RT.	2.4
101+98	LT.	3.2
104+42	LT.	2.1
107+91	RT.	2.6
110+25	LT.	1.4
116+87	RT.	1.7
117+56	LT.	1.6
120+55	RT.	1.5
122+84	LT.	1.4
123+88	RT.	2.6
124+68	RT.	1.9
125+36	RT.	1.5
134+58	LT.	1.5
136+36	RT.	2.1
144+40	RT.	1.9
144+41	LT.	1.3
145+55	RT.	1.8
156+82	LT.	3.4
		TOTAL 95.1


323 W. 3RD ST.
P.O. BOX 160
MT. CARMEL, IL
62863
PHONE:
(618)-262-8651
FAX:
(618)-263-3327

405 W. STATE ST.
SUITE
PRINCETON, IN
47670

PHONE:
(812)-386-7811
FAX:
(812)-385-2812



PROFESSIONAL DESIGN FIRM
LAND SURVEY & PROFESSIONAL ENGINEERING CORPORATION
184-00887
(62-032435)(35-002769)



AARON M. MEFFORD
NAME
Aaron Mefford
SIGNATURE
10-26-10
DATE
11-30-11
EXPIRES