

MODEL: Default
FILE NAME: \\w\macom\h-pw\benley.com\AECOM\DS1\A\Documents\60602022\2022-Brush College\900-CAD GIS\910_CAD\03_SHEETS\01_AECOM\General\6060302_Sht_500-25.dgn

				CONSTRUCTION CODE							
CODE NO.	ITEM	UNIT	TOTAL	ROADWAY	RETAINING WALL	RETAINING WALL	RETAINING WALL	RETAINING WALL	BRIDGE	BUILDING DEMOLITION	HIGHWAY LIGHTING
				0004	0044	0044	0044	0044	0008	0044	0021
				URBAN	058-W003	058-W004	058-W006	058-W007	058-9202	URBAN	URBAN
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1							
Z0049799	PROTECTING OR RESETTNG SURVEY MARKERS	EACH	1	1							
* Z0049806	REMOVAL AND DISPOSAL OF FRIABLE ASBESTOS, BUILDING NO. 6	L SUM	1							1	
* Z0049901	REMOVAL AND DISPOSAL OF NON-FRIABLE ASBESTOS, BUILDING NO. 1	L SUM	1							1	
* Z0049902	REMOVAL AND DISPOSAL OF NON-FRIABLE ASBESTOS, BUILDING NO. 2	L SUM	1							1	
* Z0049903	REMOVAL AND DISPOSAL OF NON-FRIABLE ASBESTOS, BUILDING NO. 3	L SUM	1							1	
* Z0049904	REMOVAL AND DISPOSAL OF NON-FRIABLE ASBESTOS, BUILDING NO. 4	L SUM	1							1	
* Z0049906	REMOVAL AND DISPOSAL OF NON-FRIABLE ASBESTOS, BUILDING NO. 6	L SUM	1							1	
* Z0049908	REMOVAL AND DISPOSAL OF NON-FRIABLE ASBESTOS, BUILDING NO. 8	L SUM	1							1	
Z0056668	STORM SEWERS, TYPE 2, WATER MAIN QUALITY PIPE, 12"	FOOT	668	668							
Z0056669	STORM SEWERS, TYPE 2, WATER MAIN QUALITY PIPE, 15"	FOOT	270	270							
Z0056670	STORM SEWERS, TYPE 2, WATER MAIN QUALITY PIPE, 18"	FOOT	244	244							
Z0056672	STORM SEWERS, TYPE 2, WATER MAIN QUALITY PIPE, 24"	FOOT	429	429							
Z0056678	STORM SEWERS, TYPE 2, WATER MAIN QUALITY PIPE, 36"	FOOT	92	92							
Z0056696	STORM SEWERS, TYPE 3, WATER MAIN QUALITY PIPE, 42"	FOOT	121	121							
Z0062456	TEMPORARY PAVEMENT	SQ YD	2,568	2,568							
Z0064600	SELECTIVE CLEARING	ACRE	2.00							2.00	
* Z0068200	STEEL CASINGS 30"	FOOT	50	50							

* DENOTES SPECIALTY ITEM ** DENOTES NON-PARTICIPATING ITEM % 0042



USER NAME = Jacqueline.Ng
PLOT SCALE = 2.0000 ' / in.
PLOT DATE = 10/29/2021

DESIGNED - LMB
DRAWN - LMB
CHECKED - WBS
DATE - 10/22/2021

REVISED - 01/07/2022
REVISED -
REVISED -
REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: N/A SHEET 25 OF 32 SHEETS STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
7448	09-00933-01-BR	MACON	1019	29
CONTRACT NO. 95893				
ILLINOIS FED. AID PROJECT				

EARTHWORK CUT / FILL



ROAD	STATION	CUT	FILL
		(SQ FT)	(SQ FT)
Brush College Road	46+59.43	16	0
	46+75.00	16	0
	47+00.00	25	0
	47+25.00	39	0
	47+50.00	37	0
	47+75.00	43	0
	48+00.00	44	0
	48+25.00	47	0
	48+50.00	48	0
	48+75.00	58	1
	49+00.00	72	2
	49+25.00	87	4
	49+50.00	102	5
	49+75.00	127	7
	50+00.00	160	9
	50+25.00	185	11
	50+50.00	203	12
	50+75.00	209	13
	51+00.00	203	13
	51+25.00	188	13
	51+50.00	161	12
	51+75.00	117	11
	52+00.00	83	62
	52+25.00	65	101
	52+50.00	6	243
	52+75.00	109	193
	53+00.00	19	322
	53+25.00	21	551
	53+50.00	22	606
	53+75.00	15	786
	54+00.00	11	789
	54+25.00	15	857
	54+50.00	0	831
	54+75.00	0	896
	55+00.00	0	972
	55+25.00	0	1,027
	55+50.00	0	1,001
	55+75.00	0	1,061
	56+00.00	0	1,022
	56+25.00	0	1,028
	56+50.00	0	209
	56+75.00	0	232
	57+00.00	0	2,197
	57+25.00	16	2,050
	57+50.00	19	2,113
	57+75.00	18	2,196
	58+00.00	40	2,306
	58+25.00	148	2,388

ROAD	STATION	CUT	FILL
		(SQ FT)	(SQ FT)
Brush College Road	58+50.00	259	2,392
	58+75.00	351	2,300
	59+00.00	466	2,368
	59+25.00	591	2,238
	59+50.00	370	2,239
	59+75.00	387	1,784
	60+00.00	379	1,263
	60+25.00	191	434
	60+42.10	4	112
	BRIDGE OMISSION		
	62+45.19	6	9
	62+50.00	17	8
	62+75.00	131	68
	63+00.00	85	46
	63+25.00	95	52
	63+50.00	105	56
	63+75.00	110	64
	64+00.00	98	74
	64+25.00	86	87
	64+50.00	83	112
	64+75.00	75	128
	65+00.00	57	165
	65+25.00	51	194
	65+50.00	40	241
	65+75.00	0	291
	66+00.00	0	326
	66+25.00	0	359
	66+50.00	0	354
	66+75.00	0	586
	67+00.00	0	537
	67+25.00	0	484
	67+50.00	0	432
	67+75.00	0	370
	68+00.00	0	311
	68+25.00	0	257
	68+50.00	0	208
	68+75.00	0	215
	69+00.00	0	173
	69+25.00	0	121
	69+50.00	0	79
	69+75.00	8	12
	70+00.00	29	10
	70+25.00	43	13
	70+50.00	55	14
	70+75.00	67	3
	71+00.00	71	2
	71+25.00	70	1
	71+50.00	65	1

ROAD	STATION	CUT	FILL
		(SQ FT)	(SQ FT)
Brush College Road	71+75.00	59	2
	72+00.00	46	0
	72+25.00	51	4
	72+50.00	59	11
	72+75.00	76	12
	73+00.00	53	4
	73+25.00	34	5
	73+50.00	31	3
	73+75.00	27	3
	74+00.00	30	10
	74+25.00	39	8
	74+50.00	48	1
	74+75.00	58	0
	75+00.00	62	0
	75+25.00	62	0
	75+44.21	62	0

ROAD	STATION	CUT	FILL
		(SQ FT)	(SQ FT)
Faries Parkway	205+18.73	44	0
	205+25.00	44	0
	205+50.00	53	2
	205+75.00	61	4
	206+00.00	58	2
	206+25.00	47	2
	206+50.00	43	5
	206+75.00	52	15
	207+00.00	48	14
	207+25.00	37	16
	207+50.00	29	21
	207+75.00	15	33
	208+00.00	23	10
	208+25.00	36	16
	208+50.00	39	36
	208+75.00	41	38
	209+00.00	62	46
	209+25.00	76	34
	209+50.00	78	25
	209+75.00	0	0
	210+00.00	59	29
	210+25.00	65	49
	210+50.00	59	80
	210+75.00	59	98
	211+00.00	62	46
	211+25.00	153	26
	211+50.00	204	14
	211+75.00	193	13
	212+00.00	251	11

ROAD	STATION	CUT	FILL
		(SQ FT)	(SQ FT)
Faries Parkway	212+25.00	291	9
	212+50.00	318	11
	212+75.00	333	12
	213+00.00	342	12
	213+25.00	346	13
	213+50.00	332	8
	213+75.00	330	8
	214+00.00	268	21
	214+25.00	267	9
	214+50.00	339	7
	214+75.00	393	5
	215+00.00	413	4
	215+25.00	306	5
	215+50.00	295	6
	215+75.00	328	7
	216+00.00	291	0
	216+25.00	228	0
	216+50.00	212	0
	216+75.00	213	0
	217+00.00	218	0
	217+25.00	240	0
	217+50.00	263	0
	217+75.00	261	0
	218+00.00	259	0
	218+25.00	245	0
	218+50.00	225	0
	218+75.00	233	0
	219+00.00	197	0
	219+25.00	187	0
	219+50.00	189	0
	219+75.00	204	0
	220+00.00	196	0
	220+25.00	174	0
	220+50.00	110	12
	220+75.00	132	12
	221+00.00	140	8
	221+25.00	103	12
	221+50.00	87	21
	221+75.00	127	2
	222+00.00	120	0
	222+25.00	126	0
	222+50.00	158	0
	222+75.00	167	1
	223+00.00	223	1
	223+25.00	357	20
	223+50.00	403	19
	223+75.00	441	7
	224+00.00	479	10

ROAD	STATION	CUT	FILL
		(SQ FT)	(SQ FT)
Faries Parkway	224+25.00	500	5
	224+50.00	527	2
	224+75.00	569	2
	225+00.00	512	2
	225+25.00	390	4
	225+50.00	143	7
	225+75.00	9	257
	226+00.00	7	447
	226+25.00	14	509
	226+50.00	21	575
	226+75.00	5	788
	227+00.00	14	778
	227+25.00	51	623
	227+50.00	45	433
	227+75.00	32	367
	228+00.00	64	336
	228+25.00	22	324
	228+50.00	25	328
	228+75.00	27	344
	229+00.00	36	363
	229+25.00	70	450
	229+50.00	72	433
	229+75.00	51	392
	230+00.00	51	412
	230+25.00	52	429
	230+50.00	58	384
	230+75.00	67	322
	231+00.00	69	289
	231+25.00	68	234
	231+50.00	67	138
	231+75.00	71	10
	232+00.00	68	5
	232+25.00	64	4
	232+50.00	63	5
	232+75.00	66	2
	233+00.00	52	0
	233+25.00	52	7
	233+50.00	78	0
	233+75.00	76	1
	234+00.00	71	3
	234+25.00	67	0
	234+50.00	65	0
	234+75.00	62	0
	235+00.00	59	0
	235+25.00	51	0
	235+41.47	47	0

MODEL: Default
FILE NAME: p:\1\aecom-nb-jw-bentley.com\aecom_D516_1A\Documents\60603202-Brush College\000-CAD GIS\910_CAD\03_SHEETS\01_AECOM\Roadway\60603202_SHT_Roadway_Schedule_15A.dgn

MODEL Default
FILE NAME: p:\1\aecom-nb-jw-bentley.com\AECOM_DSI\6_1\A\Documents\60603202-Brish College\000-CAD GIS\910_CAD\03_SHEETS\01_AECOM\Roadway\60603202_SHT_Roadway_Schedule_15B.dgn

EARTHWORK CUT / FILL



ROAD	STATION	CUT	FILL
		(SQ FT)	(SQ FT)
James St.	404+27.90	27	0
	404+62.16	62	0
	404+76.46	97	0
	405+00.00	126	0
	405+26.59	174	0
	405+50.00	134	0
	405+81.11	175	0
	406+05.00	160	0
	406+25.00	171	0
	406+50.00	192	0
	406+69.00	217	0
	407+00.00	274	0
	407+25.00	293	0
	407+50.00	335	0
	407+70.00	359	0
	408+00.00	431	0
	408+25.00	511	0
	408+50.00	638	0

ROAD	STATION	CUT	FILL
		(SQ FT)	(SQ FT)
Jug Handle Connector	300+50.00	6	2,904
	300+75.00	24	2,492
	301+00.00	8	2,178
	301+25.00	12	1,973
	301+50.00	9	1,682
	301+75.00	8	1,406
	302+00.00	0	1,251
	302+25.00	40	1,107
	302+50.00	81	907
	302+75.00	135	781
	303+00.00	162	661
	303+25.00	173	529
	303+50.00	187	442
	303+75.00	224	229
	304+00.00	328	52
	304+25.00	636	9
	304+50.00	894	0
	304+75.00	1,091	0
	305+00.00	1,250	0
	305+25.00	1,543	0
	305+50.00	1,702	0
	305+75.00	1,816	0
	306+00.00	1,890	0
	306+25.00	1,908	0
	306+50.00	2,023	0
	306+75.00	2,199	0
	307+00.00	2,187	0
	307+25.00	2,096	0

ROAD	STATION	CUT	FILL
		(SQ FT)	(SQ FT)
Logan St.	600+64.00	290	7
	601+00.00	128	0
	601+26.00	61	0
	601+55.35	57	0
	601+75.00	46	0
	602+02.39	44	0
	602+36.29	43	0
	602+50.00	42	1
	602+75.00	41	2
	603+00.00	43	0
	603+06.50	42	0
	603+50.00	43	0
	603+90.50	49	0
	604+00.00	53	0
	604+25.00	46	0
	604+50.00	38	1
	604+77.92	48	0
	605+00.00	41	0
	605+28.00	52	0
	605+50.00	55	0
	605+75.00	56	0
	606+00.00	59	0
	606+40.50	70	0
	606+50.00	64	0
	606+75.00	63	0
	607+00.00	65	0
	607+28.31	53	0
	607+50.00	45	0
	607+57.00	49	0
	608+00.00	53	0
	608+34.01	51	0
	608+50.00	74	0
	608+77.71	93	0
	609+00.00	134	0

ROAD	STATION	CUT	FILL
		(SQ FT)	(SQ FT)
Harrison Ave. - West	800+00.00	124	0
	800+25.00	74	0
	800+50.00	156	0
	800+75.00	157	0
	801+00.00	46	0
	801+25.00	24	0
	801+50.00	31	0
	801+75.00	27	0
	802+00.00	30	0
	802+25.00	31	0
	802+50.00	59	0
	802+75.00	34	0
	803+00.00	41	0
	803+25.00	37	0
	803+50.00	39	0
	803+75.00	53	0
	804+00.00	96	0
	804+25.00	101	0
	804+50.00	110	0
	804+75.00	130	0
	805+00.00	252	0
	805+25.00	433	0
	805+50.00	630	0
	805+75.00	886	0
	806+00.00	1,164	0
	806+25.00	1,373	0
	806+50.00	1,360	0
	806+75.00	976	0
	807+00.00	154	0
	807+25.00	88	0
	807+50.00	60	0
	807+75.00	42	0
	808+00.00	53	0
	808+25.00	155	0
	808+50.00	137	0
	808+75.00	79	1
	809+00.00	36	31
	809+25.00	20	77
	809+50.00	18	113
	809+75.00	0	127
	810+00.00	0	97

ROAD	STATION	CUT	FILL
		(SQ FT)	(SQ FT)
Harrison Ave. - East	700+75.00	0	107
	701+00.00	0	85
	701+25.00	0	54
	701+50.00	1	59
	701+75.00	2	28
	702+00.00	2	7
	702+25.00	3	2
	702+50.00	3	1
	702+75.00	7	0
	703+00.00	7	0
	703+25.00	7	0
	703+50.00	7	0
	703+75.00	7	0
	704+00.00	7	0
	704+25.00	7	0
	704+50.00	7	0
	704+75.00	7	0
	705+00.00	7	0
	705+25.00	7	0
	705+50.00	7	0
	705+75.00	7	0
	706+00.00	7	0
	706+25.00	7	0
	706+50.00	8	0
	706+75.00	21	0
	707+00.00	18	0
	707+25.00	8	0
	707+50.00	9	0
	707+75.00	9	0
	708+00.00	7	0
	708+25.00	7	0
	708+41.73	7	0

ROAD	STATION	CUT	FILL
		(SQ FT)	(SQ FT)
Cemetery Access Road	900+09.00	53	0
	900+25.00	27	0
	900+50.00	55	0
	900+75.00	48	0
	901+00.00	50	0
	901+25.00	56	0
	901+50.00	67	0
	901+75.00	73	0
	902+00.00	76	0
	902+25.00	68	0
	902+50.00	60	0
	902+75.00	49	0
	903+00.00	49	0
	903+25.00	23	0
	903+50.00	54	0
	903+75.00	67	0
	904+00.00	84	0
	904+25.00	104	0
	904+40.00	70	0

11



USER NAME	= dlshevaz
PLOT SCALE	= 20,0000 ' / In.
PLOT DATE	= 1/7/2022

DESIGNED -	LMB
DRAWN -	LMB
CHECKED -	WBS
DATE -	10/22/2021

REVISED -	01/07/2022
REVISED -	
REVISED -	
REVISED -	

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

ROADWAY SCHEDULE

SCALE: N/A	SHEET 15B	OF 16 SHEETS	STA.	TO STA.
------------	-----------	--------------	------	---------

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
7448	09-00933-01-BR	MACON	1019	698
CONTRACT NO. 95893				
		ILLINOIS	FED. AID PROJECT	