


CONSTRUCTION PLANS - ISSUED NOVEMBER 19, 2021

REHABILITATE RUNWAY 17-35 PAVEMENT & LIGHTING

ST. LOUIS REGIONAL AIRPORT AUTHORITY
ST. LOUIS REGIONAL AIRPORT (ALN)
EAST ALTON, MADISON COUNTY, ILLINOIS

IDA PROJECT NO. : ALN-4812
SBG PROJECT NO. : 3-17-SBGP-171/175



GENERAL PROJECT LOCATION

SCOPE OF WORK:

THIS PROJECT CONSISTS OF A REHABILITATION OF THE RUNWAY 17-35 PAVEMENT AND LIGHTING. THIS PROJECT WILL INCLUDE BITUMINOUS PAVING, PAVEMENT GROOVING, SHOULDER ADJUSTMENT, REMOVAL AND INSTALLATION OF AIRFIELD LIGHTING AND SIGNS, PAVEMENT MARKING, EROSION CONTROL ITEMS AND INCIDENTALS.

NOTICE TO CONTRACTORS AND BIDDERS

THESE CONSTRUCTION PLANS RELY UPON THE SPECIAL PROVISIONS AND THE SPECIFICATIONS TO PROVIDE FOR A COMPLETE DESCRIPTION OF THE WORK AND CONSTRUCTION REQUIREMENTS. THE PLANS SHALL ONLY BE USED IN COMBINATION WITH ALL CONTRACT DOCUMENTS.

No.	Issue/Description	Sheets Changed	Date	By

COVERING ELECTRICAL DESIGN
EXP. 02/28/2022

Kevin N. Lightfoot
Kevin N. Lightfoot, P.E.
Electrical Engineer
11/18/2021
Date

HANSON PROFESSIONAL SERVICES INC.
1525 South Sixth Street
Springfield, Illinois 62703-2886
Telephone: 217.788.2450
Fax: 217.788.2503

Jaycen R. Herndon
Jaycen R. Herndon, P.E.
Civil Engineer
11/18/2021
Date

ST. LOUIS REGIONAL AIRPORT AUTHORITY
8 Terminal Drive
East Alton, Illinois 62024
Telephone: 618.259.2531
Fax: 618.259.7669

David C. Miller
David C. Miller
Director of Aviation
11/17/2021
Date



ST. LOUIS REGIONAL AIRPORT

8 Terminal Drive
East Alton, Illinois 62024



Jaycen Herndon

DATE SIGNED: 11/18/2021 LICENSE EXPIRES: 2/28/2022

**REHABILITATE
RUNWAY 17-35
PAVEMENT & LIGHTING**

SBG No:
3-17-SBGP-171/175
IDA No: ALN-4812

Contract No. SR095

NO.	DATE	DESCRIPTION		
		DES	DWN	REV

ISSUE: NOVEMBER 19, 2021
PROJECT NO: 17A008504
CAD FILE: G-002-FLP.DWG
DESIGN BY: JRH 3/18/2021
DRAWN BY: JRH 4/16/2021
REVIEWED BY: BSS 4/16/2021

SHEET TITLE

**SUMMARY OF
QUANTITIES AND
INDEX TO SHEETS**

SUMMARY OF QUANTITIES				
ITEM NO.	DESCRIPTION	UNIT	TOTAL QUANTITY	AS-BUILT QUANTITY
AR108108	1/C #8 5 KV UG CABLE	FOOT	21,300	
AR109200	INSTALL ELECTRICAL EQUIPMENT	L SUM	1	
AR110012	2" DIRECTIONAL BORE	FOOT	1,290	
AR110202	2" PVC DUCT, DIRECT BURY	FOOT	15,750	
AR125400	REPLACE ISOLATION TRANSFORMER	EACH	5	
AR125511	MIRL, BASE MOUNTED-LED	EACH	58	
AR125512	MIRL, INPAVEMENT	EACH	2	
AR125546	MI THRESHOLD LIGHT BASE MTD-LED	EACH	16	
AR125561	RWY DISTANCE REMAINING SIGN-LED	EACH	5	
AR125565	SPLICE CAN	EACH	31	
AR150510	ENGINEER'S FIELD OFFICE	L SUM	1	
AR150520	MOBILIZATION	L SUM	1	
AR150530	TRAFFIC MAINTENANCE	L SUM	1	
AR401614	BIT. SURF. CSE.-METHOD II, SUPERPAVE	TON	14,885	
AR401640	BITUMINOUS PAVEMENT GROOVING	SQ YD	68,627	
AR401650	BITUMINOUS PAVEMENT MILLING	SQ YD	18,982	
AR401900	REMOVE BITUMINOUS PAVEMENT	SQ YD	851	
AR603510	BITUMINOUS TACK COAT	GALLON	25,886	
AR620520	PAVEMENT MARKING-WATERBORNE	SQ FT	89,813	
AR620525	PAVEMENT MARKING-BLACK BORDER	SQ FT	18,889	
AR620590	TEMPORARY MARKING	SQ FT	89,813	
AR751943	ADJUST MANHOLE	EACH	2	
AR751952	ADJUST UNDERDRAIN STRUCTURE	EACH	21	
AR800476	REMOVE AIRFIELD LIGHTING	L SUM	1	
AR800552	CONCRETE MAINTENANCE PAD	EACH	2	
AR800564	CABLE AND CCR TESTING AND CALIBRATION	L SUM	1	
AR901510	SEEDING	ACRE	3.20	
AR905530	TOPSOILING	SQ YD	15,573	
AR908514	LIGHT-DUTY HYDRAULIC MULCH	ACRE	3.20	

GENERAL NOTES:

QUANTITIES

PAYMENT WILL BE MADE UNDER THE ITEM NUMBERS, DESCRIPTIONS AND UNITS NOTED IN THE ABOVE TABLE IN ACCORDANCE WITH THE BASIS OF PAYMENT FOR EACH RESPECTIVE WORK ITEM COMPLETED AND ACCEPTED BY THE ENGINEER.

CERTIFIED PAYROLLS

THE RESIDENT ENGINEER/TECHNICIAN CANNOT FORWARD CONSTRUCTION REPORTS TO THE ILLINOIS DIVISION OF AERONAUTICS FOR PROCESSING UNTIL ALL CERTIFIED PAYROLLS FOR THE PERIOD HAVE BEEN RECEIVED.


MATERIAL CERTIFICATIONS

MATERIALS TO BE INCORPORATED INTO THE PROJECT CANNOT BE USED WITHOUT PRIOR APPROVAL. ALL MATERIALS TO BE USED IN THE PROJECT MUST BE SUBMITTED TO THE RESIDENT ENGINEER/TECHNICIAN FOR APPROVAL. USE OF MATERIALS WITHOUT PRIOR APPROVAL AND ULTIMATELY DETERMINED TO BE UNACCEPTABLE BY THE ILLINOIS DIVISION OF AERONAUTICS ARE SUBJECT TO REMOVAL AND/OR NON-PAYMENT.

FILES

FOLLOWING THE PROJECT AWARD, THE ENGINEER CAN PROVIDE THE RELEVANT AUTOCAD AND CIVIL 3D SURFACE MODEL FILES TO THE AWARDED CONTRACTOR UPON REQUEST TO ASSIST WITH CONSTRUCTION LAYOUT.

INDEX TO SHEETS	
SHEET NUMBER	SHEET TITLE
1	COVER SHEET
2	SUMMARY OF QUANTITIES AND INDEX TO SHEETS
3	SCOPE OF WORK
4	PROPOSED SAFETY AND PHASING PLAN - PHASE 1
5	PROPOSED SAFETY AND PHASING PLAN - PHASE 2
6	PROPOSED SAFETY AND PHASING PLAN - PHASE 3
7	PROPOSED SAFETY AND PHASING PLAN - PHASE 4
8	CONSTRUCTION SAFETY DETAILS AND NOTES - SHEET 1
9	CONSTRUCTION SAFETY DETAILS AND NOTES - SHEET 2
10	TYPICAL SECTIONS
11	PROPOSED CONSTRUCTION PLAN - STA. 99+00 TO STA. 115+00
12	PROPOSED CONSTRUCTION PLAN - STA. 115+00 TO STA. 133+00
13	PROPOSED CONSTRUCTION PLAN - STA. 133+00 TO STA. 151+00
14	PROPOSED CONSTRUCTION PLAN - STA. 151+00 TO STA. 165+99
15	PROPOSED CONSTRUCTION PLAN - STA. 205+50 TO STA. 215+50
16	PROPOSED VARIABLE MILLING PLAN
17	PROPOSED PLAN & PROFILE - STA. 99+00 TO STA. 106+00
18	PROPOSED PLAN & PROFILE - STA. 106+00 TO STA. 115+00
19	PROPOSED PLAN & PROFILE - STA. 115+00 TO STA. 124+00
20	PROPOSED PLAN & PROFILE - STA. 124+00 TO STA. 133+00
21	PROPOSED PLAN & PROFILE - STA. 133+00 TO STA. 142+00
22	PROPOSED PLAN & PROFILE - STA. 142+00 TO STA. 151+00
23	PROPOSED PLAN & PROFILE - STA. 151+00 TO STA. 160+00
24	PROPOSED PLAN & PROFILE - STA. 160+00 TO STA. 165+99
25	PROPOSED PLAN & PROFILE - STA. 205+50 TO STA. 215+50
26	PROPOSED STAKING PLAN
27	PROPOSED MARKING PLAN - STA. 99+00 TO STA. 115+00
28	PROPOSED MARKING PLAN - STA. 115+00 TO STA. 133+00
29	PROPOSED MARKING PLAN - STA. 133+00 TO STA. 151+00
30	PROPOSED MARKING PLAN - STA. 151+00 TO STA. 165+99
31	PROPOSED MARKING PLAN - STA. 205+50 TO STA. 215+50
32	MARKING DETAILS
33	EXISTING ELECTRICAL PLAN - STA. 99+00 TO STA. 115+00
34	EXISTING ELECTRICAL PLAN - STA. 115+00 TO STA. 133+00
35	EXISTING ELECTRICAL PLAN - STA. 133+00 TO STA. 151+00
36	EXISTING ELECTRICAL PLAN - STA. 151+00 TO STA. 165+99
37	EXISTING ELECTRICAL PLAN - HOMERUN PLAN
38	PROPOSED ELECTRICAL PLAN - STA. 99+00 TO STA. 115+00
39	PROPOSED ELECTRICAL PLAN - STA. 115+00 TO STA. 133+00
40	PROPOSED ELECTRICAL PLAN - STA. 133+00 TO STA. 151+00
41	PROPOSED ELECTRICAL PLAN - STA. 151+00 TO STA. 165+99
42	PROPOSED ELECTRICAL PLAN - HOMERUN PLAN
43	THRESHOLD LIGHTING DETAILS
44	LIGHT LOCATION TABLE
45	AIRFIELD LIGHTING NOTES
46	AIRFIELD LIGHT DETAILS
47	IN-PAVEMENT RUNWAY LIGHT AND SPLICE CAN DETAILS
48	RUNWAY DISTANCE REMAINING SIGN DETAILS
49	AIRFIELD LIGHTING CABLE SPLICE DETAILS
50	CONDUIT TRENCH DETAILS
51	CABLE AND DUCT MARKER DETAILS
52	ELECTRICAL NOTES SHEET 1
53	ELECTRICAL NOTES SHEET 2
54	GROUNDING DETAILS
55	GROUND RESISTANCE TESTING DETAILS
56	GROUNDING NOTES
57	ELECTRICAL LEGEND AND ABBREVIATIONS
58	EXISTING ELECTRICAL ONE-LINE DIAGRAM FOR VAULT
59	EXISTING ELECTRICAL ONE-LINE DIAGRAM FOR VAULT AND AIRFIELD
60	PROPOSED ELECTRICAL ONE LINE FOR RWY 17-35 CCR
61	EXISTING HIGH VOLTAGE WIRING SCHEMATIC FOR RUNWAY 11-29
62	EXISTING HIGH VOLTAGE WIRING SCHEMATIC FOR RWY 17-35 & TWYS
63	PROPOSED HIGH VOLTAGE SCHEMATIC FOR RWY 17-35 CCR
64	SERIES CIRCUIT CABLE TESTING DETAILS




CRITICAL POINTS					
POINT #	LATITUDE	LONGITUDE	GROUND ELEV.	EQUIP. HEIGHT	EQUIP. ELEV.
CP#1	N38° 53' 56.30"	W90° 03' 23.78"	537.0'	25'	555.55
CP#2	N38° 53' 56.39"	W90° 03' 13.67"	531.0'	25'	555.55
CP#3	N38° 53' 51.82"	W90° 03' 08.72"	533.2'	25'	555.55
CP#4	N38° 53' 45.07"	W90° 03' 16.43"	536.0'	25'	555.55
CP#5	N38° 53' 41.99"	W90° 03' 07.20"	536.7'	25'	555.55
CP#6	N38° 53' 36.30"	W90° 03' 06.39"	538.6'	25'	555.55
CP#7	N38° 53' 30.86"	W90° 03' 05.57"	540.6'	25'	555.55
CP#8	N38° 53' 29.03"	W90° 03' 05.30"	541.1'	25'	555.55
CP#9	N38° 53' 15.50"	W90° 03' 07.90"	0.0'	2'	555.55
CP#10	N38° 53' 08.89"	W90° 03' 06.21"	541.0'	2'	555.55
CP#11	N38° 52' 53.30"	W90° 03' 05.06"	540.0'	2'	555.55
CP#12	N38° 53' 37.83"	W90° 03' 20.14"	0.0'	25'	555.55
CP#13	N38° 53' 30.78"	W90° 02' 56.25"	539.0'	2'	555.55
CP#14	N38° 52' 55.59"	W90° 03' 07.37"	541.0'	25'	555.55
CP#15	N38° 52' 47.30"	W90° 02' 59.08"	542.1'	25'	555.55

LEGEND:

- EXISTING PAVEMENT
- PROPOSED RUNWAY REHAB
- EXISTING BUILDINGS
- EXISTING FENCE
- CONSTRUCTION STAGING AREA
- HAUL ROUTE
- AIRPORT PROPERTY LINE
- PROPOSED BARRICADES
- PROPOSED CRITICAL POINTS
- TEMPORARY CONSTRUCTION SIGN
- RSA — RUNWAY SAFETY AREA (500' WIDE)
- TOFA — TAXIWAY OBJECT FREE AREA (186' WIDE)

REGIONAL GROUND FREQUENCY = 120.20



SAFETY PLAN COMPLIANCE DOCUMENT
 PRIOR TO THE ISSUANCE OF A CONSTRUCTION NOTICE-TO-PROCEED (NTP), THE CONTRACTOR SHALL BE RESPONSIBLE FOR PREPARING AND SUBMITTING A SAFETY PLAN COMPLIANCE DOCUMENT IN ACCORDANCE WITH FAA ADVISORY CIRCULAR 150/5370-2G, PARAGRAPH 2.4.2, OR EQUIVALENT SECTION IN SUBSEQUENT/CURRENT ISSUE. THE AIRPORT DIRECTOR SHALL APPROVE THIS DOCUMENT AND SUBMIT TO THE AIRPORT AUTHORITY FOR APPROVAL PRIOR TO THE NTP ISSUANCE.

PHASE 3 NOTES

1. THE WORK ITEMS TO BE COMPLETED IN THIS PHASE SHALL INCLUDE REMOVAL AND REPLACEMENT OF AIRFIELD LIGHTING AND SIGNAGE, PLACEMENT OF BITUMINOUS PAVEMENT, SHOULDER ADJUSTMENT, TEMPORARY MARKING AND ASSOCIATED ITEMS BETWEEN STA. 122+89 AND STA. 164+99.
2. PHASE 2B MAY BE CONSTRUCTED SIMULTANEOUSLY WITH PHASE 3, HOWEVER PHASE 2B TIME RESTRICTIONS SHALL STILL BE ENFORCED. THERE IS NO TIME RESTRAINT FOR PHASE 3, HOWEVER ALL WORK WILL COUNT TOWARDS OVERALL PROJECT TIME.
3. THE CONTRACTOR SHALL PLACE ORANGE SNOW/SAFETY FENCE ALONG THE RUNWAY 11-29 SAFETY AREA LIMITS NEAR THE WORK AREA. THIS LINE WILL DESIGNATE THE LIMITS OF CONTRACTOR ACTIVITY WHILE RUNWAY 11-29 IS OPEN TO AIRCRAFT. THE CONTRACTOR SHALL MAINTAIN THIS FENCE THROUGHOUT CONSTRUCTION.
4. RUNWAY 17-35 WILL BE CLOSED FOR THE DURATION OF THIS PHASE. RUNWAY 11-29 SHALL REMAIN OPEN FOR THE DURATION OF THIS PHASE. AT ALL TIMES, THE CONTRACTOR'S OPERATIONS SHALL BE SUCH AS TO MINIMIZE CLOSURES. CLOSURE CROSSES AND BARRICADES SHALL BE IN PLACE PRIOR TO BEGINNING CONSTRUCTION.
5. RUNWAY 17-35 LIGHTING CIRCUITS AND NAVAIDS SHALL BE TURNED OFF WHILE THE RUNWAY IS CLOSED TO AIRCRAFT. EXISTING TAXIWAY EDGES LIGHTS WITHIN THE CLOSED PORTIONS OF THIS PHASE SHALL BE TURNED OFF OR OBSCURED. THE CONTRACTOR SHALL PROVIDE APPROVED MATERIALS TO OBSCURE ALL AFFECTED EDGE LIGHTS. INSTALL AND MAINTAIN THE MATERIALS DURING CONSTRUCTION. ALL COSTS FOR OBSCURING LIGHT SHALL BE INCIDENTAL TO THE PROJECT.
6. AIRPORT SECURITY SHALL BE MAINTAINED THROUGHOUT THE PROJECT. THE CONTRACTOR SHALL BE RESTRICTED TO THE DESIGNATED WORK AREAS. THE CONTRACTOR SHALL ENSURE THAT ACCESS POINTS USED BY CONSTRUCTION VEHICLES AND PERSONNEL ARE MONITORED WHEN OPEN AND LOCKED WHEN NOT IN USE TO PREVENT UNAUTHORIZED ACCESS TO THE AIRPORT MOVEMENT AREA.
7. AT THE COMPLETION OF ALL CONSTRUCTION, THE HAUL ROUTE AND CONSTRUCTION EQUIPMENT PARKING AREA SHALL BE RESTORED TO PRE-CONSTRUCTION CONDITIONS PER THE SPECIFICATIONS.



ST. LOUIS REGIONAL AIRPORT
 8 Terminal Drive
 East Alton, Illinois 62024



Jaycen R. Herndon

DATE: 11/18/2021 LICENSE: 2/28/2022

**REHABILITATE
 RUNWAY 17-35
 PAVEMENT & LIGHTING**

SBG No:
 3-17-SBGP-171/175
 IDA No: ALN-4812

Contract No. SR095

NO.	DATE	DESCRIPTION		
		DES	DWN	REV

ISSUE: NOVEMBER 19, 2021
 PROJECT NO: 17A008504
 CAD FILE: G-004-SFY.DWG
 DESIGN BY: JRH 3/18/2021
 DRAWN BY: JRH 4/16/2021
 REVIEWED BY: BSS 4/16/2021

SHEET TITLE

**PROPOSED SAFETY
 AND PHASING PLAN -
 PHASE 3**

FOR BID



Jaycen Herndon

DATE SIGNED: 11/18/2021 LICENSE EXPIRES: 2/28/2022

**REHABILITATE
RUNWAY 17-35
PAVEMENT & LIGHTING**

SBG No:
3-17-SBGP-171/175
IDA No: ALN-4812

Contract No. SR095

NO.	DATE	DESCRIPTION		
		DES	DWN	REV

ISSUE: NOVEMBER 19, 2021

PROJECT NO: 17A008504

CAD FILE: G-501-SFY.DWG

DESIGN BY: JRH 3/18/2021

DRAWN BY: JRH 4/16/2021


REVIEWED BY: BSS 4/16/2021

SHEET TITLE

**CONSTRUCTION
SAFETY DETAILS
AND NOTES -
SHEET 1**

SAFETY NOTES

- FOLLOWING ARE THE CONSTRUCTION SAFETY PROCEDURES THAT THE CONTRACTOR SHALL FOLLOW THROUGHOUT THIS PROJECT. ADDITIONAL REQUIREMENTS ARE SHOWN ON THE CONSTRUCTION SAFETY AND PHASING PLAN SHEET AND THIS SHEET.
- ALL PROVISIONS OF THE LATEST EDITION OF FAA ADVISORY CIRCULAR AC 150/5370-2 (CURRENT EDITION), "OPERATIONAL SAFETY ON AIRPORTS DURING CONSTRUCTION", APPLY TO THIS CONTRACT, EXCEPT AS MODIFIED BY THIS SAFETY PLAN, OR AS MODIFIED BY THE OWNER THROUGH THE RESIDENT ENGINEER/TECHNICIAN AT THE PRECONSTRUCTION CONFERENCE, OR DURING THE COURSE OF THE CONTRACT.
- THE CONTRACTORS SHALL MINIMIZE DISRUPTION OF STANDARD OPERATING PROCEDURES FOR AERONAUTICAL ACTIVITY BY REMAINING WITHIN THE PRESCRIBED STAGING, CONSTRUCTION, AND PHASING AREAS PRESENTED ON THE CONSTRUCTION SAFETY AND PHASING PLAN SHEETS.
- NO UNAUTHORIZED PERSONNEL SHALL ENTER ANY AREA OF THE AIRPORT THAT COULD POTENTIALLY BE HAZARDOUS. THE AIRPORT MANAGER RESERVES THE RIGHT TO SUSPEND OPERATIONS IN ORDER TO MAINTAIN SAFETY AT THE AIRPORT.
- CONTRACTOR EQUIPMENT, VEHICLES, AND PROJECT MATERIALS SHALL BE STORED IN THE EQUIPMENT PARKING/STAGING AREA SHOWN ON THE PLAN VIEW, EXCEPT AS OTHERWISE PROVIDED FOR AT THE PRECONSTRUCTION CONFERENCE.
- ALL CONSTRUCTION EQUIPMENT OPERATING IN THE PRESCRIBED CONSTRUCTION AREA IS REQUIRED TO DISPLAY A CHECKERBOARD FLAG PROPERLY LOCATED OR A ROTATING BEACON (STROBE) AS SPECIFIED IN AC 150/5210-5, "PAINTING, MARKING, AND LIGHTING OF VEHICLES USED ON AN AIRPORT" LATEST EDITION.
- NO CONSTRUCTION MATERIAL STOCKPILES SHALL BE LOCATED WITHIN 250' OF ANY ACTIVE RUNWAY, WITHIN 93' OF ANY OTHER ACTIVE AIRPORT OPERATIONS AREA, OR PENETRATE A PART 77 IMAGINARY SURFACE (PROVIDED BY THE RESIDENT ENGINEER/TECHNICIAN) EXTENDING OUT AND UPWARDS FROM ALL SIDES OF AN ACTIVE RUNWAY.
- CLOSED AIRFIELD PHASING AREAS, OPEN TRENCHES, AND STOCKPILED MATERIALS AT THE CONSTRUCTION SITE SHALL BE PROMINENTLY MARKED WITH LIGHTED BARRICADES WITH STEADY BURNING OR FLASHING RED LIGHTS AS SPECIFIED IN 150/5370-2, "OPERATIONAL SAFETY ON AIRPORT DURING CONSTRUCTION, LATEST EDITION. LIGHTED BARRICADES MUST BE NO TALLER THAN 18" (EXCLUSIVE OF SUPPLEMENTARY LIGHTS AND FLAGS) ON THE TAXIWAYS AND COMPLY WITH ADVISORY CIRCULAR 150/5370-2, LATEST EDITION. CONTRACTOR SHALL NIGHT CHECK BARRICADES DAILY FOR PROPER OPERATION.
- NO OPEN TRENCHES WITHIN 250' OF AN ACTIVE RUNWAY CENTERLINE OR WITHIN 93' OF ANY AIRPORT OPERATIONS AREA WILL BE PERMITTED UNLESS PROPERLY MARKED. OTHER TRENCHES SHALL BE MAINTAINED SAFE, I.E., BARRICADED OR COVERED WITH STEEL PLATES IN ALL OTHER AREAS.
- OPEN TRENCHES, EXCAVATIONS, AND STOCKPILED MATERIALS AT THE CONSTRUCTION SITE SHOULD BE PROMINENTLY MARKED WITH ORANGE FLAGS AND LIGHTED WITH FLASHING RED LIGHTS DURING HOURS OF RESTRICTED VISIBILITY AND/OR DARKNESS.
- NO CONSTRUCTION EQUIPMENT GREATER THAN 25' TALL WILL BE PERMITTED ON THE AIRPORT. HOWEVER OTHER EQUIPMENT TALLER THAN 25' MAY BE PERMITTED WITH THE APPROVAL OF THE AIRPORT MANAGER AND AIRSPACE APPROVAL BY THE FAA.
- NO OPEN FLAME WELDING OR TORCH CUTTING OPERATION IS PERMITTED UNLESS ADEQUATE FIRE AND SAFETY PRECAUTIONS ARE PROVIDED AND HAVE BEEN APPROVED BY THE AIRPORT MANAGER NO FLARE POTS ARE ALLOWED ON THE PROJECT.
- SOIL, DEBRIS, AND LOOSE MATERIAL DROPPED OR TRUCKED ONTO AIRPORT ROADS, TAXIWAYS, AND SOD SURFACES, OR WHICH CAN BE BLOWN ONTO SUCH SURFACES, SHALL BE IMMEDIATELY SWEEPED, PICKED UP AND REMOVED, OR PLACED INTO CLOSED CONTAINERS. ANY DAMAGE TO AIRPORT PROPERTY SHALL BE REPAIRED IMMEDIATELY AT NO COST TO THE OWNER.
- EACH CONTRACTOR SHALL BE RESPONSIBLE FOR LOCATING AND MAINTAINING AIRPORT LIGHTING AND NAVIGATIONAL ELECTRICAL SYSTEMS DURING CONSTRUCTION. A CONTACT PERSON AND TELEPHONE NUMBER FOR 24 HOUR EMERGENCY IMMEDIATE REPAIR SHALL BE SUBMITTED TO THE AIRPORT MANAGER AND RESIDENT ENGINEER/TECHNICIAN. HAUL ROUTES CROSSING PAVEMENT, DRAINAGE, MISCELLANEOUS, STRUCTURES AND/OR AIRFIELD CABLES SHALL BE PROTECTED FROM DAMAGE.
- ALL AIRCRAFT AND AIRPORT OPERATIONS HAVE THE RIGHT-OF-WAY. CONTRACTOR TO YIELD TO VEHICLES AND REMAIN CLEAR AT ALL TIMES.
- CONTRACTOR SHALL PLACE, SECURE, AND MAINTAIN LIGHTED BARRICADES AND CLOSURE CROSSES WHEN A RUNWAY/TAXIWAY/APRON IS CLOSED OR AS REQUIRED BY THE PLANS AND DESIGNATED BY THE RESIDENT ENGINEER/TECHNICIAN.
- CONTRACTOR SHALL MARK HAZARDOUS AREA WITH STEADY-BURNING OR FLASHING RED LIGHTS DURING PERIODS OF LOW VISIBILITY AS REQUIRED.
- THE CONTRACTOR SHALL PERIODICALLY PERFORM ONSITE INSPECTIONS THROUGHOUT THE DURATION OF THE PROJECT WITH THE IMMEDIATE REMEDY OF ANY DIFFERENCES, WHETHER CAUSED BY NEGLIGENCE, OVERSIGHT, OR PROJECT SCOPE CHANGE.
- CONTRACTOR SHALL MOVE MAINTENANCE OF TRAFFIC COMPONENTS AT THE WRITTEN DIRECTION OF THE RESIDENT ENGINEER/TECHNICIAN AT NO ADDITIONAL COST.
- CONTRACTOR SHALL NOT REMOVE THE BARRICADES WITHOUT THE APPROVAL BY THE RESIDENT ENGINEER/TECHNICIAN.
- CONTRACTOR SHALL MAINTAIN FLASHERS, SIGNS AND/OR BARRICADES AS REQUIRED BY THE PLANS, CITY OR COUNTY REGULATIONS OR CONTRACTOR ACTIVITIES. CONTRACTOR SHALL OBTAIN ANY AND ALL REQUIRED LOCAL PERMITS UNLESS SPECIFIED OTHERWISE.
- THE CONTRACTOR SHALL UTILIZE WATER AND/OR CHEMICALS APPROVED BY THE RESIDENT ENGINEER/TECHNICIAN AS NECESSARY TO CONTROL DUST.
- NO CONSTRUCTION VEHICLES SHALL BE DRIVEN ACROSS ANY ACTIVE RUNWAY, INCLUDING TURF RUNWAYS. CONSTRUCTION EQUIPMENT OR CONSTRUCTION ACTIVITY WILL NOT BE PERMITTED WITHIN 250' OF ANY ACTIVE RUNWAY CENTERLINE OR WITHIN 93' OF ANY OTHER ACTIVE AIRPORT TAXIWAY OR APRON. HOWEVER, CONSTRUCTION MAY BE PERMITTED IN THESE AREAS IF THE CONTRACTOR HAS GAINED APPROVAL FROM THE AIRPORT MANAGER AT LEAST 7 DAYS IN ADVANCE OF THE SCHEDULED CONSTRUCTION PERIOD AND THE OPERATIONAL AREA IS CLOSED TO TRAFFIC AND PROPER NOTAMS ARE ISSUED BY THE AIRPORT MANAGER TO THE APPROPRIATE FLIGHT SERVICE STATION.
- UNLESS SPECIFIED OTHERWISE, COST FOR THE ABOVE IS TO BE CONSIDERED INCIDENTAL TO THE PROJECT. SEPARATE PAYMENT SHALL NOT BE MADE.



SIGNAGE NOTES

- ALL CONSTRUCTION SIGNS AND TRAFFIC CONTROL DEVICES SHALL CONFORM TO THE MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES INCLUDING THE ILLINOIS SUPPLEMENT (LATEST EDITION) AND THE FAA ADVISORY CIRCULARS (LATEST EDITION) UNLESS NOTED OTHERWISE. THE FAA OR MORE STRINGENT SPECIFICATIONS SHALL GOVERN.
- UNLESS OTHERWISE SPECIFIED, CONSTRUCTION SIGNS SHALL BE MOUNTED ON PORTABLE OR NON-PORTABLE SUPPORTS. A PORTABLE SUPPORT IS DEFINED AS A TYPICAL SIGN STANDARD AS SHOWN ON THIS SHEET, OR A SMALL LIGHT WEIGHT TRAILER. A NON-PORTABLE SUPPORT IS DEFINED AS DRIVEN METAL OR WOOD POST. ALL SIGNS, REGARDLESS OF THE TYPE OF SUPPORTS USED, SHALL BE MOUNTED SUCH THAT THE MESSAGE ON THE SIGN IS LEVEL IN THE HORIZONTAL PLANE AFTER PLACEMENT. THE COST OF CONSTRUCTION WARNING LIGHTS SHALL BE INCLUDED IN THE COST OF THE CONSTRUCTION SIGNS.
- CONSTRUCTION RED WARNING LIGHT: THESE ARE PORTABLE, LENS DIRECTED, ENCLOSED LIGHTS. THE COLOR OF THE LIGHT EMITTED SHALL BE RED. THEY ARE TO BE USED IN A LOW INTENSITY FLASHING MODE (TYPE A).
- THE LIGHTING SHALL BE MAINTAINED IN OPERATION DURING THE HOURS OF DARKNESS BETWEEN 1/2 HOUR AFTER SUNSET AND 1/2 HOUR BEFORE SUNRISE AND WHEN CONDITIONS EXIST WHICH TEND TO OBSCURE VISION.
- COST FOR PROVIDING, PLACING, MAINTAINING, AND REMOVING SIGNS SHALL BE INCLUDED IN ITEM AR150540 HAUL ROUTE.



W20-3
48" x 48" A



W20-3
48" x 48" B

CONSTRUCTION SIGNS

NOT TO SCALE



Jaycen R. Herndon

DATE: 11/18/2021 LICENSE: 2/28/2022
SIGNED: 11/18/2021 EXPIRES: 2/28/2022

REHABILITATE
RUNWAY 17-35
PAVEMENT & LIGHTING

SBG No:
3-17-SBGP-171/175
IDA No: ALN-4812

Contract No. SR095

NO.	DATE	DESCRIPTION		
		DES	DWN	REV

ISSUE: NOVEMBER 19, 2021

PROJECT NO: 17A008504

CAD FILE: G-501-SFY.DWG

DESIGN BY: JRH 4/12/2021

DRAWN BY: JRH 4/16/2021

REVIEWED BY: BSS 4/16/2021

SHEET TITLE



CONSTRUCTION
SAFETY DETAILS
AND NOTES -
SHEET 2

CLOSURE CROSS NOTES

1. RUNWAY CLOSURE CROSS MARKINGS SHALL BE LIGHTED DURING DARKNESS AND PERIODS OF REDUCED VISIBILITY. THE LIGHTED MARKERS SHALL BE PLACED OVER THE RUNWAY NUMERALS OR IMMEDIATELY OFF THE END OF THE RUNWAY ON THE EXTENDED CENTERLINE, AS DIRECTED BY THE RESIDENT ENGINEER/TECHNICIAN.
2. THE CONTRACTOR SHALL PROVIDE THE RUNWAY CLOSURE CROSSES BY ONE OF TWO OPTIONS:


OPTION 1: TEMPORARY CLOSURE CROSS MARKINGS SHALL BE CONSTRUCTED OF PLYWOOD, SNOW FENCE OR APPROVED FABRIC AND SHALL BE SECURED TO PAVEMENT BY SANDBAGS OR OTHER APPROVED METHOD.

OPTION 2: THE CONTRACTOR SHALL PROVIDE TWO (2) L-893 LIGHTED RUNWAY CLOSURE MARKERS, MEETING THE REQUIREMENTS IN FAA ADVISORY CIRCULAR 150/5345-55 AND SHALL BE IN PLACE AND OPERATING WHENEVER THE RUNWAY IS CLOSED AND REMOVED WHEN THE RUNWAY IS RE-OPENED.
3. TAXIWAY CLOSURE CROSSES SHALL MEET OPTION 1 IN THE ABOVE NOTE.
4. THE CONTRACTOR SHALL MAKE FREQUENT INSPECTION OF THE LIGHTED CROSSES AND MAKE PROMPT REPAIRS AS NECESSARY.
5. THE CONTRACTOR SHALL BE ON-CALL FOR 24-HOUR EMERGENCY MAINTENANCE WHEN LIGHTED CROSSES ARE BEING USED.
6. LIGHTED MARKERS SHALL BE SECURED FROM WIND EFFECTS BY THE CONTRACTOR AS RECOMMENDED BY THE MANUFACTURER.
7. COST FOR PROVIDING, PLACING, OPERATING, MAINTAINING, RELOCATING AND REMOVING CLOSURE CROSSES SHALL BE INCLUDED IN THE COST OF THE TRAFFIC MAINTENANCE.





BARRICADE NOTES

1. ALL CONSTRUCTION SIGNS AND TRAFFIC CONTROL DEVICES SHALL CONFORM TO THE MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES INCLUDING THE ILLINOIS SUPPLEMENT (LATEST EDITION) AND THE FAA ADVISORY CIRCULARS (LATEST EDITION) UNLESS NOTED OTHERWISE. THE FAA OR MORE STRINGENT SPECIFICATIONS SHALL GOVERN.
2. BARRICADES SHALL BE "LOW-PROFILE" WITH A MAXIMUM HEIGHT OF 18" ABOVE GROUND, EXCLUSIVE OF ASSOCIATED WARNING LIGHTS AND FLAGS.
3. BARRICADES SHALL BE SPACED END TO END THE WIDTH OF THE PAVEMENT, WITH GAPS BETWEEN BARRICADES NOT TO EXCEED 4' WIDE. BARRICADES ARE TO BE SET BACK 66' FROM THE ACTIVE TAXIWAY CENTERLINE OR AS SHOWN ON THE PLANS.
4. CONSTRUCTION RED WARNING LIGHT: THESE ARE PORTABLE, LENS DIRECTED, ENCLOSED LIGHTS. THE COLOR OF THE LIGHT EMITTED SHALL BE RED. THEY MAY BE USED IN EITHER A STEADY BURN (TYPE C) OR LOW INTENSITY FLASHING MODE (TYPE A) UNLESS NOTED OTHERWISE.
5. THE LIGHTING SHALL BE MAINTAINED IN OPERATION DURING THE HOURS OF DARKNESS BETWEEN 1/2 HOUR BEFORE SUNSET AND 1/2 HOUR AFTER SUNRISE AND WHEN CONDITIONS EXIST WHICH TEND TO OBSCURE VISION.
6. BARRICADES SHALL BE SECURED TO THE GROUND BY APPROVED METHODS TO PREVENT MOVEMENT BY PROP WASH, JET BLAST OR OTHER WIND CURRENTS.
7. THE ONLY COLOR COMBINATION ON BARRICADES IS ORANGE AND WHITE. THE ORANGE STRIPES SHALL BE ENCAPSULATED LENS REFLECTIVE SHEETING. THE WHITE STRIPES SHALL BE EITHER ENCAPSULATED OR ENCLOSED LENS REFLECTIVE SHEETING AND MUST BE IN ACCEPTABLE CONDITION.
8. COST FOR PROVIDING, PLACING, MAINTAINING, AND REMOVING BARRICADES SHALL BE PAID FOR UNDER ITEM AR150520 - MOBILIZATION.




DETAIL ABOVE REPRESENTS ONE OPTION FOR LOW-PROFILE BARRICADES. OTHER OPTIONS MAY BE UTILIZED AS LONG AS THEY MEET THE REQUIREMENTS OF THE PROJECT, INCLUDING BARRICADE NOTE 1.

NOV 18, 2021 11:29 AM HERND01562
 I:\17\JOBS\17A08504\CAD\AIRPORT\T\SHEETC-121-CON



KEYMAP



LEGEND:

- EXISTING PAVEMENT
- PROPOSED RUNWAY REHAB
- PROPOSED BUTT JOINT
- PROPOSED SAWCUT
- EXISTING STORM SEWER
- EXISTING UNDERDRAIN
- EXISTING INLET
- EXISTING UNDERDRAIN CLEANOUT/INSPECTION HOLE

KEYNOTES

- (A) EXISTING UNDERDRAIN CLEANOUT/INSPECTION HOLE (NOT SURVEYED) TO BE ADJUSTED TO MATCH FINAL SHOULDER GRADE. FIELD VERIFY LOCATION & ELEVATION.
- (B) EXISTING UNDERDRAIN CLEANOUT/INSPECTION HOLE (SURVEYED) TO BE ADJUSTED TO MATCH FINAL SHOULDER GRADE. EXIST TOC - XXX.XX

HANSON
 Engineering | Planning | Allied Services
 Hanson Professional Services Inc.
 1525 S. 6th Street
 Springfield, IL 62703
 phone: 217-788-2450
 fax: 217-788-2503
 Offices Nationwide
 www.hanson-inc.com
 Illinois Licensed
 Professional Service Corporation
 #184-001084



ST. LOUIS REGIONAL AIRPORT
 8 Terminal Drive
 East Alton, Illinois 62024



Jaycen R. Herndon

DATE: 11/18/2021 LICENSE: 062.069664
 SIGNED: 11/18/2021 EXPIRES: 2/28/2022

REHABILITATE RUNWAY 17-35 PAVEMENT & LIGHTING

SBG No: 3-17-SBGP-171/175
 IDA No: ALN-4812

Contract No. SR095

NO.	DATE	DESCRIPTION		
		DES	DWN	REV

ISSUE: NOVEMBER 19, 2021
 PROJECT NO: 17A008504
 CAD FILE: C-121-CON.DWG
 DESIGN BY: JRH 3/18/2021
 DRAWN BY: JRH 4/16/2021
 REVIEWED BY: BSS 4/16/2021

SHEET TITLE

PROPOSED CONSTRUCTION
 PLAN - STA. 115+00
 TO STA. 133+00

FOR BID



Jaycen Herndon

DATE SIGNED: 11/18/2021 LICENSE EXPIRES: 2/28/2022

**REHABILITATE
RUNWAY 17-35
PAVEMENT & LIGHTING**

SBG No:
3-17-SBGP-171/175
IDA No: ALN-4812

Contract No. SR095

NO.	DATE	DESCRIPTION		
		DES	DWN	REV

ISSUE: NOVEMBER 19, 2021

PROJECT NO: 17A008504

CAD FILE: C-121-CON.DWG

DESIGN BY: JRH 3/18/2021


DRAWN BY: JRH 4/16/2021

REVIEWED BY: BSS 4/16/2021


SHEET TITLE

PROPOSED
CONSTRUCTION
PLAN - STA. 133+00
TO STA. 151+00

FOR BID



KEYMAP




LEGEND:

- EXISTING PAVEMENT
- PROPOSED RUNWAY REHAB
- PROPOSED BUTT JOINT
- PROPOSED SAWCUT
- EXISTING STORM SEWER
- EXISTING UNDERDRAIN
- EXISTING INLET
- EXISTING UNDERDRAIN CLEANOUT/INSPECTION HOLE

KEYNOTES

- (A) EXISTING UNDERDRAIN CLEANOUT/INSPECTION HOLE (NOT SURVEYED) TO BE ADJUSTED TO MATCH FINAL SHOULDER GRADE. FIELD VERIFY LOCATION & ELEVATION.
- (B) EXISTING UNDERDRAIN CLEANOUT/INSPECTION HOLE (SURVEYED) TO BE ADJUSTED TO MATCH FINAL SHOULDER GRADE. EXIST TOC - XXX.XX



NOV 18, 2021 11:29 AM HERNDON1562
I:\17\JOBS\17A008504\CAD\AIRPORT\T\SHEETC-121-CON



Jaycen Herndon

DATE: 11/18/2021 LICENSE: 2/28/2022
SIGNED: 11/18/2021 EXPIRES: 2/28/2022

**REHABILITATE
RUNWAY 17-35
PAVEMENT & LIGHTING**

SBG No:
3-17-SBGP-171/175
IDA No: ALN-4812


Contract No. SR095

NO.	DATE	DESCRIPTION		
		DES	DWN	REV


ISSUE: NOVEMBER 19, 2021
PROJECT NO: 17A008504
CAD FILE: C-121-CON.DWG
DESIGN BY: JRH 3/18/2021
DRAWN BY: JRH 4/16/2021
REVIEWED BY: BSS 4/16/2021

SHEET TITLE

PROPOSED
CONSTRUCTION
PLAN - STA. 151+00
TO STA. 165+99



KEYMAP




LEGEND:

- EXISTING PAVEMENT
- PROPOSED RUNWAY REHAB
- PROPOSED BUTT JOINT
- PROPOSED SAWCUT
- EXISTING STORM SEWER
- EXISTING UNDERDRAIN
- EXISTING INLET
- EXISTING UNDERDRAIN CLEANOUT/INSPECTION HOLE

KEYNOTES

- (A) EXISTING UNDERDRAIN CLEANOUT/INSPECTION HOLE (NOT SURVEYED) TO BE ADJUSTED TO MATCH FINAL SHOULDER GRADE. FIELD VERIFY LOCATION & ELEVATION.
- (B) EXISTING UNDERDRAIN CLEANOUT/INSPECTION HOLE (SURVEYED) TO BE ADJUSTED TO MATCH FINAL SHOULDER GRADE. EXIST TOC - XXX.XX



NOV 18, 2021 11:29 AM HERND01562 I:\17\JOBS\17A008504\CAD\AIRPORT\T\SHEETC-121-CON

FOR BID



Jaycen R. Herndon

DATE SIGNED: 11/18/2021 LICENSE EXPIRES: 2/28/2022

**REHABILITATE
RUNWAY 17-35
PAVEMENT & LIGHTING**

SBG No:
3-17-SBGP-171/175
IDA No: ALN-4812

Contract No. SR095

NO.	DATE	DESCRIPTION		
		DES	DWN	REV

ISSUE: NOVEMBER 19, 2021

PROJECT NO: 17A008504

CAD FILE: C-181-STK.DWG



DESIGN BY: JRH 4/12/2021

DRAWN BY: JRH 4/16/2021

REVIEWED BY: BSS 4/16/2021

SHEET TITLE

**PROPOSED
VARIABLE MILLING
PLAN**




LEGEND:

- EXISTING PAVEMENT
- PROPOSED RUNWAY REHAB
- EXISTING STORM SEWER
- EXISTING UNDERDRAIN
- EXISTING INLET
- EXISTING UNDERDRAIN CLEANOUT/INSPECTION HOLE

NO.	MIN. MILL DEPTH	MAX. MILL DEPTH	COLOR
1	-4"	-5"	Red
2	-3"	-4"	Yellow
3	-2"	-3"	Green
4	-1"	-2"	Blue
5	0"	-1"	Purple

NOTES:

- THIS PLAN SHEET IS INTENDED TO BE PRINTED IN COLOR FOR BEST VISIBILITY.
- FOLLOWING THE PROJECT AWARD, THE ENGINEER CAN PROVIDE THE RELEVANT AUTOCAD AND CIVIL 3D SURFACE MODEL FILES TO THE AWARDED CONTRACTOR UPON REQUEST TO ASSIST WITH CONSTRUCTION LAYOUT.



NOV 18, 2021 11:29 AM HERND01562
I:\17\JOBS\17A008504\CAD\AIRPORT\181-STK

FOR BID



Jaycen R. Herndon

DATE SIGNED: 11/18/2021 LICENSE EXPIRES: 2/28/2022

**REHABILITATE
RUNWAY 17-35
PAVEMENT & LIGHTING**

SBG No:
3-17-SBGP-171/175
IDA No: ALN-4812

Contract No. SR095

NO.	DATE	DESCRIPTION		
		DES	DWN	REV

ISSUE: NOVEMBER 19, 2021

PROJECT NO: 17A008504

CAD FILE: C-701-PNP.DWG




DESIGN BY: JRH 3/18/2021

DRAWN BY: JRH 4/16/2021

REVIEWED BY: BSS 4/16/2021


SHEET TITLE

**PROPOSED PLAN &
PROFILE - STA. 99+00
TO STA. 106+00**



LEGEND:

- EXISTING PAVEMENT
- PROPOSED RUNWAY REHAB
- PROPOSED BUTT JOINT
- PROPOSED 10' SHOULDER ADJUSTMENT/TOPSOILING
- EXISTING STORM SEWER
- EXISTING UNDERDRAIN
- EXISTING INLET
- EXISTING UNDERDRAIN CLEANOUT/INSPECTION HOLE



NOV 18, 2021 11:29 AM HERNDON1562 I:\17\JOBS\17A008504\CAD\AIRPORT\T\SHEET\C-701-PNP

FOR BID



Jaycen R. Herndon

DATE: 11/18/2021 LICENSE: 062.069664
SIGNED: 11/18/2021 EXPIRES: 2/28/2022

**REHABILITATE
RUNWAY 17-35
PAVEMENT & LIGHTING**

SBG No:
3-17-SBGP-171/175
IDA No: ALN-4812



Contract No. SR095

NO.	DATE	DESCRIPTION		
		DES	DWN	REV


ISSUE: NOVEMBER 19, 2021
PROJECT NO: 17A008504
CAD FILE: C-701-PNP.DWG
DESIGN BY: JRH 3/18/2021
DRAWN BY: JRH 4/16/2021
REVIEWED BY: BSS 4/16/2021

SHEET TITLE

PROPOSED PLAN &
PROFILE - STA.
106+00 TO STA.
115+00




KEYMAP



LEGEND:

- EXISTING PAVEMENT
- PROPOSED RUNWAY REHAB
- PROPOSED BUTT JOINT
- PROPOSED 10' SHOULDER ADJUSTMENT/TOPSOILING
- EXISTING STORM SEWER
- EXISTING UNDERDRAIN
- EXISTING INLET
- EXISTING UNDERDRAIN CLEANOUT/INSPECTION HOLE



FOR BID

NOV 18, 2021 11:29 AM HERNDON1562
I:\17\JOBS\17A008504\CAD\AIRPORT\T\SHEET\C-701-PNP



Jaycen Herndon

DATE: 11/18/2021 LICENSE: 062.069664
 SIGNED: 11/18/2021 EXPIRES: 2/28/2022

**REHABILITATE
 RUNWAY 17-35
 PAVEMENT & LIGHTING**

SBG No:
 3-17-SBGP-171/175
 IDA No: ALN-4812


Contract No. SR095

NO.	DATE	DESCRIPTION		
		DES	DWN	REV


ISSUE: NOVEMBER 19, 2021
 PROJECT NO: 17A008504
 CAD FILE: C-701-PNP.DWG
 DESIGN BY: JRH 3/18/2021
 DRAWN BY: JRH 4/16/2021
 REVIEWED BY: BSS 4/16/2021

SHEET TITLE

**PROPOSED PLAN &
 PROFILE - STA.
 124+00 TO STA.
 133+00**





KEYMAP



LEGEND:

- EXISTING PAVEMENT
- PROPOSED RUNWAY REHAB
- PROPOSED BUTT JOINT
- PROPOSED 10' SHOULDER ADJUSTMENT/TOPSOILING
- EXISTING STORM SEWER
- EXISTING UNDERDRAIN
- EXISTING INLET
- EXISTING UNDERDRAIN CLEANOUT/INSPECTION HOLE



NOV 18, 2021 11:29 AM HERNDON1562
 I:\17\JOBS\17A008504\CAD\AIRPORT\TSHEET\C-701-PNP

FOR BID



Jaycen Herndon

DATE: 11/18/2021 LICENSE: 062.069664
SIGNED: 11/18/2021 EXPIRES: 2/28/2022

**REHABILITATE
RUNWAY 17-35
PAVEMENT & LIGHTING**

SBG No:
3-17-SBGP-171/175
IDA No: ALN-4812


Contract No. SR095

NO.	DATE	DESCRIPTION		
		DES	DWN	REV


ISSUE: NOVEMBER 19, 2021
PROJECT NO: 17A008504
CAD FILE: C-701-PNP.DWG
DESIGN BY: JRH 3/18/2021
DRAWN BY: JRH 4/16/2021
REVIEWED BY: BSS 4/16/2021

SHEET TITLE

PROPOSED PLAN &
PROFILE - STA.
133+00 TO STA.
142+00





KEYMAP



LEGEND:

- EXISTING PAVEMENT
- PROPOSED RUNWAY REHAB
- PROPOSED BUTT JOINT
- PROPOSED 10' SHOULDER ADJUSTMENT/TOPSOILING
- EXISTING STORM SEWER
- EXISTING UNDERDRAIN
- EXISTING INLET
- EXISTING UNDERDRAIN CLEANOUT/INSPECTION HOLE



NOV 18, 2021 11:30 AM HERNDON1562
I:\17\JOBS\17A008504\CAD\AIRPORT\T\SHEET\C-701-PNP

FOR BID



Jaycen Herndon

DATE: 11/18/2021 LICENSE: 062.069664
SIGNED: 11/18/2021 EXPIRES: 2/28/2022

**REHABILITATE
RUNWAY 17-35
PAVEMENT & LIGHTING**

SBG No:
3-17-SBGP-171/175
IDA No: ALN-4812


Contract No. SR095

NO.	DATE	DESCRIPTION		
		DES	DWN	REV

ISSUE: NOVEMBER 19, 2021
PROJECT NO: 17A008504
CAD FILE: C-701-PNP.DWG
DESIGN BY: JRH 3/18/2021
DRAWN BY: JRH 4/16/2021
REVIEWED BY: BSS 4/16/2021

SHEET TITLE

**PROPOSED PLAN &
PROFILE - STA.
151+00 TO STA.
160+00**





KEYMAP



0' 20' 40' 80'
HALF SIZE SCALE: 1" = 80'
FULL SIZE SCALE: 1" = 40'

LEGEND:

- EXISTING PAVEMENT
- PROPOSED RUNWAY REHAB
- PROPOSED BUTT JOINT
- PROPOSED 10' SHOULDER ADJUSTMENT/TOPSOILING
- EXISTING STORM SEWER
- EXISTING UNDERDRAIN
- EXISTING INLET
- EXISTING UNDERDRAIN CLEANOUT/INSPECTION HOLE



NOV 18, 2021 11:30 AM HERNDON1562
I:\17\JOBS\17A008504\CAD\AIRPORT\T\SHEET\C-701-PNP

FOR BID



Jaycen Herndon

DATE: 11/18/2021 LICENSE: 062.069664
SIGNED: 11/18/2021 EXPIRES: 2/28/2022

**REHABILITATE
RUNWAY 17-35
PAVEMENT & LIGHTING**

SBG No:
3-17-SBGP-171/175
IDA No: ALN-4812


Contract No. SR095

NO.	DATE	DESCRIPTION		
		DES	DWN	REV


ISSUE: NOVEMBER 19, 2021
PROJECT NO: 17A008504
CAD FILE: C-701-PNP.DWG
DESIGN BY: JRH 3/18/2021
DRAWN BY: JRH 4/16/2021
REVIEWED BY: BSS 4/16/2021

SHEET TITLE

PROPOSED PLAN &
PROFILE - STA.
160+00 TO STA.
165+99





KEYMAP



LEGEND:

- EXISTING PAVEMENT
- PROPOSED RUNWAY REHAB
- PROPOSED BUTT JOINT
- PROPOSED 10' SHOULDER ADJUSTMENT/TOPSOILING
- EXISTING STORM SEWER
- EXISTING UNDERDRAIN
- EXISTING INLET
- EXISTING UNDERDRAIN CLEANOUT/INSPECTION HOLE



NOV 18, 2021 11:30 AM HERNDON1562 I:\17\JOBS\17A008504\CAD\AIRPORT\T\SHEET\C-701-PNP

FOR BID



Jaycen Herndon

DATE: 11/18/2021 LICENSE: 062.069664
SIGNED: 11/18/2021 EXPIRES: 2/28/2022

**REHABILITATE
RUNWAY 17-35
PAVEMENT & LIGHTING**

SBG No:
3-17-SBGP-171/175
IDA No: ALN-4812


Contract No. SR095

NO.	DATE	DESCRIPTION		
		DES	DWN	REV


ISSUE: NOVEMBER 19, 2021
PROJECT NO: 17A008504
CAD FILE: C-701-PNP.DWG
DESIGN BY: JRH 3/18/2021
DRAWN BY: JRH 4/16/2021
REVIEWED BY: BSS 4/16/2021

SHEET TITLE

PROPOSED PLAN &
PROFILE - STA.
205+50 TO STA.
215+50





KEYMAP



0' 20' 40' 80'
HALF SIZE SCALE: 1" = 80'
FULL SIZE SCALE: 1" = 40'

LEGEND:

- EXISTING PAVEMENT
- PROPOSED RUNWAY REHAB
- PROPOSED BUTT JOINT
- PROPOSED 10' SHOULDER ADJUSTMENT/TOPSOILING
- EXISTING STORM SEWER
- EXISTING UNDERDRAIN
- EXISTING INLET
- EXISTING UNDERDRAIN CLEANOUT/INSPECTION HOLE



NOV 18, 2021 11:30 AM HERNDON1562
I:\17\JOBS\17A008504\CAD\AIRPORT\T\SHEET\C-701-PNP

FOR BID



Jaycen R. Herndon

DATE SIGNED: 11/18/2021 LICENSE EXPIRES: 2/28/2022

**REHABILITATE
 RUNWAY 17-35
 PAVEMENT & LIGHTING**

SBG No:
 3-17-SBGP-171/175
 IDA No: ALN-4812



Contract No. SR095

NO.	DATE	DESCRIPTION		
		DES	DWN	REV


ISSUE: NOVEMBER 19, 2021
 PROJECT NO: 17A008504
 CAD FILE: C-182-STK.DWG
 DESIGN BY: JRH 4/12/2021
 DRAWN BY: JRH 4/16/2021
 REVIEWED BY: BSS 4/16/2021

SHEET TITLE

**PROPOSED STAKING
 PLAN**



- LEGEND:**
- EXISTING PAVEMENT
 - PROPOSED RUNWAY REHAB
 - EXISTING STORM SEWER
 - EXISTING UNDERDRAIN
 - EXISTING INLET
 - EXISTING UNDERDRAIN CLEANOUT/INSPECTION HOLE



NOV 18, 2021 11:30 AM HERNDON1562
 I:\17 JOBS\17A008504\CAD\AIRPORT\T\SHEET\C-182-STK

FOR BID



Jaycen Herndon

DATE: 11/18/2021
LICENSE: 062.069664
SIGNED: 11/18/2021 EXPIRES: 2/28/2022

**REHABILITATE
RUNWAY 17-35
PAVEMENT & LIGHTING**

SBG No:
3-17-SBGP-171/175
IDA No: ALN-4812


Contract No. SR095

NO.	DATE	DESCRIPTION		
		DES	DWN	REV


ISSUE: NOVEMBER 19, 2021
PROJECT NO: 17A008504
CAD FILE: C-151-MRK.DWG
DESIGN BY: CEM 3/18/2021
DRAWN BY: CEM 3/18/2021
REVIEWED BY: JRH 3/22/2021

SHEET TITLE

PROPOSED MARKING
PLAN - STA. 115+00
TO STA. 133+00




KEYMAP



LEGEND:



- EXISTING PAVEMENT
- PROPOSED RUNWAY REHAB




NOV 18, 2021 11:30 AM HERNDON1562
I:\17\JOBS\17A008504\CAD\AIRPORT\T\SHEETC-151-MRK

FOR BID

NOV 18, 2021 11:30 AM HERND01562
 I:\17\JOBS\17A08504\CAD\AIRPORT\T\SHEETC-151-MRK



KEYMAP



LEGEND:

- EXISTING PAVEMENT
- PROPOSED RUNWAY REHAB



Engineering | Planning | Allied Services
 Hanson Professional Services Inc.
 1525 S. 6th Street
 Springfield, IL 62703
 phone: 217-788-2450
 fax: 217-788-2503
 Offices Nationwide
 www.hanson-inc.com

Illinois Licensed
 Professional Service Corporation
 #184-001084



ST. LOUIS REGIONAL AIRPORT
 8 Terminal Drive
 East Alton, Illinois 62024



Jaycen R. Herndon

DATE: 11/18/2021
 LICENSE: 062.069664
 SIGNED: 11/18/2021
 EXPIRES: 2/28/2022

**REHABILITATE
 RUNWAY 17-35
 PAVEMENT & LIGHTING**

SBG No:
 3-17-SBGP-171/175
 IDA No: ALN-4812

Contract No. SR095

NO.	DATE	DESCRIPTION		
		DES	DWN	REV

ISSUE: NOVEMBER 19, 2021
 PROJECT NO: 17A008504
 CAD FILE: C-151-MRK.DWG
 DESIGN BY: CEM 3/18/2021
 DRAWN BY: CEM 3/18/2021
 REVIEWED BY: JRH 3/22/2021

SHEET TITLE

PROPOSED MARKING
 PLAN - STA. 133+00
 TO STA. 151+00

FOR BID



Engineering | Planning | Allied Services

Hanson Professional Services Inc.
1525 S. 6th Street
Springfield, IL 62703
phone: 217-788-2450
fax: 217-788-2503

Offices Nationwide
www.hanson-inc.com

Illinois Licensed
Professional Service Corporation
#184-001084



ST. LOUIS REGIONAL AIRPORT

8 Terminal Drive
East Alton, Illinois 62024



DATE SIGNED: 11/18/2021 LICENSE EXPIRES: 2/28/2022

REHABILITATE
RUNWAY 17-35
PAVEMENT & LIGHTING

SBG No:
3-17-SBGP-171/175
IDA No: ALN-4812


Contract No. SR095

NO.	DATE	DESCRIPTION		
		DES	DWN	REV


ISSUE: NOVEMBER 19, 2021
PROJECT NO: 17A008504
CAD FILE: C-151-MRK.DWG
DESIGN BY: CEM 3/18/2021
DRAWN BY: CEM 3/18/2021
REVIEWED BY: JRH 3/22/2021

SHEET TITLE

PROPOSED MARKING
PLAN - STA. 151+00
TO STA. 165+99





KEYMAP



LEGEND:

- EXISTING PAVEMENT
- PROPOSED RUNWAY REHAB




FOR BID

NOV 18, 2021 11:30 AM HERNDON1562
I:\17\JOBS\17A008504\CAD\AIRPORT\TSHEETC-151-MRK


MARKING QUANTITIES	
YELLOW MARKING	TOTAL AREA (S.F.)
TAXIWAY CENTERLINES	2,439
RUNWAY HOLDING POSITION	713
TOTAL YELLOW:	3,152
WHITE MARKING	TOTAL AREA (S.F.)
RUNWAY CENTERLINE STRIPES	7,094
THRESHOLD BARS	13,800
AIMING POINTS	20,699
RUNWAY EDGE STRIPES	42,894
RUNWAY NUMERALS	2,174
TOTAL WHITE:	86,661
BLACK MARKING	TOTAL AREA (S.F.)
TAXIWAY CENTERLINES	2,439
RUNWAY HOLDING POSITION	1,183
RUNWAY CENTERLINE STRIPES	4,224
THRESHOLD BARS	2,508
AIMING POINTS	1,020
RUNWAY EDGE STRIPES	7,149
RUNWAY NUMERALS	366
TOTAL BLACK:	18,889
TOTAL YELLOW AND WHITE:	89,813
TOTAL BLACK:	18,889
TOTAL MARKING	108,702

PAVEMENT MARKING NOTES

- GLASS BEADS SHALL BE REQUIRED FOR ALL WHITE AND YELLOW PERMANENT PAINT MARKINGS. GLASS BEADS ARE NOT REQUIRED FOR TEMPORARY MARKINGS OR BLACK PAINT. REFER TO SPECIFICATION ITEM P-620 FOR ADDITIONAL INFORMATION.
- IMMEDIATELY PRIOR TO THE APPLICATION OF PAINT, ALL SURFACES SHALL BE DRY AND FREE FROM DIRT, GREASE, OIL, LAITANCE, OR OTHER FOREIGN MATERIAL WHICH WOULD REDUCE THE BOND BETWEEN THE PAINT AND THE PAVEMENT. THIS SHALL INCLUDE PAINTED AREAS ON THE EXISTING PAVEMENTS. REFER TO SPECIFICATION P-620-3.3 FOR ADDITIONAL INFORMATION.
- EXISTING PAVEMENT MARKINGS OUTSIDE THE LIMITS OF THE MARKINGS SHOWN ON THE MARKING PLAN WHICH ARE REMOVED OR WORN DUE TO CONSTRUCTION ACTIVITY SHALL BE REPAINTED. NO ADDITIONAL COMPENSATION SHALL BE MADE FOR THIS WORK.
- NUMERAL MARKING TEMPLATES FOR SURFACE PAINTED HOLD POSITION SIGN MARKINGS SHALL BE PROVIDED BY THE CONTRACTOR FOR USE ON THE PROJECT. TEMPLATES SHALL BE MAINTAINED IN GOOD CONDITION AND TURNED OVER TO THE OWNER AT PROJECT COMPLETION.
- IF THE CONTRACTOR ELECTS TO "BLOCK PAINT" THE BLACK PAINT AND THEN PAINT EITHER YELLOW OR WHITE PAINT OVER THE BLACK PAINT; ONLY THE VISIBLE 6" BLACK OUTLINE WILL BE ELIGIBLE FOR PAYMENT.




KEYMAP



LEGEND:

- EXISTING PAVEMENT
- PROPOSED RUNWAY REHAB



Engineering | Planning | Allied Services

Hanson Professional Services Inc.
1525 S. 6th Street
Springfield, IL 62703
phone: 217-788-2450
fax: 217-788-2503

Offices Nationwide
www.hanson-inc.com

Illinois Licensed
Professional Service Corporation
#184-001084



ST. LOUIS REGIONAL AIRPORT

8 Terminal Drive
East Alton, Illinois 62024



Jaycen R. Herndon

DATE: 11/18/2021 LICENSE: 062.069664
SIGNED: 11/18/2021 EXPIRES: 2/28/2022

**REHABILITATE
RUNWAY 17-35
PAVEMENT & LIGHTING**

SBG No:
3-17-SBGP-171/175
IDA No: ALN-4812

Contract No. SR095

NO.	DATE	DESCRIPTION		
		DES	DWN	REV

ISSUE: NOVEMBER 19, 2021
PROJECT NO: 17A008504
CAD FILE: C-151-MRK.DWG
DESIGN BY: CEM 3/18/2021
DRAWN BY: CEM 3/18/2021
REVIEWED BY: JRH 3/22/2021

SHEET TITLE

**PROPOSED MARKING
PLAN - STA. 205+50
TO STA. 215+50**

FOR BID

NOV 18, 2021 11:30 AM HERND01562
I:\17\JOBS\17A008504\CAD\AIRPORT\TSHEETC-151-MRK



Jaycen R. Herndon

DATE SIGNED: 11/18/2021 LICENSE EXPIRES: 2/28/2022

**REHABILITATE
RUNWAY 17-35
PAVEMENT & LIGHTING**

SBG No:
3-17-SBGP-171/175
IDA No: ALN-4812

Contract No. SR095

NO.	DATE	DESCRIPTION		
		DES	DWN	REV

ISSUE: NOVEMBER 19, 2021

PROJECT NO: 17A008504

CAD FILE: C-501-MRK.DWG








DESIGN BY: HLE 4/12/2021

DRAWN BY: HLE 4/12/2021

REVIEWED BY: JRH 4/12/2021

SHEET TITLE

MARKING DETAILS



RUNWAY DESIGNATION MARKING NOTES

- ALL NUMERAL MARKING WILL BE WHITE IN COLOR WITH A 6" BLACK OUTLINE.
- NUMERALS ARE HORIZONTALLY SPACED 15 FEET APART.
- DOUBLE DIGIT NUMERAL DESIGNATIONS ARE CENTERED ON THE RUNWAY PAVEMENT CENTERLINE BASED ON THE CENTER OF THE OUTER EDGES OF THE TWO NUMERALS.



Kevin N. Lightfoot

DATE SIGNED: 11/18/2021 LICENSE EXPIRES: 2/28/2022

**REHABILITATE
RUNWAY 17-35
PAVEMENT & LIGHTING**

SBG No:
3-17-SBGP-171/175
IDA No: ALN-4812


Contract No. SR095

NO.	DATE	DESCRIPTION		
		DES	DWN	REV

ISSUE: NOVEMBER 19, 2021
PROJECT NO: 17A008504
CAD FILE: C-141-ELE.DWG
DESIGN BY: JRH 3/18/2021
DRAWN BY: CWS 3/18/2021
REVIEWED BY: KNL 3/18/2021

SHEET TITLE

EXISTING
ELECTRICAL PLAN -
STA. 99+00 TO STA.
115+00





KEYMAP



0' 20' 40' 80'
HALF SIZE SCALE: 1"= 80'
FULL SIZE SCALE: 1"= 40'

LEGEND

- EXISTING PAVEMENT
- EXISTING BUILDING
- EXISTING MARKING
- EXISTING ELECTRICAL DUCT
- EXISTING ELECTRICAL CABLES
- EXISTING ELECTRICAL CABLES
- EXISTING ELECTRICAL CABLES
- EXISTING STORM SEWER/UNDERDRAIN
- EXISTING ELECTRIC UTILITY UG PRIMARY
- EXISTING TELEPHONE
- EXISTING GAS
- EXISTING FENCE
- EXISTING STAKE MOUNTED TAXIWAY LIGHT
- EXISTING BASE MOUNTED TAXIWAY LIGHT
- EXISTING TAXI/RUNWAY SIGN
- EXISTING STAKE MOUNTED RUNWAY LIGHT TO BE REMOVED
- EXISTING BASE MOUNTED RUNWAY LIGHT TO BE REMOVED
- EXISTING STAKE MOUNTED RUNWAY THRESHOLD LIGHT TO BE REMOVED
- EXISTING AIRFIELD SIGN TO BE REMOVED
- EXISTING ELECTRICAL HANDHOLE
- EXISTING SPLICE CAN
- EXISTING ELECTRICAL MANHOLE
- EXISTING BASE MOUNTED RUNWAY THRESHOLD LIGHT TO BE REMOVED
- EXISTING REIL
- EXISTING WIND CONE





Kevin N. Lightfoot

DATE SIGNED: 11/18/2021 LICENSE EXPIRES: 2/28/2022

**REHABILITATE
RUNWAY 17-35
PAVEMENT & LIGHTING**

SBG No:
3-17-SBGP-171/175
IDA No: ALN-4812

Contract No. SR095

NO.	DATE	DESCRIPTION		
		DES	DWN	REV

ISSUE: NOVEMBER 19, 2021

PROJECT NO: 17A008504

CAD FILE: C-142-ELE.DWG




DESIGN BY: JRH 03/18/2021

DRAWN BY: CWS 03/18/2021

REVIEWED BY: KNL 03/18/2021

SHEET TITLE

**PROPOSED
ELECTRICAL PLAN -
STA. 115+00 TO STA.
133+00**



LEGEND

- EXISTING PAVEMENT
- EXISTING BUILDING
- EXISTING MARKING
- EXISTING ELECTRICAL DUCT
- PROPOSED ELECTRICAL DUCT
- EXISTING ELECTRICAL CIRCUIT
- EXISTING ELECTRICAL CIRCUIT
- EXISTING ELECTRICAL CIRCUIT
- EXISTING ELECTRICAL CABLES
- EXISTING STORM SEWER/UNDERDRAIN
- EXISTING ELECTRIC UTILITY UG PRIMARY
- EXISTING TELEPHONE
- EXISTING GAS
- EXISTING FENCE
- PROPOSED 1/C #8 AWG, FAA L-824, 5000 VOLT TYPE C UNDERGROUND CABLE IN 2" SCHED 40 (MIN.) PVC OR HDPE DUCT
- PROPOSED 2-1/C #8 AWG, FAA L-824, 5000 VOLT TYPE C UNDERGROUND CABLE IN 2" SCHED 40 (MIN.) PVC OR HDPE DUCT
- EXISTING STAKE MOUNTED TAXIWAY LIGHT
- EXISTING BASE MOUNTED TAXIWAY LIGHT
- PROPOSED BASE MOUNTED RUNWAY LIGHT
- PROPOSED BASE MOUNTED RUNWAY THRESHOLD LIGHT
- EXISTING RUNWAY/TAXI GUIDANCE SIGN
- PROPOSED RUNWAY DISTANCE REMAINING SIGN
- EXISTING ELECTRICAL HANDHOLE
- EXISTING ELECTRICAL MANHOLE
- EXISTING SPLICE CAN
- PROPOSED ELECTRICAL HANDHOLE
- PROPOSED SPLICE CAN
- EXISTING WIND CONE
- EXISTING REIL

FOR BID

NOV 18, 2021 11:31 AM HERND01562 I:\17\JOBS\17A008504\CAD\AIRPORT\T\SHEET\C-142-ELE



Kevin N. Lightfoot

DATE: 11/18/2021 LICENSE: 062-047643
SIGNED: 11/18/2021 EXPIRES: 2/28/2022

REHABILITATE
RUNWAY 17-35
PAVEMENT & LIGHTING

SBG No:
3-17-SBGP-171/175
IDA No: ALN-4812


Contract No. SR095

NO.	DATE	DESCRIPTION		
		DES	DWN	REV



ISSUE: NOVEMBER 19, 2021
PROJECT NO: 17A008504
CAD FILE: C-142-ELE.DWG
DESIGN BY: JRH 03/18/2021
DRAWN BY: CWS 03/18/2021
REVIEWED BY: KNL 03/18/2021

SHEET TITLE

PROPOSED
ELECTRICAL PLAN -
STA. 133+00 TO STA.
151+00




KEYMAP



LEGEND

- EXISTING PAVEMENT
- EXISTING BUILDING
- EXISTING MARKING
- EXISTING ELECTRICAL DUCT
- PROPOSED ELECTRICAL DUCT
- EXISTING ELECTRICAL CIRCUIT
- EXISTING ELECTRICAL CIRCUIT
- EXISTING ELECTRICAL CIRCUIT
- EXISTING ELECTRICAL CABLES
- EXISTING STORM SEWER/UNDERDRAIN
- EXISTING ELECTRIC UTILITY UG PRIMARY
- EXISTING TELEPHONE
- EXISTING GAS
- EXISTING FENCE
- PROPOSED 1/C #8 AWG, FAA L-824, 5000 VOLT TYPE C UNDERGROUND CABLE IN 2" SCHED 40 (MIN.) PVC OR HDPE DUCT
- PROPOSED 2-1/C #8 AWG, FAA L-824, 5000 VOLT TYPE C UNDERGROUND CABLE IN 2" SCHED 40 (MIN.) PVC OR HDPE DUCT
- EXISTING STAKE MOUNTED TAXIWAY LIGHT
- EXISTING BASE MOUNTED TAXIWAY LIGHT
- PROPOSED BASE MOUNTED RUNWAY LIGHT
- PROPOSED BASE MOUNTED RUNWAY THRESHOLD LIGHT
- EXISTING RUNWAY/TAXI GUIDANCE SIGN
- PROPOSED RUNWAY DISTANCE REMAINING SIGN
- EXISTING ELECTRICAL HANDHOLE
- EXISTING ELECTRICAL MANHOLE
- EXISTING SPLICE CAN
- PROPOSED ELECTRICAL HANDHOLE
- PROPOSED SPLICE CAN
- EXISTING WIND CONE
- EXISTING REIL

FOR BID



NOV 18, 2021 11:31 AM HERND01562
I:\17\JOBS\17A008504\CAD\AIRPORT\T\SHEET\C-142-ELE



Kevin N. Lightfoot

DATE SIGNED: 11/18/2021 LICENSE EXPIRES: 2/28/2022

REHABILITATE
RUNWAY 17-35
PAVEMENT & LIGHTING

SBG No:
3-17-SBGP-171/175
IDA No: ALN-4812

Contract No. SR095

NO.	DATE	DESCRIPTION		
		DES	DWN	REV

ISSUE: NOVEMBER 19, 2021

PROJECT NO: 17A008504

CAD FILE: E-510-THRS.DWG


DESIGN BY: BSS 03/18/2021

DRAWN BY: CWS 03/18/2021


REVIEWED BY: BSS 03/18/2021

SHEET TITLE


THRESHOLD
LIGHTING DETAILS



KEYMAP




THRESHOLD LIGHT PLAN RUNWAY 17 END
(NOT TO SCALE)




THRESHOLD LIGHT PLAN RUNWAY 35 END
(NOT TO SCALE)

NOTE:
CONTRACTOR SHALL TOOL CONTROL JOINTS IN NEW CONCRETE, 1/4\"/>



THRESHOLD LIGHTING MAINTENANCE PAD DETAIL
(NOT TO SCALE)



DETAIL 1
(NOT TO SCALE)



Kevin N. Lightfoot

DATE SIGNED: 11/18/2021 LICENSE EXPIRES: 2/28/2022

**REHABILITATE
RUNWAY 17-35
PAVEMENT & LIGHTING**

SBG No:
3-17-SBGP-171/175
IDA No: ALN-4812

Contract No. SR095

NO.	DATE	DESCRIPTION		
		DES	DWN	REV

ISSUE: NOVEMBER 19, 2021

PROJECT NO: 17A008504

CAD FILE: E-501-DETL.DWG



DESIGN BY: KNL 03/18/2021

DRAWN BY: CWS 03/18/2021

REVIEWED BY: KNL 03/18/2021


SHEET TITLE

**AIRFIELD LIGHT
DETAILS**



NOTE:
AFFIX NON-CORROSIVE, NON-BREAKABLE, TAG TO FIXTURE FACING RUNWAY/TAXIWAY WITH SET SCREW, WIRE TIE, OR METAL BAND. NUMERALS SHALL BE ENGRAVED FOR PERMANENT READABILITY. STAINLESS STEEL OR BRASS TAGS WITH 1/2" HIGH STAMPED LETTERING WILL ALSO BE ACCEPTABLE.

NUMBERING TAG DETAIL
(NOT TO SCALE)



LIGHTING CONNECTION SCHEMATIC

NOT TO SCALE

NOTES:

- SEE ELECTRICAL NOTES SHEETS.
- SEE "ELECTRICAL NOTES SHEET 2" AND "GROUNDING NOTES" SHEET FOR GROUNDING NOTES FOR AIRFIELD LIGHTING.
- SEE PROPOSED LIGHTING LAYOUT SHEET(S) FOR LIGHT LOCATIONS
- WHERE GROUND LUGS ARE NOT ACCESSIBLE ON BASE CANS, PROVIDE A UL LISTED PIPE GROUND CLAMP RATED FOR DIRECT BURIAL IN EARTH AND BOND TO THE METAL CONDUIT EXTENSION TO PROVIDE GROUND PATH TO LIGHT BASE.
- THE PROPOSED AIRFIELD LIGHT FIXTURES SHALL CONFORM TO ADVISORY CIRCULAR 150/5345-46 (CURRENT ISSUE(S) IN EFFECT) AND BE FAA APPROVED FOR TYPE L-861(L) FOR RUNWAY EDGE LIGHTS AND L-861SE(L) FOR THRESHOLD LIGHTS. AIRFIELD LIGHT FIXTURES SHALL HAVE LED (LIGHT EMITTING DIODE) ILLUMINATION AND SHALL CONFORM TO THE APPLICABLE REQUIREMENTS OF FAA ENGINEERING BRIEF NO. 67D LIGHT SOURCES OTHER THAN INCANDESCENT AND XENON FOR AIRPORT AND OBSTRUCTION LIGHTING FIXTURES.
- LIGHT BASE CANS FOR THE AIRFIELD LIGHT FIXTURES SHALL CONFORM TO THE REQUIREMENTS OF FAA AC 150/5345-42 (CURRENT ISSUE IN EFFECT), FOR TYPE L-867, CLASS IA, SIZE B (12 IN. NOMINAL DIAMETER), AND 24 IN. DEEP AND/OR AS DETAILED ON THE PLANS. EACH LIGHT BASE CAN SHALL INCLUDE INTERNAL AND EXTERNAL GROUND LUGS TO ACCOMMODATE THE RESPECTIVE APPLICATIONS. LIGHT BASE PLATES SHALL BE SIZED AND COMPATIBLE WITH THE RESPECTIVE LIGHT BASES AND LIGHT FIXTURES WITH STAINLESS STEEL BOLTS.
- PRIOR TO INSTALLING THE AIRFIELD LIGHT FIXTURES, APPLY AN OXIDE-INHIBITING, ANTI-SEIZING COMPOUND TO ALL SCREWS, NUTS, BREAKABLE COUPLING, AND ALL PLACES WHERE METAL COMES INTO CONTACT WITH METAL.
- SERIES CIRCUIT ISOLATION TRANSFORMERS FOR THE AIRFIELD LIGHTING SHALL BE MANUFACTURED TO FAA SPECIFICATION AC 150/5345-47, (CURRENT EDITION IN EFFECT), AND SHALL BE FAA-APPROVED (ETL/INTERTEK TESTING SERVICES-CERTIFIED). SERIES CIRCUIT TRANSFORMER SHALL BE PROPERLY SIZED FOR THE RESPECTIVE AIRFIELD LIGHTING DEVICE, AND SHALL BE AS RECOMMENDED BY THE RESPECTIVE EQUIPMENT MANUFACTURER. CONFIRM PROPER TRANSFORMER SELECTION AND SIZING WITH THE RESPECTIVE EQUIPMENT MANUFACTURER.
- THE CONCRETE USED IN THE CONSTRUCTION OF THE BASES FOR THE AIRFIELD LIGHTING AND SPLICE CANS SHALL BE IN ACCORDANCE WITH ITEM 610 CONCRETE FOR MISCELLANEOUS STRUCTURES.
- IDENTIFICATION TAGS SHALL BE ATTACHED TO EACH AIRFIELD LIGHT FIXTURE.
- PER ILLINOIS STANDARD SPECIFICATIONS FOR CONSTRUCTION OF AIRPORTS ITEM 108, ITEM 125, AND FAA AC 150/5370-10H ITEM L-108 AND L-125, RUBBER AND PLASTIC ELECTRICAL TAPES SHALL BE SCOTCH ELECTRICAL TAPE NUMBERS 130C LINERLESS RUBBER SPLICING TAPE (2" WIDE) AND 88 (1.5" WIDE) RESPECTIVELY, AS MANUFACTURED THE MINNESOTA MINING AND MANUFACTURING COMPANY, OR EQUIVALENT.

A LIGHT BASE GROUND SHALL BE INSTALLED AT EACH STAKE MOUNTED LIGHT AND EACH TRANSFORMER BASE/LIGHT CAN ASSOCIATED WITH RUNWAY LIGHTS, TAXIWAY LIGHTS, RUNWAY DISTANCE REMAINING SIGNS, AND LIGHTED RUNWAY/TAXI GUIDANCE SIGNS. THE LIGHT BASE GROUND SHALL BE A #6 AWG BARE COPPER CONDUCTOR CONNECTED TO THE GROUND LUG ON THE RESPECTIVE L-867 TRANSFORMER BASE/LIGHT CAN OR MOUNTING STAKE AND A 3/4-INCH DIAMETER BY 10-FOOT LONG (MINIMUM) UL LISTED COPPER CLAD GROUND ROD.

FOR BID



Kevin N. Lightfoot

DATE SIGNED: 11/18/2021 LICENSE EXPIRES: 2/28/2022

**REHABILITATE
RUNWAY 17-35
PAVEMENT & LIGHTING**

SBG No:
3-17-SBGP-171/175
IDA No: ALN-4812

Contract No. SR095

NO.	DATE	DESCRIPTION		
		DES	DWN	REV

ISSUE: NOVEMBER 19, 2021

PROJECT NO: 17A008504

CAD FILE: E-509-DETL.DWG


DESIGN BY: KNL 03/18/2021

DRAWN BY: CWS 03/18/2021

REVIEWED BY: KNL 03/18/2021

SHEET TITLE


**IN-PAVEMENT
RUNWAY LIGHT AND
SPlice CAN DETAILS**



IN-PAVEMENT RUNWAY LIGHT
"NOT TO SCALE"

NOTES:

- MEDIUM INTENSITY IN-PAVEMENT RUNWAY LIGHT SHALL BE AN L-852D(L) LED IN-PAVEMENT TAXIWAY CENTERLINE LIGHT WITH WHITE/WHITE COLOR OR WHITE/YELLOW COLOR CORRESPONDING TO THE LIGHT FIXTURE SCHEDULE. FAA AC 150/5340-30J, CHAPTER 2 RUNWAY AND TAXIWAY EDGE LIGHTING SYSTEMS, PART 2.3.1.2.2 INTERSECTIONS, PARAGRAPH 2 MIRL NOTES THE FOLLOWING: IF THE DISTANCE BETWEEN THE RUNWAY EDGE LIGHTS UNITS IS GREATER THAN 400 FT, INSTALL AN L-852D, TAXIWAY CENTERLINE LIGHT FIXTURE (PER AC 150/5345-46, SPECIFICATION FOR RUNWAY AND TAXIWAY LIGHT FIXTURES), MODIFIED TO PRODUCE WHITE LIGHT (BY REMOVING THE FILTERS IF AN INCANDESCENT LAMP IS USED) OR WHITE/YELLOW, AND MAINTAIN THE DESIGNED SPACING PER PER FIGURE A-3.
- SAW CUT AND REMOVE PAVEMENT FROM EDGE CLOSEST TO RESPECTIVE IN-PAVEMENT LIGHT FIXTURE TO ACCOMMODATE INSTALLATION. RESTORE PAVEMENT AND AREA AROUND IN-PAVEMENT LIGHT FIXTURE WITH ITEM 610 CONCRETE FOR MISCELLANEOUS STRUCTURES. SURROUNDING CONCRETE PAVEMENT DEPTH AND AGGREGATE BASE DEPTH SHALL MATCH EXISTING.
- IN-PAVEMENT RUNWAY LIGHT WILL BE PAID FOR UNDER ITEM AR125512 MIRL, INPAVEMENT PER EACH.



SPlice CAN/JUNCTION CAN DETAIL
"NOT TO SCALE"

NOTES FOR SPlice CAN/JUNCTION CAN DETAIL:

- SPlice CANS SHALL CONFORM TO THE REQUIREMENTS OF FAA AC 150/5345-42 (CURRENT ISSUES IN EFFECT), FOR TYPE L-867, CLASS IA, SIZE D, (16 IN. NOMINAL DIAMETER), AND 24 IN. DEEP AND/OR AS DETAILED ON THE PLANS. EACH SPlice CAN SHALL INCLUDE INTERNAL AND EXTERNAL GROUND LUGS TO ACCOMMODATE THE RESPECTIVE APPLICATIONS. SPlice CANS AND/OR JUNCTION CANS SHALL HAVE GALVANIZED STEEL COVERS, 3/8-INCH THICK (MINIMUM), WITH STAINLESS STEEL BOLTS.
- FOR THE PURPOSE OF ENHANCING SAFETY, EACH BASE MUST HAVE INSTALLED, BY THE MANUFACTURER, AN INTERNAL AND EXTERNAL GROUND STRAP THAT IS AVAILABLE FOR THE PURPOSE OF ATTACHING A GROUND LUG THAT IS CONNECTED TO AN EARTH GROUND OR A SAFETY GROUND CONDUCTOR INSTALLED WITH THE RESPECTIVE CIRCUIT. FOR AIRPORT PROJECTS RECEIVING FEDERAL FUNDS THIS REQUIREMENT IS MANDATORY PER FAA AC 150/5345-42 (CURRENT ISSUES IN EFFECT).
- APPLY AN OXIDE-INHIBITING, ANTI-SEIZING COMPOUND TO ALL SCREWS, NUTS, AND ALL PLACES WHERE METAL COMES INTO CONTACT WITH METAL.
- THE CONCRETE USED IN THE CONSTRUCTION OF THE BASES FOR THE AIRFIELD LIGHTING CANS SHALL BE IN ACCORDANCE WITH ITEM 610 STRUCTURAL PORTLAND CEMENT CONCRETE.
- LIDS FOR THE SPlice CANS CONTAINING HIGH VOLTAGE AIRFIELD LIGHTING CABLES SHALL INCLUDE MINIMUM 1/2-INCH HIGH LETTERING LABELED "DANGER HIGH VOLTAGE KEEP OUT" TO COMPLY WITH NEC ARTICLE 300.45 "WARNING SIGNS" AND NEC ARTICLE 314.71(E) "SUITABLE COVERS". THIS WILL NEED TO BE COORDINATED WITH THE SPlice CAN MANUFACTURER.
- LIDS FOR THE SPlice CANS CONTAINING LOW VOLTAGE CABLES (RATED 600 VOLTS AND BELOW) WILL BE ACCEPTABLE TO USE BLANK COVERS.

FOR BID



Kevin N. Lightfoot

DATE SIGNED: 11/18/2021 LICENSE EXPIRES: 2/28/2022

**REHABILITATE
RUNWAY 17-35
PAVEMENT & LIGHTING**

SBG No:
3-17-SBGP-171/175
IDA No: ALN-4812

Contract No. SR095

NO.	DATE	DESCRIPTION		
		DES	DWN	REV

ISSUE: NOVEMBER 19, 2021
PROJECT NO: 17A008504
CAD FILE: E-502-DET.DWG
DESIGN BY: KNL 03/18/2021
DRAWN BY: CWS 03/18/2021
REVIEWED BY: KNL 03/18/2021

SHEET TITLE

**RUNWAY DISTANCE
REMAINING SIGN
DETAILS**



FOR BID

RUNWAY DISTANCE REMAINING SIGN SCHEDULE

SIGN DESIGNATION	SIDE A	SIDE B
R2-DRS1	1	5
R2-DRS2	2	4
R2-DRS3	3	3
R2-DRS4	4	2
R2-DRS5	5	1



DISTANCE REMAINING SIGN NOTES

1. THE PROPOSED RUNWAY DISTANCE REMAINING SIGNS SHALL CONFORM TO ADVISORY CIRCULAR 150/5345-44H (OR LATEST ISSUE IN FORCE) AND BE FAA APPROVED FOR TYPE L-858-B(L) LIGHT EMITTING DIODE RUNWAY DISTANCE REMAINING SIGN. THE SIGN SHALL BE SIZE 4, 48-IN. SIGN FACE WITH A 40-IN. LEGEND; STYLE 2, POWERED FROM A 4.8 TO 6.6 AMP SERIES LIGHTING CIRCUIT; CLASS 2, FOR OPERATION FROM -40°F TO 131°F; MODE 2, TO WITHSTAND WIND LOADS OF 200 M.P.H., BASE-MOUNTED, DOUBLE-SIDED, AS SPECIFIED ON THE PLANS.
2. ALL SIGNS SHALL BE FURNISHED WITH TETHERS. TETHERS SHALL BE 3/16" STAINLESS STEEL AIRCRAFT CABLE WITH A FORMED EYE ON BOTH ENDS. THE TETHER EYE SHALL BE ATTACHED TO THE SIGN AND BASE BY BEING SANDWICHED BETWEEN TWO STAINLESS STEEL FENDER WASHERS, WITH A 1/2" MINIMUM STAINLESS STEEL BOLT. THE TETHER SHALL BE OF SUFFICIENT LENGTH TO HAVE A MINIMUM OF 6" OF SLACK WHEN ATTACHED BETWEEN THE SIGN AND THE SIGN BASE. THE TETHERS AND BONDING CONDUCTORS SHALL BE OF SUFFICIENT LENGTH TO ALLOW THE FRANGIBLE COUPLINGS TO OPERATE WITHOUT RESTRICTIONS AND TO ALLOW THE POWER CABLE TO DISCONNECT IF THE SIGN FALLS OVER. PROVIDE 3" ± 1/2" SLACK IN TETHER AND ALL TETHERS SHALL BE THE SAME LENGTH.
3. DISTANCE REMAINING SIGNS SHALL BE CONNECTED TO THE RESPECTIVE RUNWAY LIGHTING SERIES CIRCUIT SO THE SIGNS WILL BE ILLUMINATED WHEN THE RUNWAY EDGE LIGHTS ARE ILLUMINATED TO COMPLY WITH FAA AC 150/5340-18G, CHAPTER 2, PART 2.4 "SIGN OPERATION".



A LIGHT BASE GROUND MUST BE INSTALLED AT EACH LIGHT FIXTURE. A LIGHT BASE GROUND SHALL BE INSTALLED AT EACH STAKE MOUNTED LIGHT AND EACH TRANSFORMER BASE/LIGHT CAN ASSOCIATED WITH RUNWAY LIGHTS, TAXIWAY LIGHTS, AND LIGHTED AIRFIELD GUIDANCE SIGNS. THE LIGHT BASE GROUND SHALL BE A #6 AWG BARE COPPER CONDUCTOR CONNECTED TO THE GROUND LUG ON THE RESPECTIVE L-867 TRANSFORMER BASE/LIGHT CAN, SIGN FRAME, OR MOUNTING STAKE AND A 3/4-INCH DIAMETER BY 10-FOOT LONG (MINIMUM) UL LISTED COPPER CLAD GROUND ROD.

- NOTES:**
1. DETAILS SHOWN ON THIS SHEET APPLY TO NEW DISTANCE REMAINING SIGNS AND/OR RELOCATED DISTANCE REMAINING SIGNS.
 2. RUNWAY 17-35 SERIES CIRCUIT CABLES SHALL BE #8 AWG.
 3. INCLUDE TETHERS FOR EACH SIGN.





Kevin N. Lightfoot

DATE SIGNED: 11/18/2021 LICENSE EXPIRES: 2/28/2022

**REHABILITATE
RUNWAY 17-35
PAVEMENT & LIGHTING**

SBG No:
3-17-SBGP-171/175
IDA No: ALN-4812

Contract No. SR095

NO.	DATE	DESCRIPTION		
		DES	DWN	REV

ISSUE: NOVEMBER 19, 2021

PROJECT NO: 17A008504

CAD FILE: E-504-DETL.DWG

DESIGN BY: KNL 03/18/2021

DRAWN BY: CWS 03/18/2021


REVIEWED BY: KNL 03/18/2021

SHEET TITLE


**AIRFIELD LIGHTING
CABLE SPLICE
DETAILS**

NOTES:


1. SPLICE DETAILS ARE PROVIDED FOR NEW WORK AND TO ASSIST IN REPAIRS OF ACCIDENTAL OR UNEXPECTED INTERRUPTIONS AND/OR CUTS TO AIRFIELD LIGHTING CABLES.
2. KEEP ON HAND A MINIMUM OF 10 SETS OF SPLICE KITS FOR L-823 CONNECTORS AND A MINIMUM OF 10 SETS OF TYPE A LOW VOLTAGE SPLICE KITS TO ACCOMMODATE REPAIRS.
3. EVERY AIRFIELD LIGHTING CABLE SPICER SHALL BE QUALIFIED IN MAKING CABLE SPLICES AND TERMINATIONS ON CABLES RATED AT AND/OR ABOVE 5,000 VOLTS AC TO COMPLY WITH THE REQUIREMENTS OF FAA AC 150/5370-10G ITEM L-108.
4. INSIDE DIAMETER OF RESPECTIVE CABLE CONNECTOR SHALL PROPERLY MATCH OUTSIDE DIAMETER OF CABLE.
5. WHEN PREPARING CABLE FOR SPLICES, THE CONTRACTOR SHALL USE A CABLE STRIPPER/PENCILLER WHENEVER CABLE CONNECTIONS ARE MADE.
6. WRAP ALL PRIMARY AND SECONDARY POWER CONNECTIONS WITH SUFFICIENT LAYERS OF HIGH VOLTAGE ELECTRICAL INSULATING TAPE (RUBBER SPLICING TAPE SUITABLE FOR PRIMARY ELECTRICAL INSULATION FOR SPLICING CABLE FROM 600 VOLTS TO 69,000 VOLTS) AND COVER WITH VINYL ELECTRICAL TAPE (ALL-WEATHER VINYL INSULATING TAPE SUITABLE FOR PROTECTIVE JACKETING FOR HIGH-VOLTAGE CABLE SPLICES AND REPAIRS) FOR FULL VALUE OF CABLE INSULATION VOLTAGE. PER ILLINOIS STANDARD SPECIFICATIONS FOR CONSTRUCTION OF AIRPORTS ITEM 108, ITEM 125, AND FAA AC 150/5370-10H ITEM L-108 AND L-125, HIGH VOLTAGE ELECTRICAL INSULATING TAPE SHALL BE 3M SCOTCH 130C LINERLESS RUBBER SPLICING TAPE (2 INCHES WIDE) OR APPROVED EQUIVALENT, AND VINYL ELECTRICAL TAPE SHALL BE 3M SCOTCH 88 (1.5 INCHES WIDE) OR APPROVED EQUIVALENT. TAPES MUST BE RATED SUITABLE FOR THE APPLICATION.
7. PROVIDE CABLE TAGS TO IDENTIFY THE RESPECTIVE CIRCUITS ALL POINTS OF ACCESS INCLUDING L-867 BASES, L-868 BASES, HANDHOLES, MANHOLES, JUNCTION BOXES, AND WIREWAYS.
8. CONNECTION OF CONDUCTORS MUST BE MADE BY USING CRIMP CONNECTORS AND A CRIMPING TOOL APPROVED BY THE CONNECTOR/LUG MANUFACTURER. THE TOOL MUST PRODUCE A COMPLETE CRIMP BEFORE IT CAN BE REMOVED. FOR THE L-823 CONNECTORS, THE CRIMPING TOOL USED MUST BE LISTED BY THE L-823 KIT MANUFACTURER. MAKE THE NUMBER AND TYPE OF CRIMPS PER THE KIT MANUFACTURER'S INSTRUCTIONS.




TYPE A
FOR SPLICES IN LOW VOLTAGE CABLE (600V) HOMERUNS FOR EXTENSIONS TO EXISTING LOW VOLTAGE CABLES ONLY. TYPE A SPLICES SHALL BE MADE IN SPLICE CANS, HANDHOLES, MANHOLES, OR JUNCTION BOXES



LOW VOLTAGE UNDERGROUND TAP SPLICE
FOR TAP SPLICES IN LOW VOLTAGE (600V) CABLE. SPLICES SHALL BE RATED AND LISTED SUITABLE FOR DIRECT BURIAL LOCATIONS. FOR SPLICES UP TO #2 AWG CONDUCTOR, SPLICES SHALL BE WYE RESIN TYPE POWER CABLE TAP SPLICE KIT SUITABLE FOR THE RESPECTIVE CABLES AND RESPECTIVE APPLICATION.




TYPE B
FOR SPLICES AT JUNCTION OF HOMERUN WITH LOOP CIRCUIT AND FOR SPLICES IN HOMERUNS TO EXISTING CABLES



TYPE C
FOR SPLICES AT RUNWAY AND TAXIWAY LIGHTS AND TAXI SIGNS

NOTES:
INSIDE DIAMETER OF CONNECTOR SHALL PROPERLY MATCH THE OUTSIDE DIAMETER OF CABLE.



1. CONTRACTOR SHALL PROVIDE CABLE CIRCUIT IDENTIFICATION MARKERS ATTACHED TO BOTH SIDES OF EACH CABLE CONNECTION.
2. CABLE IDENTIFICATION TAGS SHALL BE STAINLESS STEEL OR BRASS.
3. THE CABLE SHALL THOROUGHLY BE CLEANED PRIOR TO THE INSTALLATION OF THE L-823 CONNECTOR KIT.
4. ATTACH EACH CABLE TIE ENOUGH TO HOLD IN PLACE WITHOUT COMPRESSING EDGE OF CABLE TAG INTO CONDUCTOR. TRIM OFF EXCESS CABLE TIE.
5. CABLE TAGS SHALL BE PROVIDED AT ALL POINTS OF ACCESS INCLUDING L-867 BASES, L-868 BASES, HANDHOLES, MANHOLES, JUNCTION BOXES, AND WIREWAYS.
6. CABLE TAGS SHALL BE LABELED AS FOLLOWS FOR RESPECTIVE AIRFIELD LIGHTING CIRCUITS, RUNWAY 11-29 LGHTING: R1
RUNWAY 17-35 LIGHTING: R2

CABLE SPLICES
"NOT TO SCALE"

CABLE TAG DETAIL
"NOT TO SCALE"

FOR BID

NOV 18, 2021 11:33 AM HERND01562 I:\17\JOBS\17A008504\CAD\AIRPORT\TSHEETE-504-DETL



Kevin N. Lightfoot

DATE SIGNED: 11/18/2021 LICENSE EXPIRES: 2/28/2022

REHABILITATE
RUNWAY 17-35
PAVEMENT & LIGHTING

SBG No:
3-17-SBGP-171/175
IDA No: ALN-4812

Contract No. SR095

NO.	DATE	DESCRIPTION		
		DES	DWN	REV

ISSUE: NOVEMBER 19, 2021

PROJECT NO: 17A008504

CAD FILE: E-506-DETL.DWG

DESIGN BY: KNL 03/18/2021


DRAWN BY: CWS 03/18/2021

REVIEWED BY: KNL 03/18/2021


SHEET TITLE

CABLE AND DUCT
MARKER DETAILS


FOR BID




TURF CABLE MARKERS
"NOT TO SCALE"



TURF CABLE MARKERS
"NOT TO SCALE"




TURF CABLE MARKERS
"NOT TO SCALE"




BITUMINOUS PAVEMENT DUCT MARKERS
"NOT TO SCALE"

NOTE:

1. TOP OF MARKER SHALL BE FLUSH WITH FINISHED PAVEMENT SURFACE. MARKER MAY BE INSTALLED IN A DRILLED HOLE AND SECURED WITH EPOXY GLUE
2. BRASS DUCT MARKERS ARE AVAILABLE FROM BERNTSEN INTERNATIONAL INC., P.O. BOX 8670, MADISON, WI. 53708-8670, PHONE: 1-877-959-8556, SURV-KAP, 3225 E. 47TH ST., TUCSON, AZ 85713, PHONE: (502)-622-6011, OR OTHER EQUIVALENT MANUFACTURERS.



DUCT MARKER DETAIL-PLAN
"NOT TO SCALE"



UNDERGROUND ELECTRICAL DUCT

(NOT TO SCALE)

CABLE & DUCT MARKER NOTES:

1. THE COST OF ALL TURF AND PAVEMENT DUCT MARKERS SHALL BE INCIDENTAL TO THE DUCT. THE COST OF ALL CABLE MARKERS SHALL BE INCIDENTAL TO THE CABLE.
2. BITUMINOUS PAVEMENT DUCT MARKER AND CONCRETE DUCT MARKER TO BE PROVIDED AT EACH END OF EACH DUCT AS SHOWN ON THE LOCATION PLAN. FOR CONCRETE PAVEMENT, THE LETTER "D" SHALL BE IMPRESSED IN THE PAVEMENT INSTEAD OF THE MARKER. THE LETTER SHALL BE INFORMED AS DESCRIBED IN NOTE 4.
3. UNDERGROUND CABLE RUNS MUST BE IDENTIFIED BY CABLE MARKERS AT 200 FEET (61 M) MAXIMUM SPACING WITH AN ADDITIONAL MARKER AT EACH CHANGE OF DIRECTION OF THE CABLE RUN. CABLE MARKERS MUST BE INSTALLED ABOVE THE CABLE. CABLE MARKERS ARE NOT REQUIRED FOR CABLE RUNS BETWEEN RUNWAY/TAXIWAY EDGE LIGHTS.
4. CONCRETE CABLE MARKERS AND DUCT MARKERS SHALL HAVE LETTERS 4" HIGH, 3" WIDE WITH WIDTH OF STROKE 1/2" AND 1/4" DEEP. ALL LETTERS, NUMBERS AND ARROWS TO BE IMPRESSED.
5. EMPLOY THE FOLLOWING METHODS WHERE ADDITIONAL SPACE TO FIT THE LEGEND IS REQUIRED:
A. REDUCE LETTER SIZE TO 3" HIGH, 2" WIDE.
B. INCREASE THE MARKER SIZE TO 30" X 30".
C. PROVIDE ADDITIONAL MARKERS PLACED SIDE BY SIDE
6. TURF DUCT MARKERS ARE NOT REQUIRED AT PAVEMENT CROSSINGS WHERE DUCTS TERMINATE IN HANDHOLES, OR JUNCTION STRUCTURES.
7. LOCATION OF ALL DIRECT EARTH BURIAL UNDERGROUND CABLE SPLICE/CONNECTIONS, EXCEPT THOSE AT ISOLATION TRANSFORMERS, MUST BE IDENTIFIED BY SPLICE MARKERS. SPLICE MARKERS MUST BE PLACED ABOVE THE SPLICE/CONNECTIONS. DIRECT EARTH BURIAL UNDERGROUND CABLE SPLICES SHALL BE AVOIDED WHERE POSSIBLE. CABLE SPLICES SHALL BE LOCATED IN SPLICE CANS, LIGHT BASES, HANDHOLES, MANHOLES, OR OTHER JUNCTION STRUCTURES UNLESS OTHERWISE APPROVED BY THE PROJECT ENGINEER.
8. THE CABLE AND SPLICE MARKERS MUST IDENTIFY THE CIRCUITS TO WHICH THE CABLES BELONG. FOR EXAMPLE: RWY 4-22, PAPI-4, PAPI-22.
9. LOCATIONS OF ENDS OF ALL UNDERGROUND DUCTS MUST BE IDENTIFIED BY DUCT MARKERS.



Kevin N. Lightfoot

DATE SIGNED: 11/18/2021 LICENSE EXPIRES: 2/28/2022

REHABILITATE
RUNWAY 17-35
PAVEMENT & LIGHTING

SBG No:
3-17-SBGP-171/175
IDA No: ALN-4812

Contract No. SR095

NO.	DATE	DESCRIPTION		
		DES	DWN	REV

ISSUE: NOVEMBER 19, 2021

PROJECT NO: 17A008504

CAD FILE: E-507-DETL.DWG


DESIGN BY: KNL 03/18/2021

DRAWN BY: CWS 03/18/2021

REVIEWED BY: KNL 03/18/2021

SHEET TITLE


GROUNDING DETAILS



DETAIL NOTES

- ALL BELOW GRADE CONNECTIONS TO GROUND RODS & GROUND RING CONDUCTORS SHALL BE EXOTHERMIC WELD TYPE CONNECTIONS. EXOTHERMIC WELDS SHALL BE CADWELD AS MANUFACTURED BY PENTAIR ERICO PRODUCTS, ULTRAWELD AS MANUFACTURED BY HARGER LIGHTNING PROTECTION & GROUNDING EQUIPMENT, OR THERMOWELD AS MANUFACTURED BY CONTINENTAL INDUSTRIES OR APPROVED EQUAL. VERIFY PROPER SIZES, MOLDS, TYPES, AND REQUIREMENTS FOR THE RESPECTIVE APPLICATION WITH THE MANUFACTURER, AND INSTALL PER THEIR DIRECTIONS.
- FOR APPLICATIONS TO GALVANIZED STEEL OR PAINTED STEEL, REMOVE GALVANIZING AND/OR PAINT & CLEAN THE SURFACE TO EXPOSE BARE STEEL BEFORE MAKING EXOTHERMIC WELD CONNECTION.
- INDIVIDUAL GROUNDING ELECTRODE CONDUCTORS SHALL NOT BE INSTALLED IN METAL CONDUIT. INSTALL GROUNDING ELECTRODE CONDUCTORS IN SCHED 40 PVC CONDUIT AS REQUIRED IN FOUNDATIONS, FOR PROTECTION, WHERE ENTERING ENCLOSURES, ETC. WHERE PLASTIC CONDUIT IS USED FOR INDIVIDUAL GROUND WIRES, DO NOT COMPLETELY ENCIRCLE THE CONDUIT WITH FERROUS AND/OR MAGNETIC MATERIALS. WHERE METAL CLAMPS ARE INSTALLED USE NYLON BOLTS, NUTS, WASHERS, & SPACERS TO INTERRUPT A COMPLETE METALLIC PATH FROM ENCIRCLING THE CONDUIT.

EXOTHERMIC WELD DETAILS




2 HOLE LONG BARREL COMPRESSION LUG TABLE (OR APPROVED EQUAL)

WIRE SIZE	BURNDY CAT. NO.	THOMAS & BETTS CAT. NO.	PENN-UNION CAT. NO.
#8 AWG STRANDED	YA8C-2TC38	256-30695-1157	BBLU-8D-2TC38
#6 AWG SOLID	YA8C-2TC38 OR YGA6C-2TC38E2G1		
#6 AWG STRANDED	YA6C-2TC38	256-30695-1158	BBLU-6D-2TC38
#4 AWG STRANDED	YA4C-2TC38	256-30695-1159	BBLU-4D-2TC38
#2 AWG STRANDED	YA2C-2TC38	256-30695-1160	BBLU-2D-2TC38
#2 AWG SOLID	YA3C-2TC38	256-30695-1160	BBLU-3D-2TC38
#1/0 AWG STRANDED	YA25-2TC38	256-30695-1162	BBLU-1/0D-2TC38
#2/0 AWG STRANDED	YA26-2TC38	256-30695-1116	BBLU-2/0D-2TC38
#3/0 AWG STRANDED	YA27-2TC38	54816BE	BBLU-3/0D-2TC38
#4/0 AWG STRANDED	YA28-2TC38	256-30695-1117	BBLU-4/0D-2TC38

NOTES

- ALL CONNECTIONS TO GROUND BUS BAR SHALL BE WITH 2 HOLE TONGUE LONG BARREL COMPRESSION LUGS BOLTED TO THE BUS BAR.
- GROUND WIRE CONNECTIONS TO EQUIPMENT SHALL BE WITH 2 HOLE TONGUE LONG BARREL COMPRESSION LUGS BOLTED TO THE DEVICE OR WITH THE RESPECTIVE EQUIPT MANUFACTURER'S LUG OR TERMINAL WHERE APPLICABLE.
- GROUNDING ELECTRODE CONDUCTORS, BONDING JUMPERS, & INDIVIDUAL GROUND WIRES SHALL NOT BE INSTALLED IN METAL CONDUIT. WHERE PLASTIC CONDUIT IS USED FOR INDIVIDUAL GROUND WIRES, DO NOT COMPLETELY ENCIRCLE THE CONDUIT WITH FERROUS AND/OR MAGNETIC MATERIALS. WHERE METAL CLAMPS ARE INSTALLED USE NYLON BOLTS, NUTS, WASHERS, & SPACERS TO INTERRUPT A COMPLETE METALLIC APTH FROM ENCIRCLING THE CONDUIT.
- ALL CONNECTIONS SHALL BE COATED WITH A CORROSION PREVENTATIVE COMPOUND (SANCHEM INC. NO-OX-ID "A-SPECIAL", BURNDY PENETROX E, OR APPROVED EQUAL) BEFORE JOINING. ALL COPPER BUS BARS SHALL BE CLEANED PRIOR TO MAKING CONNECTIONS TO REMOVE SURFACE OXIDATION. CLEAN SURFACES, OF RESPECTIVE DEVICES TO BE BONDED, TO BARE METAL, PER NEC 250-12.

GROUNDING LUG CONNECTION DETAIL



PIPE GROUNDING CLAMP TABLE (OR APPROVED EQUAL)

BURNDY CAT. NO.	THOMAS & BETTS CAT. NO.	PIPE SIZE
GAR3902-BU	3902BU	1/2" - 1"
GAR3903-BU	3903BU	1 1/4" - 2"
GAR3904-BU	3904BU	2 1/2" - 3 1/2"
GAR3905-BU	3905BU	4" - 5"
GAR3906-BU	3906BU	6"

NOTES

- PIPE GROUNDING CLAMPS SHALL HAVE BRONZE HARDWARE, BE CORROSION RESISTANT, SUITABLE FOR DIRECT BURIAL IN EARTH OR CONCRETE, & UL 467 LISTED.


PIPE/CONDUIT GROUNDING CLAMP DETAIL

GROUNDING NOTES

THE CONTRACTOR SHALL FURNISH AND INSTALL ALL GROUNDING AS MAY BE NECESSARY OR REQUIRED TO MAKE A COMPLETE GROUNDING SYSTEM AS REQUIRED BY THE LATEST NATIONAL ELECTRICAL CODE (NFPA 70) IN FORCE AND FAA-STD-019e (LIGHTNING AND SURGE PROTECTION, GROUNDING, BONDING, AND SHIELDING REQUIREMENTS FOR FACILITIES AND ELECTRONIC EQUIPMENT). THE RELIABILITY OF THE GROUNDING SYSTEM IS DEPENDENT ON CAREFUL, PROPER INSTALLATION AND CHOICE OF MATERIALS. IMPROPER PREPARATION OF SURFACES TO BE JOINED TO MAKE AN ELECTRICAL PATH, LOOSE JOINTS OR CORROSION CAN INTRODUCE IMPEDANCE THAT WILL SERIOUSLY IMPAIR THE ABILITY OF THE GROUND PATH TO PROTECT PERSONNEL AND EQUIPMENT AND TO ABSORB TRANSIENTS THAT CAN CAUSE NOISE IN COMMUNICATIONS CIRCUITS. THE FOLLOWING FUNCTIONS ARE PARTICULARLY IMPORTANT TO ENSURE A RELIABLE GROUND SYSTEM:

- FURNISH AND INSTALL GROUND RODS AS DETAILED HEREIN. GROUND RODS SHALL BE MINIMUM 3/4-IN. DIAMETER BY 10-FT LONG, UL-LISTED, COPPER CLAD WITH 10-MIL MINIMUM COPPER COATING (UNLESS DETAILED OTHERWISE HEREIN). GROUND RODS SHALL BE SPACED OR AS DETAILED ON THE RESPECTIVE PLANS, AND IN NO CASE SPACED LESS THAN ONE ROD LENGTH APART. ALL CONNECTIONS TO GROUND RODS AND THE GROUND RING SHALL BE MADE WITH EXOTHERMIC WELD TYPE CONNECTORS, CADWELD BY PENTAIR ERICO PRODUCTS, INC., THERMOWELD BY CONTINENTAL INDUSTRIES, INC., ULTRAWELD BY HARGER, OR APPROVED EQUAL. EXOTHERMIC WELD CONNECTIONS SHALL BE INSTALLED IN CONFORMANCE WITH THE RESPECTIVE MANUFACTURER'S DIRECTIONS USING MOLDS AS REQUIRED FOR EACH RESPECTIVE APPLICATION. BOLTED CONNECTIONS WILL NOT BE PERMITTED AT GROUND RODS OR AT BURIED GROUNDING ELECTRODE CONDUCTORS.
- CONTRACTOR SHALL TEST EACH MADE ELECTRODE GROUND ROD/GROUND FIELD/GROUND RING WITH AN INSTRUMENT SPECIFICALLY DESIGNED FOR TESTING GROUND FIELD SYSTEMS. IF GROUND RESISTANCE EXCEEDS 25 OHMS, CONTACT THE PROJECT ENGINEER FOR FURTHER DIRECTION. ALSO REFER TO EOR-47643 FOR ADDITIONAL INFORMATION ON GROUNDING REQUIREMENTS WHERE APPLICABLE. COPIES OF GROUND ROD TEST RESULTS SHALL BE FURNISHED TO THE RESIDENT ENGINEER/RESIDENT TECHNICIAN AND THE PROJECT ENGINEER.
- ALL PRODUCTS ASSOCIATED WITH THE GROUNDING SYSTEM SHALL BE UL-LISTED AND LABELED.
- ALL BOLTED OR MECHANICAL CONNECTIONS SHALL BE COATED WITH A CORROSION PREVENTATIVE COMPOUND BEFORE JOINING, SANCHEM INC. "NO-OX-ID "A-SPECIAL" COMPOUND, BURNDY PENETROX E, OR APPROVED EQUAL.
- METALLIC SURFACES TO BE JOINED SHALL BE PREPARED BY THE REMOVAL OF ALL NON-CONDUCTIVE MATERIAL, PER 2017 NATIONAL ELECTRICAL CODE ARTICLE 250-12. ALL COPPER BUS BARS MUST BE CLEANED PRIOR TO MAKING CONNECTIONS TO REMOVE SURFACE OXIDATION.
- METALLIC RACEWAY FITTINGS SHALL BE MADE UP TIGHT TO PROVIDE A PERMANENT LOW IMPEDANCE PATH FOR ALL CIRCUITS. METAL CONDUIT TERMINATIONS IN ENCLOSURES SHALL BE BONDED TO THE ENCLOSURE WITH UL-LISTED FITTINGS SUITABLE FOR GROUNDING. PROVIDE GROUNDING BUSHINGS WITH BONDING JUMPERS FOR ALL METAL CONDUITS ENTERING SERVICE EQUIPMENT (METER BASE, CT CABINET, MAIN SERVICE BREAKER ENCLOSURE, ETC.). PROVIDE GROUNDING BUSHINGS WITH BONDING JUMPERS FOR ALL METAL CONDUITS ENTERING AN ENCLOSURE THROUGH CONCENTRIC OR ECCENTRIC KNOCKOUTS THAT ARE PUNCHED OR OTHERWISE FORMED SO AS TO IMPAIR THE ELECTRICAL CONNECTION TO GROUND. STANDARD LOCKNUTS OR BUSHINGS SHALL NOT BE THE SOLE MEANS FOR BONDING WHERE A CONDUIT ENTERS AN ENCLOSURE THROUGH A CONCENTRIC OR ECCENTRIC KNOCKOUT
- ALL CONNECTIONS, LOCATED ABOVE GRADE, BETWEEN THE DIFFERENT TYPES OF GROUNDING CONDUCTORS SHALL BE MADE USING UL-LISTED DOUBLE COMPRESSION CRIMP TYPE CONNECTORS OR UL-LISTED BOLTED GROUND CONNECTORS. FOR GROUND CONNECTIONS TO ENCLOSURES, CASES AND FRAMES OF ELECTRICAL EQUIPMENT NOT SUPPLIED WITH GROUND LUGS THE CONTRACTOR SHALL DRILL REQUIRED HOLES FOR MOUNTING A BOLTED GROUND CONNECTOR. ALL BOLTED GROUND CONNECTORS SHALL BE BURNDY, DOSSERT CORPORATION, ILSCO CORPORATION, PENN-UNION CORPORATION, THOMAS & BETTS, OR APPROVED EQUAL. TIGHTEN CONNECTIONS TO COMPLY WITH TIGHTENING TORQUES IN UL STANDARD 486A TO ASSURE PERMANENT AND EFFECTIVE GROUNDING.
- ALL METAL EQUIPMENT ENCLOSURES, CONDUITS, CABINETS, BOXES, RECEPTACLES, MOTORS, ETC. SHALL BE BONDED TO THE RESPECTIVE GROUNDING SYSTEM.
- PROVIDE ALL BOXES FOR PROPOSED OUTLETS, SWITCHES, CIRCUIT BREAKERS, ETC. WITH GROUNDING SCREWS. PROVIDE ALL PANELBOARD, SWITCHGEAR, ETC., ENCLOSURES WITH GROUNDING BARS WITH INDIVIDUAL SCREWS, LUGS, CLAMPS, ETC., FOR EACH OF THE GROUNDING CONDUCTORS THAT ENTER THEIR RESPECTIVE ENCLOSURES.
- EACH NEW FEEDER CIRCUIT AND/OR BRANCH CIRCUIT SHALL INCLUDE AN EQUIPMENT GROUND WIRE. METAL RACEWAY OR CONDUIT SHALL NOT MEET THIS REQUIREMENT. THE EQUIPMENT GROUND WIRE FROM EQUIPMENT SHALL NOT BE SMALLER THAN ALLOWED BY 2017 NEC TABLE 250-122 "MINIMUM SIZE CONDUCTORS OR GROUNDING RACEWAY AND EQUIPMENT." WHEN CONDUCTORS ARE ADJUSTED IN SIZE TO COMPENSATE FOR VOLTAGE DROP, EQUIPMENT-GROUNDING CONDUCTORS SHALL BE ADJUSTED PROPORTIONATELY ACCORDING TO CIRCULAR MIL AREA. ALL EQUIPMENT GROUND WIRES SHALL BE COPPER, EITHER BARE OR INSULATED GREEN IN COLOR. WHERE THE EQUIPMENT GROUNDING CONDUCTORS ARE INSULATED, THEY SHALL BE IDENTIFIED BY THE COLOR GREEN, AND SHALL BE THE SAME INSULATION TYPE AS THE PHASE CONDUCTORS.

- ALL EXTERIOR METAL CONDUIT, WHERE NOT ELECTRICALLY CONTINUOUS BECAUSE OF MANHOLES, HANDHOLES, NON-METALLIC JUNCTION BOXES, ETC., SHALL BE BONDED TO ALL OTHER METAL CONDUIT IN THE RESPECTIVE DUCT RUN, AND AT EACH END, WITH A COPPER-BONDING JUMPER SIZED IN CONFORMANCE WITH 2017 NEC 250-102. WHERE METAL CONDUITS TERMINATE IN AN ENCLOSURE (SUCH AS A MOTOR CONTROL CENTER, SWITCHBOARD, ETC) WHERE THERE IS NOT ELECTRICAL CONTINUITY WITH THE CONDUIT AND THE RESPECTIVE ENCLOSURE, PROVIDE A BONDING JUMPER FROM THE RESPECTIVE ENCLOSURE GROUND BUS TO THE CONDUIT SIZED PER 2017 NEC 250-102.
- IT IS THE INTENT OF THIS SPECIFICATION THAT ALL MOTOR FRAMES, PUMP BASES ELECTRICAL EQUIPMENT ENCLOSURES, PANEL HOUSINGS, CONDUITS, BOXES, ETC. HAVE A CONTINUOUS COPPER WIRE GROUND CONNECTION AND SHALL BE POSITIVELY BONDED TO THE RESPECTIVE GROUNDING SYSTEM. CONDUIT CONNECTORS WILL NOT BE CONSIDERED AS ADEQUATE GROUNDING.
- PROVIDE A POSITIVE GROUND BOND FOR ALL OUTLET BOXES, ELECTRICAL EQUIPMENT ENCLOSURES, GROUNDING RECEPTACLES, TOGGLE SWITCHES, ETC. INSTALL A GROUNDING CONDUCTOR IN ALL WIRE AND CABLE RACEWAYS. GROUND CONDUCTOR TO HAVE 600-VOLT INSULATION AND BE IDENTIFIED BY A CONTINUOUS GREEN COLOR COATING. THEY SHALL BE USED SOLELY FOR GROUNDING PURPOSES AND BE ENTIRELY SEPARATE FROM WHITE GROUNDED NEUTRAL CONDUCTOR, EXCEPT AT SUPPLY SIDE OF SERVICE DISCONNECTING MEANS, WHERE GROUNDING AND NEUTRAL SYSTEMS ARE TO BE CONNECTED TO SERVICE GROUND.
- EACH AND ALL GROUNDED CASED AND METAL PARTS ASSOCIATED WITH ELECTRICAL EQUIPMENT SHALL BE TESTED FOR CONTINUITY OF CONNECTION WITH GROUND BUS SYSTEM BY CONTRACTOR IN PRESENCE OF OWNER'S REPRESENTATIVE.
- ALL CONNECTIONS BETWEEN THE DIFFERENT TYPES OF GROUNDING CONDUCTORS ABOVE GRADE SHALL BE MADE USING BOLTED GROUND CONNECTORS. GROUND LUGS SHALL BE PROVIDED IN ALL ENCLOSURES AND WIRING TERMINATION JUNCTION BOXES. EQUIPMENT GROUNDS AND GROUNDING CONDUCTOR SHALL BE CONNECTED TO THESE GROUND LUGS. FOR GROUND CONNECTIONS TO ENCLOSURES, CASES AND FRAMES OF ELECTRICAL EQUIPMENT NOT SUPPLIED WITH GROUND LUGS THE CONTRACTOR SHALL DRILL REQUIRED HOLES FOR MOUNTING A BOLTED GROUND CONNECTOR. ALL BOLTED GROUND CONNECTORS SHALL BE BURNDY, DOSSERT CORPORATION, ILSCO CORPORATION, PENN-UNION CORPORATION, THOMAS & BETTS, OR APPROVED EQUAL.
- BOND ALL NONCURRENT-CARRYING PARTS OF METAL EQUIPMENT TO GROUND SYSTEM.
- BUILDING STRUCTURAL STEEL SYSTEM SHALL BE BONDED TO ELECTRICAL GROUND SYSTEM.
- INSTALL GROUNDING ELECTRODE CONDUCTORS, LIGHTNING PROTECTION DOWN CONDUCTORS AND SEPARATE GROUND CONDUCTORS IN SCHEDULE 40 OR SCHEDULE 80 PVC CONDUIT OR EXPOSED WHERE ACCEPTABLE TO LOCAL CODES. WHERE GROUNDING ELECTRODE CONDUCTORS, LIGHTNING PROTECTION DOWN CONDUCTORS OR INDIVIDUAL GROUND CONDUCTORS ARE RUN IN PVC CONDUIT, DO NOT COMPLETELY ENCIRCLE CONDUIT WITH FERROUS AND/OR MAGNETIC MATERIALS. USE NON-METALLIC REINFORCED FIBERGLASS STRUT SUPPORT. WHERE METAL CONDUIT CLAMPS ARE INSTALLED, USE NYLON BOLTS, NUTS, WASHERS AND SPACERS TO INTERRUPT A COMPLETE METALLIC PATH FROM ENCIRCLING THE CONDUIT. THIS IS REQUIRED TO AVOID GIRDLING OF GROUND CONDUCTORS. GIRDLING OF A GROUND CONDUCTOR IS THE RESULT OF PLACING THE CONDUCTOR IN A RING OF MAGNETIC MATERIAL. THIS RING COULD BE A METALLIC CONDUIT, U-BOLT OR STRUT SUPPORT PIPE CLAMP, OR OTHER SUPPORT HARDWARE. THE RESULT OF GIRDLING GROUND CONDUCTORS SIGNIFICANTLY INCREASES THE INDUCTIVE IMPEDANCE OF THE GROUND CONDUCTOR. INDUCTIVE AND CAPACITIVE IMPEDANCE IS A TYPE OF RESISTANCE THAT OPPOSES THE FLOW OF ALTERNATING CURRENT. ANY INCREASE IN THE IMPEDANCE OF A GROUND CONDUCTOR REDUCES ITS ABILITY TO EFFECTIVELY MITIGATE RADIO FREQUENCY NOISE IN THE GROUND SYSTEM. THE CONDITION WHERE A GROUND CONDUCTOR IS GIRDLING DURING A LIGHTNING STRIKE RESULTS IN PHENOMENA KNOWN AS SURGE IMPEDANCE LOADING. SURGE IMPEDANCE LOADING IS A RESULT OF VOLTAGE AND CURRENT REACHING 500,000 VOLTS AND 10,000 AMPS FOR A SHORT DURATION. GIRDLING FURTHER INCREASES THE IMPEDANCE AT LIGHTNING FREQUENCIES OF 100 KILOHERTZ TO 100 MEGAHERTZ. AT THESE POWER AND FREQUENCY LEVELS ANY INCREASE IN THE IMPEDANCE OF THE GROUND CONDUCTOR MUST BE CONTROLLED. DURING LIGHTNING DISCHARGE CONDITIONS A LOW INDUCTIVE IMPEDANCE PATH IS MORE IMPORTANT THAN A LOW DC RESISTANCE PATH.
- IF LOCAL CODES DICTATE THAT INDIVIDUAL GROUNDING CONDUCTORS MUST BE RUN IN METAL CONDUIT OR RACEWAY, THEN THE CONDUIT OR RACEWAY MUST BE BONDED AT EACH END OF THE RUN WITH A BONDING JUMPER SIZED EQUAL TO THE INDIVIDUAL GROUNDING CONDUCTOR OR AS REQUIRED BY 2017 NEC 250-102. NOTE THIS DOES NOT APPLY TO AC EQUIPMENT GROUNDING CONDUCTORS RUN WITH AC CIRCUITS.
- NEVER REMOVE, ALTER, OR ATTEMPT TO REPAIR CONDUCTORS OR CONDUIT SYSTEMS PROVIDING GROUNDING OR ELECTRICAL BONDING FOR ANY ELECTRICAL EQUIPMENT UNTIL ALL POWER IS REMOVED FROM EQUIPMENT. WARN ALL PERSONNEL OF THE UNGROUNDED CONDITION OF THE EQUIPMENT. DISPLAY APPROPRIATE WARNING SIGNS, SUCH AS DANGER TAGS, TO WARN PERSONNEL OF THE POSSIBLE HAZARDS.
- GROUNDING WORK AND MODIFICATIONS SHALL NOT BE PERFORMED DURING A THUNDERSTORM OR WHEN A THUNDERSTORM IS PREDICTED IN THE AREA
- WHERE A CONFLICT IS DETERMINED WITH RESPECT TO GROUNDING REQUIREMENTS PER MANUFACTURER INSTALLATION INSTRUCTIONS, NEC, AND/OR THE CONTRACT DOCUMENTS, CONTACT THE PROJECT ENGINEER FOR FURTHER DIRECTIONS.
- GROUND RODS SHALL BE MANUFACTURED IN THE UNITED STATES OF AMERICA FROM 100 PERCENT DOMESTIC STEEL TO COMPLY WITH THE AIRPORT IMPROVEMENT PROGRAM BUY AMERICAN REQUIREMENTS AND THE STEEL PRODUCTS PROCUREMENT ACT.



10 FT. GROUND ROD

GROUND RODS

NOT TO SCALE

NOTES

- TYPE AND MINIMUM NUMBER OF GROUND RODS SHALL BE AS SPECIFIED ON THE PLAN.
- THE RESISTANCE TO GROUND OF THE GROUNDING SYSTEM SHALL NOT EXCEED 25 OHMS.
- COST OF GROUND RODS IS INCIDENTAL TO THE ASSOCIATED ITEMS REQUIRING GROUNDING UNLESS OTHERWISE SPECIFIED.
- GROUND RODS SHALL BE SPACED AS DETAILED ON THE PLANS AND SHALL NOT BE SPACED LESS THAN ONE ROD LENGTH APART.
- TOP OF GROUND RODS FOR AIRFIELD LIGHT FIXTURES AND TAXI GUIDANCE SIGNS, SHALL BE 12" MINIMUM BELOW GRADE UNLESS DETAILED OTHERWISE HEREIN.
- GROUND RODS FOR INDIVIDUAL SPLICE CANS SHALL BE 3/4-IN DIAMETER BY 10 FOOT LONG. WHERE GROUND RESISTANCE EXCEEDS 25 OHMS FURNISH AND INSTALL A SECOND GROUND ROD SPACED MINIMUM OF 10 FEET APART (ONE ROD LENGTH APART), AND CONNECT TO FIRST GND ROD.



Engineering | Planning | Allied Services

Hanson Professional Services Inc.
1525 S. 6th Street
Springfield, IL 62703
phone: 217-788-2450
fax: 217-788-2503

Offices Nationwide
www.hanson-inc.com

Illinois Licensed
Professional Service Corporation
#184-001084



ST. LOUIS REGIONAL AIRPORT

8 Terminal Drive
East Alton, Illinois 62024



Kevin N. Lightfoot

DATE SIGNED: 11/18/2021 LICENSE EXPIRES: 2/28/2022

REHABILITATE RUNWAY 17-35 PAVEMENT & LIGHTING

SBG No:
3-17-SBGP-171/175
IDA No: ALN-4812

Contract No. SR095

NO.	DATE	DESCRIPTION		
		DES	DWN	REV

ISSUE: NOVEMBER 19, 2021

PROJECT NO: 17A008504

CAD FILE: E-004-NOTES.DWG

DESIGN BY: KNL 03/18/2021

DRAWN BY: CWS 03/18/2021

REVIEWED BY: KNL 03/18/2021

SHEET TITLE

GROUNDING NOTES

FOR BID



Kevin N. Lightfoot

DATE SIGNED: 11/18/2021 LICENSE EXPIRES: 2/28/2022

REHABILITATE
RUNWAY 17-35
PAVEMENT & LIGHTING

SBG No:
3-17-SBGP-171/175
IDA No: ALN-4812

Contract No. SR095

NO.	DATE	DESCRIPTION		
		DES	DWN	REV

ISSUE: NOVEMBER 19, 2021

PROJECT NO: 17A008504

CAD FILE: E-602.DWG

DESIGN BY: KNL 03/18/2021

DRAWN BY: CWS 03/18/2021


REVIEWED BY: KNL 03/18/2021

SHEET TITLE

EXISTING HIGH
VOLTAGE WIRING
SCHEMATIC FOR
RUNWAY 11-29

NOTES:

- KEEP ALL WORK, POWER OUTAGES, AND/OR SHUT DOWN OF EXISTING SYSTEMS COORDINATED WITH THE AIRPORT MANAGER/DIRECTOR AND RESIDENT ENGINEER/TECHNICIAN. ONCE SHUT DOWN, THE CIRCUITS SHALL BE LABELED AS SUCH TO PREVENT ACCIDENTAL ENERGIZING OF THE RESPECTIVE CIRCUITS. ALL PERSONNEL SHALL FOLLOW U.S. DEPARTMENT OF LABOR OCCUPATIONAL SAFETY & HEALTH ADMINISTRATION (OSHA) 29 CFR PART 1910 OCCUPATIONAL SAFETY & HEALTH STANDARDS FOR ELECTRICAL SAFETY AND LOCKOUT/TAGOUT PROCEDURES INCLUDING, BUT NOT LIMITED TO, 29 CFR SECTION 1910.147 THE CONTROL OF HAZARDOUS ENERGY (LOCKOUT/TAGOUT).
- EXAMINE THE SITE TO CONFIRM AND FIELD VERIFY EXISTING SITE CONDITIONS.
- VERIFY RESPECTIVE CIRCUITS AND POWER SOURCES FOR RESPECTIVE SYSTEMS PRIOR TO REMOVING, DISCONNECTING, WORKING ON, RELOCATING, RECONNECTING, AND/OR INSTALLING THE RESPECTIVE AIRFIELD LIGHTING, TAXI SIGN, NAVAID, VAULT EQUIPMENT, OR OTHER DEVICES. THE CONTRACTOR WILL NEED TO EXERCISE CAUTION WHEN WORKING IN THE VAULT AND ON THE AIRFIELD. CONTRACTOR SHALL REPORT ANY VARIATIONS, DEFICIENCIES, AND/OR APPARENT SAFETY CONCERNS TO THE PROJECT ENGINEER AND THE RESIDENT PROJECT REPRESENTATIVE. CONTRACTOR SHALL FOLLOW LOCKOUT/TAGOUT PROCEDURES FOR SAFETY PERSONNEL.
- IDENTIFY EACH RESPECTIVE CIRCUIT PRIOR TO PERFORMING WORK ON THAT CIRCUIT.
- NOTE THE EXISTING AIRPORT ELECTRICAL VAULT HAS APPARENT NATIONAL ELECTRICAL CODE WORKING CLEARANCE VIOLATIONS WHICH MIGHT CAUSE UNSAFE WORKING CONDITIONS. CONTRACTOR SHALL FIELD VERIFY EXISTING CONDITIONS AND CIRCUITS. CONTRACTOR WILL NEED TO EXERCISE CAUTION WHEN WORKING IN THE VAULT AND ON THE AIRFIELD.
- NEVER REMOVE OR INSERT A CUTOUT WITH THE CIRCUIT ENERGIZED. SHUTOFF CIRCUITS PRIOR TO PULLING OR INSERTING A SERIES PLUG CUTOUT.
- THE RESPECTIVE PERSONNEL PERFORMING AIRFIELD LIGHTING WORK, VAULT WORK, AND/OR TESTS SHALL BE FAMILIAR WITH, AND QUALIFIED TO WORK ON, 5000 VOLT AIRFIELD LIGHTING SERIES CIRCUITS, CONSTANT CURRENT REGULATORS, AND ASSOCIATED AIRPORT ELECTRICAL VAULT EQUIPMENT.
- EXERCISE CAUTION, PRACTICE SAFETY, AND DISCONNECT THE SERIES CIRCUITS FROM THE RESPECTIVE CONSTANT CURRENT REGULATORS, AS APPLICABLE WHEN PERFORMING WORK ON THE AIRFIELD LIGHTING OR WORK THAT MIGHT AFFECT THE AIRFIELD LIGHTING. CONTRACTOR SHALL MAKE NECESSARY ARRANGEMENTS TO DISCONNECT POWER AND LOCKOUT CIRCUITS FOR PROTECTION OF PERSONNEL. EXISTING CCR'S DO NOT APPEAR TO HAVE CUTOUTS.
- OVERSEE AND CONDUCT TESTS FOR AREAS OF WORK WHERE THE RESPECTIVE CIRCUITS MIGHT BE AFFECTED. MEGGER TEST AND RECORD EXISTING SERIES CIRCUITS (WITH A CABLE INSULATION TESTER) PRIOR TO CABLE WORK OR ANY OTHER WORK THAT MIGHT POSSIBLY AFFECT AIRFIELD LIGHTING SYSTEMS, AND AGAIN AFTER AIRFIELD LIGHTING MODIFICATIONS, ADDITIONS, UPGRADES AND/OR OTHER WORK HAS BEEN COMPLETED. PROVIDE 5KV INSULATION TESTER FOR 5,000 VOLT SERIES CIRCUIT CABLES. ALSO TEST AND RECORD SERIES CIRCUIT LOOP RESISTANCE WITH AN OHMMETER. PROVIDE COPY OF TEST RESULTS TO THE ENGINEER OF RECORD (EOR) WITHIN 5 DAYS OF CONDUCTING TESTS.
- RESPECTIVE CCR'S SHALL BE TESTED FOR PROPER OPERATION BEFORE REMOVAL WORK, MODIFICATIONS, ADDITIONS AND/OR ANY AIRFIELD WORK THAT MIGHT AFFECT LIGHTING CIRCUITS AND AGAIN AFTER THE AIRFIELD WORK AND ADDITIONS HAVE BEEN COMPLETED. CONTRACTOR SHALL TEST AND RECORD THE INPUT CURRENT AND OUTPUT CURRENT FOR EACH CONSTANT CURRENT REGULATOR IN THE AUTOMATIC AND MANUAL MODES OF OPERATION. PROVIDE A TRUE RMS AMMETER FOR CURRENT MEASUREMENTS. CONTRACTOR SHALL REPORT CONCERNS AND/OR DEFICIENCIES TO THE RESIDENT PROJECT REPRESENTATIVE AND THE ENGINEER OF RECORD (EOR). WRITTEN TEST RESULTS SHALL BE PROVIDED TO THE RESIDENT PROJECT REPRESENTATIVE AND THE ENGINEER OF RECORD (EOR).
- FURNISH AND INSTALL UL LISTED FIRE STOP MATERIAL AT EACH SERIES PLUG CUTOUT ENCLOSURE CONDUIT ENTRY AND EXIT.



EXISTING VOLTAGE WIRING SCHEMATIC FOR RUNWAY 11-29

LEGEND

- "I" DENOTES PLUG CUTOUT WITH PLUG INSERTED
- "P" DENOTES PLUG CUTOUT WITH PLUG PULLED
- "CCR" DENOTES CONSTANT CURRENT REGULATOR

NEMA 1 OR NEMA 12 ENCLOSURE WITH HINGED COVER AND BACK PANEL. ENCLOSURE SHALL BE PAD LOCKABLE AND ADEQUATELY SIZED FOR TWO TYPE S-1 PLUG CUTOUTS ADJACENT TO EACH OTHER. PLUG CUTOUT PAIR SHALL BE WIRED FOR MANUAL LOAD TRANSFER SWITCH OPERATION BETWEEN TWO REGULATORS AND SHALL HAVE ONE S1 HANDLE/PLUG ASSEMBLY FOR THE PAIR OF CUTOUTS.



Kevin N. Lightfoot

DATE LICENSE
SIGNED: 11/18/2021 EXPIRES: 2/28/2022

**REHABILITATE
RUNWAY 17-35
PAVEMENT & LIGHTING**

SBG No:
3-17-SBGP-171/175
IDA No: ALN-4812

Contract No. SR095

NO.	DATE	DESCRIPTION		
		DES	DWN	REV

ISSUE: NOVEMBER 19, 2021

PROJECT NO: 17A008504

CAD FILE: E-603.DWG

DESIGN BY: KNL 03/18/2021


DRAWN BY: CWS 03/18/2021

REVIEWED BY: KNL 03/18/2021

SHEET TITLE

**EXISTING HIGH
VOLTAGE WIRING
SCHEMATIC FOR
RWY 17-35 & TWYS**

FOR BID



EXISTING HIGH VOLTAGE WIRING SCHEMATIC FOR RUNWAY 17-35 & TAXIWAYS

LEGEND

- "I" DENOTES PLUG CUTOUT WITH PLUG INSERTED
- "P" DENOTES PLUG CUTOUT WITH PLUG PULLED
- "CCR" DENOTES CONSTANT CURRENT REGULATOR

NOTES:

1. KEEP ALL WORK, POWER OUTAGES, AND/OR SHUT DOWN OF EXISTING SYSTEMS COORDINATED WITH THE AIRPORT MANAGER/DIRECTOR AND RESIDENT ENGINEER/TECHNICIAN. ONCE SHUT DOWN, THE CIRCUITS SHALL BE LABELED AS SUCH TO PREVENT ACCIDENTAL ENERGIZING OF THE RESPECTIVE CIRCUITS. ALL PERSONNEL SHALL FOLLOW U.S. DEPARTMENT OF LABOR OCCUPATIONAL SAFETY & HEALTH ADMINISTRATION (OSHA) 29 CFR PART 1910 OCCUPATIONAL SAFETY & HEALTH STANDARDS FOR ELECTRICAL SAFETY AND LOCKOUT/TAGOUT PROCEDURES INCLUDING, BUT NOT LIMITED TO, 29 CFR SECTION 1910.147 THE CONTROL OF HAZARDOUS ENERGY (LOCKOUT/TAGOUT).
2. EXAMINE THE SITE TO CONFIRM AND FIELD VERIFY EXISTING SITE CONDITIONS.
3. VERIFY RESPECTIVE CIRCUITS AND POWER SOURCES FOR RESPECTIVE SYSTEMS PRIOR TO REMOVING, DISCONNECTING, WORKING ON, RELOCATING, RECONNECTING, AND/OR INSTALLING THE RESPECTIVE AIRFIELD LIGHTING, TAXI SIGN, NAVAID, VAULT EQUIPMENT, OR OTHER DEVICES. THE CONTRACTOR WILL NEED TO EXERCISE CAUTION WHEN WORKING IN THE VAULT AND ON THE AIRFIELD. CONTRACTOR SHALL REPORT ANY VARIATIONS, DEFICIENCIES, AND/OR APPARENT SAFETY CONCERNS TO THE PROJECT ENGINEER AND THE RESIDENT PROJECT REPRESENTATIVE. CONTRACTOR SHALL FOLLOW LOCKOUT/TAGOUT PROCEDURES FOR SAFETY PERSONNEL.
4. IDENTIFY EACH RESPECTIVE CIRCUIT PRIOR TO PERFORMING WORK ON THAT CIRCUIT.
5. NOTE THE EXISTING AIRPORT ELECTRICAL VAULT HAS APPARENT NATIONAL ELECTRICAL CODE WORKING CLEARANCE VIOLATIONS WHICH MIGHT CAUSE UNSAFE WORKING CONDITIONS. CONTRACTOR SHALL FIELD VERIFY EXISTING CONDITIONS AND CIRCUITS. CONTRACTOR WILL NEED TO EXERCISE CAUTION WHEN WORKING IN THE VAULT AND ON THE AIRFIELD.
6. NEVER REMOVE OR INSERT A CUTOUT WITH THE CIRCUIT ENERGIZED. SHUTOFF CIRCUITS PRIOR TO PULLING OR INSERTING A SERIES PLUG CUTOUT.
7. THE RESPECTIVE PERSONNEL PERFORMING AIRFIELD LIGHTING WORK, VAULT WORK, AND/OR TESTS SHALL BE FAMILIAR WITH, AND QUALIFIED TO WORK ON, 5000 VOLT AIRFIELD LIGHTING SERIES CIRCUITS, CONSTANT CURRENT REGULATORS, AND ASSOCIATED AIRPORT ELECTRICAL VAULT EQUIPMENT.
8. EXERCISE CAUTION, PRACTICE SAFETY, AND DISCONNECT THE SERIES CIRCUITS FROM THE RESPECTIVE CONSTANT CURRENT REGULATORS, AS APPLICABLE WHEN PERFORMING WORK ON THE AIRFIELD LIGHTING OR WORK THAT MIGHT AFFECT THE AIRFIELD LIGHTING. CONTRACTOR SHALL MAKE NECESSARY ARRANGEMENTS TO DISCONNECT POWER AND LOCKOUT CIRCUITS FOR PROTECTION OF PERSONNEL. EXISTING CCR'S DO NOT APPEAR TO HAVE CUTOUTS.
9. OVERSEE AND CONDUCT TESTS FOR AREAS OF WORK WHERE THE RESPECTIVE CIRCUITS MIGHT BE AFFECTED. MEGGER TEST AND RECORD EXISTING SERIES CIRCUITS (WITH A CABLE INSULATION TESTER) PRIOR TO CABLE WORK OR ANY OTHER WORK THAT MIGHT POSSIBLY AFFECT AIRFIELD LIGHTING SYSTEMS, AND AGAIN AFTER AIRFIELD LIGHTING MODIFICATIONS, ADDITIONS, UPGRADES AND/OR OTHER WORK HAS BEEN COMPLETED. PROVIDE 5KV INSULATION TESTER FOR 5,000 VOLT SERIES CIRCUIT CABLES. ALSO TEST AND RECORD SERIES CIRCUIT LOOP RESISTANCE WITH AN OHMMETER. PROVIDE COPY OF TEST RESULTS TO THE ENGINEER OF RECORD (EOR) WITHIN 5 DAYS OF CONDUCTING TESTS.
10. RESPECTIVE CCR'S SHALL BE TESTED FOR PROPER OPERATION BEFORE REMOVAL WORK, MODIFICATIONS, ADDITIONS AND/OR ANY AIRFIELD WORK THAT MIGHT AFFECT LIGHTING CIRCUITS AND AGAIN AFTER THE AIRFIELD WORK AND ADDITIONS HAVE BEEN COMPLETED. CONTRACTOR SHALL TEST AND RECORD THE INPUT CURRENT AND OUTPUT CURRENT FOR EACH CONSTANT CURRENT REGULATOR IN THE AUTOMATIC AND MANUAL MODES OF OPERATION. PROVIDE A TRUE RMS AMMETER FOR CURRENT MEASUREMENTS. CONTRACTOR SHALL REPORT CONCERNS AND/OR DEFICIENCIES TO THE RESIDENT PROJECT REPRESENTATIVE AND THE ENGINEER OF RECORD (EOR). WRITTEN TEST RESULTS SHALL BE PROVIDED TO THE RESIDENT PROJECT REPRESENTATIVE AND THE ENGINEER OF RECORD (EOR).
11. FURNISH AND INSTALL UL LISTED FIRE STOP MATERIAL AT EACH SERIES PLUG CUTOUT ENCLOSURE CONDUIT ENTRY AND EXIT.



Kevin N. Lightfoot

DATE SIGNED: 11/18/2021 LICENSE EXPIRES: 2/28/2022

REHABILITATE
RUNWAY 17-35
PAVEMENT & LIGHTING

SBG No:
3-17-SBGP-171/175
IDA No: ALN-4812

Contract No. SR095

NO.	DATE	DESCRIPTION		
		DES	DWN	REV

ISSUE: NOVEMBER 19, 2021

PROJECT NO: 17A008504

CAD FILE: E-606-SCM.DWG

DESIGN BY: KNL 03/18/2021

DRAWN BY: CWS 03/18/2021

REVIEWED BY: KNL 03/18/2021

SHEET TITLE

PROPOSED HIGH
VOLTAGE
SCHEMATIC FOR
RWY 17-35 CCR

LEGEND PLATE SCHEDULE	
DEVICE	LABEL
RUNWAY 17-35 CCR	RUNWAY 17-35
RUNWAY 17-35 CCR	CAUTION OPERATE CUTOUT WITH CCR SHUT OFF
CUTOUT ENCLOSURE FOR RUNWAY 17-35	RUNWAY 17-35


LEGEND NOTES:

- LEGEND PLATES SHALL BE WEATHERPROOF ENGRAVED PLASTIC OR PHENOLIC MATERIAL, 1/4" HIGH BLACK LETTERS ON A WHITE BACKGROUND UNLESS NOTED OTHERWISE. SECURE WITH WEATHERPROOF ADHESIVE AND MACHINE SCREWS. FURNISH ADDITIONAL LEGEND PLATES WHERE REQUIRED BY CODE, FOR ADDITIONAL EQUIPMENT, AS DETAILED HEREIN ON THE PLANS, AND AS NOTED IN THE SPECIAL PROVISION SPECIFICATIONS.
- FURNISH & INSTALL A WEATHERPROOF WARNING LABEL FOR EACH SAFETY SWITCH, PANELBOARD, LOAD CENTER, CUTOUT, & CONTROL PANEL TO WARN PERSONS OF POTENTIAL ELECTRIC ARC FLASH HAZARDS, PER THE REQUIREMENTS OF NEC 110.16 "ARC-FLASH HAZARD WARNING".



"DANGER - HIGH VOLTAGE" SIGN

FURNISH AND INSTALL "DANGER - HIGH VOLTAGE" LABELS/SIGNS FOR EACH CUTOUT ENCLOSURE, EACH CONSTANT CURRENT REGULATOR, AND THE HIGH VOLTAGE WIREWAY, TO COMPLY WITH FAA AC 150/5340-26C "MAINTENANCE OF AIRPORT VISUAL AID FACILITIES". LABELS SHALL BE APPROXIMATELY 4" X 6" OR 5" X 7".



PROPOSED HIGH VOLTAGE WIRING SCHEMATIC FOR RWY 17-35 CCR

NOT TO SCALE

NOTES:

- ALL WORK, POWER OUTAGES, AND/OR SHUT DOWN OF EXISTING SYSTEMS SHALL BE COORDINATED WITH THE AIRPORT DIRECTOR AND THE RESPECTIVE FAA ATCT PERSONNEL. ONCE SHUT DOWN, THE CIRCUITS SHALL BE LABELED AS SUCH TO PREVENT ACCIDENTAL ENERGIZING OF THE RESPECTIVE CIRCUITS. ALL PERSONNEL SHALL FOLLOW U.S. DEPARTMENT OF LABOR OCCUPATIONAL SAFETY & HEALTH ADMINISTRATION (OSHA) 29 CFR PART 1910 OCCUPATIONAL SAFETY & HEALTH STANDARDS FOR ELECTRICAL SAFETY AND LOCKOUT/TAGOUT PROCEDURES INCLUDING, BUT NOT LIMITED TO, 29 CFR SECTION 1910.147 THE CONTROL OF HAZARDOUS ENERGY (LOCKOUT/TAGOUT).
- THE RESPECTIVE PERSONNEL PERFORMING AIRFIELD LIGHTING WORK, VAULT WORK, AND/OR TESTS SHALL BE FAMILIAR WITH, AND QUALIFIED TO WORK ON, 5000 VOLT AIRFIELD LIGHTING SERIES CIRCUITS, CONSTANT CURRENT REGULATORS, AND ASSOCIATED AIRPORT ELECTRICAL VAULT EQUIPMENT.
- CONTRACTOR SHALL EXERCISE CAUTION, PRACTICE SAFETY, AND DISCONNECT THE SERIES CIRCUITS FROM THE RESPECTIVE CONSTANT CURRENT REGULATORS, AS APPLICABLE WHEN PERFORMING WORK ON THE AIRFIELD LIGHTING OR WORK THAT MIGHT AFFECT THE AIRFIELD LIGHTING. CONTRACTOR SHALL MAKE NECESSARY ARRANGEMENTS TO DISCONNECT POWER AND LOCKOUT CIRCUITS FOR PROTECTION OF PERSONNEL.
- EQUIPMENT AND MATERIALS NOT LABELED AS EXISTING ARE NEW.
- SERIES PLUG CUTOUTS SHALL BE TYPE S-1, RATED 5000 VOLTS, 20-AMP. SERIES PLUG CUTOUTS SHALL BE RATED SUITABLE FOR NORMAL OPERATION WITH HANDLE REMOVED OR HANDLE INSERTED. CUTOUTS SHALL DISCONNECT THE INPUT FROM THE FROM THE OUTPUT, SHORT THE INPUT TERMINALS, AND SHORT THE OUTPUT TERMINALS WHEN THE HANDLE/PLUG IS REMOVED. SERIES PLUG CUTOUTS SHALL BE MANAIRCO CAT. NO MRS1, CROUSE-HINDS CAT. NO. 30775, OR APPROVED EQUAL. THE RESPECTIVE MANUFACTURER SHALL CERTIFY IN WRITING THAT THEIR CUTOUT IS SUITABLE AND RATED FOR THE RESPECTIVE APPLICATION.
- BOND EACH REGULATOR FRAME TO VAULT GROUND BUS WITH A DEDICATED #6 AWG COPPER BONDING JUMPER.
- MAINTAIN SEPARATION OF HIGH VOLTAGE WIRING (AIRFIELD LIGHTING 5000 VOLT SERIES CIRCUITS AND/OR OTHER CIRCUITS RATED ABOVE 600 VOLTS) FROM LOW VOLTAGE WIRING (RATED 600 VOLTS AND BELOW) TO COMPLY WITH NEC 300.3(C)(2). HIGH VOLTAGE AND LOW VOLTAGE WIRING SHALL NOT BE INSTALLED IN THE SAME RACEWAY, CONDUIT, WIREWAY, PULL BOX, SPLICE CAN, HANDHOLE, OR MANHOLE.
- PROVIDE PHENOLIC ENGRAVED LEGEND PLATES FOR EACH CONSTANT CURRENT REGULATOR NOTING THE RUNWAY AND/OR TAXIWAY SERVED.
- EXISTING RUNWAY 17-35 CCR SHALL BE REMOVED AND REPLACED WITH A NEW CCR. EXISTING RUNWAY 17-35 CCR SHALL BE RELOCATED TO A STORAGE AREA ON THE AIRPORT.
- PROVIDE A LOCKOUT STATION SUITABLE FOR WALL MOUNTING, WITH 10 LOCKOUT PADLOCKS EACH WITH A DIFFERENT KEY, 5 LOCKOUT HASPS TO ACCOMMODATE MULTIPLE PADLOCKS, AND 100 LOCKOUT TAGS. LOCKOUT STATION AND COMPONENTS SHALL COMPLY WITH OSHA STANDARD 1910.147. INCLUDE HARDWARE TO MOUNT ON THE VAULT INTERIOR WALL.
- FURNISH AND INSTALL UL LISTED FIRE STOP MATERIAL AT EACH SERIES PLUG CUTOUT ENCLOSURE (EXISTING AND/OR NEW) CONDUIT ENTRY AND EXIT.

FOR BID



Kevin N. Lightfoot

DATE SIGNED: 11/18/2021 LICENSE EXPIRES: 2/28/2022

REHABILITATE
 RUNWAY 17-35
 PAVEMENT & LIGHTING

SBG No:
 3-17-SBGP-171/175
 IDA No: ALN-4812

Contract No. SR095

NO.	DATE	DESCRIPTION		
		DES	DWN	REV

ISSUE: NOVEMBER 19, 2021

PROJECT NO: 17A008504

CAD FILE: E-604.DWG

DESIGN BY: KNL 03/18/2021


DRAWN BY: CWS 03/18/2021

REVIEWED BY: KNL 03/18/2021

SHEET TITLE


SERIES CIRCUIT
 CABLE TESTING
 DETAILS

FOR BID



CABLE INSULATION RESISTANCE TEST (MEGGER TEST) NOTES

- PRIOR TO BEGINNING EXCAVATIONS, AIRFIELD LIGHTING MODIFICATIONS, CABLE INSTALLATION, AND/OR ANY OTHER WORK THAT MIGHT POSSIBLY AFFECT AIRFIELD LIGHTING CIRCUITS, ALL EXISTING SERIES CIRCUIT LIGHTING CABLES SHALL BE MEGGER TESTED WITH AN INSULATION RESISTANCE TESTER AND RECORDED AT THE RESPECTIVE AIRPORT ELECTRICAL VAULT.
- AFTER AIRFIELD LIGHTING MODIFICATIONS, ADDITIONS, UPGRADES, AND/OR OTHER WORK AND ADDITIONS HAVE BEEN COMPLETED ALL EXISTING SERIES CIRCUIT LIGHTING CABLES SHALL BE MEGGER TESTED WITH AN INSULATION RESISTANCE TESTER AND RECORDED AT THE RESPECTIVE AIRPORT ELECTRICAL VAULT.
- THE CONTRACTOR IS RESPONSIBLE TO EMPLOY THE SERVICES OF PERSONNEL QUALIFIED, FAMILIAR WITH, AND TRAINED TO PERFORM THE RESPECTIVE TESTS, AND QUALIFIED TO WORK ON 5000 VOLT AIRFIELD LIGHTING SERIES CIRCUITS, CONSTANT CURRENT REGULATORS, AND ASSOCIATED AIRPORT ELECTRICAL VAULT EQUIPMENT.
- INSULATION RESISTANCE TESTING EQUIPMENT FOR USE WITH 5,000 VOLT SERIES CIRCUIT CABLES SHALL USE AN INSULATION RESISTANCE TESTER CAPABLE OF TESTING THE CABLES AT 5,000 VOLTS. OLDER SERIES CIRCUIT CABLES AND/OR CABLES IN POOR CONDITION MAY REQUIRE THE TEST VOLTAGE TO BE PERFORMED AT A VOLTAGE LOWER THAN 5,000 VOLTS (EXAMPLE 1,000 VOLTS, 500 VOLTS, OR LESS THAN 500 VOLTS). THE RESPECTIVE TEST VOLTAGE SHALL BE RECORDED FOR EACH CABLE INSULATION RESISTANCE TEST RESULT.
- INSULATION RESISTANCE TESTING EQUIPMENT FOR USE WITH 600 VOLT RATED CABLES SHALL USE A 500 VOLT INSULATION RESISTANCE TESTER. THE RESPECTIVE TEST VOLTAGE SHALL BE RECORDED FOR EACH CABLE INSULATION RESISTANCE TEST RESULT.
- IT IS RECOMMENDED TO USE THE SAME INSULATION RESISTANCE TEST EQUIPMENT THROUGHOUT THE PROJECT TO ENSURE RELIABLE COMPARATIVE READINGS AT THE BEGINNING OF THE PROJECT AND AT THE COMPLETION OF THE PROJECT.
- DISCONNECT THE AIRFIELD LIGHTING SERIES CIRCUIT CABLES FROM THE CONSTANT CURRENT REGULATOR WHEN PERFORMING CABLE INSULATION RESISTANCE TESTS (MEGGER TESTS). TEST THE CABLES THAT GO TO THE AIRFIELD FOR THE RESPECTIVE AIRFIELD LIGHTING SERIES CIRCUIT. CONNECT THE CABLE INSULATION RESISTANCE TESTER TO ONE OF THE AIRFIELD LIGHTING SERIES CIRCUIT CABLES AND TO A GOOD GROUND IN THE AIRPORT ELECTRICAL VAULT SUCH AS THE AIRPORT VAULT GROUND BUS. CONDUCT THE CABLE INSULATION RESISTANCE TEST ON EACH RESPECTIVE CABLE FOR NOT LESS THAN 90 SECONDS. RECORD THE TEST RESULTS AT THE END OF THE TIME DURATION FOR THE TEST.
- FAA ADVISORY CIRCULAR 150/5340-26C MAINTENANCE OF AIRPORT VISUAL AID FACILITIES PROVIDES GUIDANCE ON INSULATION RESISTANCE TESTS. ALSO REFER TO THE USER MANUAL FOR THE RESPECTIVE CABLE INSULATION RESISTANCE TESTER. REASONABLY NEW SERIES CIRCUIT CABLES AND TRANSFORMERS WITH GOOD CONNECTIONS SHOULD READ 500 MEGA-OHMS TO 1,000 MEGA-OHMS OR HIGHER. THE READINGS SHOULD DECREASE WITH AGE. THE RESISTANCE VALUE DECLINES OVER THE SERVICE LIFE OF THE CIRCUIT; A 10-20 PERCENT DECLINE PER YEAR MAY BE CONSIDERED NORMAL. A YEARLY DECLINE OF 50 PERCENT (4 PERCENT MONTHLY) OR GREATER INDICATES THE EXISTENCE OF A PROBLEM, SUCH AS A HIGH RESISTANCE GROUND, SERIOUS DETERIORATION OF THE CIRCUIT INSULATION, LIGHTNING DAMAGE, BAD CONNECTIONS, BAD SPLICES, CABLE INSULATION DAMAGE, OR OTHER FAILURE. FAA ADVISORY CIRCULAR 150/5340-26C NOTES "GENERALLY SPEAKING, ANY CIRCUIT THAT MEASURES LESS THAN 1 MEGOHM IS CERTAINLY DESTINED FOR RAPID FAILURE." AIRFIELD LIGHTING SERIES CIRCUITS WITH CABLE INSULATION READINGS OF LESS THAN 1 MEGOHM ARE NOT UNCOMMON FOR OLDER CIRCUITS THAT ARE 20 YEARS OR MORE OF AGE.
- BASED ON INFORMATION IN FAA AC NO. 150/5340-26C MAINTENANCE OF AIRPORT VISUAL AID FACILITIES, THE CABLE INSULATION RESISTANCE VALUE INEVITABLY DECLINES OVER THE SERVICE LIFE OF THE CIRCUIT; A 10-20 PERCENT DECLINE PER YEAR MAY BE CONSIDERED NORMAL. IN THE EVENT THAT THE CABLE INSULATION RESISTANCE READINGS HAVE DECLINED MORE THAN 2 PERCENT PER MONTH IT MIGHT INDICATE CABLE DAMAGE DUE TO LIGHTNING OR DAMAGE AS A RESULT OF CONTRACTOR OPERATIONS. WHERE THE CABLE INSULATION RESISTANCE READINGS HAVE DECLINED MORE THAN 2 PERCENT PER MONTH OVER THE PROJECT CONSTRUCTION DURATION AS A RESULT OF CONTRACTOR OPERATIONS, CONTRACTOR WILL NEED TO INVESTIGATE, ADDRESS, AND REPAIR THE RESPECTIVE CABLE CIRCUITS.



SERIES CIRCUIT LOOP RESISTANCE MEASUREMENT NOTES

- PRIOR TO BEGINNING EXCAVATIONS, AIRFIELD LIGHTING MODIFICATIONS, CABLE INSTALLATION, AND/OR ANY OTHER WORK THAT MIGHT POSSIBLY AFFECT AIRFIELD LIGHTING CIRCUITS, THE RESPECTIVE SERIES CIRCUIT CABLE LOOPS SHALL HAVE THE RESISTANCE MEASURED WITH AN OHMMETER AND RECORDED FOR EACH CIRCUIT AT THE VAULT.
- AFTER AIRFIELD LIGHTING MODIFICATIONS, ADDITIONS, UPGRADES, AND/OR OTHER WORK AND ADDITIONS HAVE BEEN COMPLETED THE RESPECTIVE SERIES CIRCUIT CABLE LOOPS SHALL HAVE THE RESISTANCE MEASURED WITH AN OHMMETER AND RECORDED FOR EACH CIRCUIT AT THE VAULT.
- ALL EXISTING SERIES CIRCUIT CABLE LOOPS SHALL HAVE THE RESISTANCE MEASURED WITH AN OHMMETER AND RECORDED FOR EACH CIRCUIT AT THE VAULT. THE RESISTANCE OF THE SERIES CIRCUIT LOOP WITH CONNECTIONS USING #8 AWG COPPER CONDUCTOR SHOULD BE APPROXIMATELY 0.8 TO 1 OHM PER THOUSAND FEET OF CABLE LENGTH. THE RESISTANCE OF THE SERIES CIRCUIT LOOP WITH CONNECTIONS USING #6 AWG COPPER CONDUCTOR SHOULD BE APPROXIMATELY 0.5 TO 0.7 OHM PER THOUSAND FEET OF CABLE LENGTH. THE NUMBER OF SERIES CIRCUIT TRANSFORMERS AND CONNECTIONS WILL AFFECT THE OVERALL RESISTANCE OF THE SERIES CIRCUIT LOOP AND THEREFORE THE MEASUREMENTS MIGHT BE SLIGHTLY HIGHER THAN THE CALCULATED RESISTANCE FOR THE RESPECTIVE LENGTH OF CABLE.