

40' TYP TERMINAL HANGAR MILL AND REPLACE EXISTING PAVEMENT NEW 6" P.C.C. PAVEMENT (501) REMOVE P.C.C. PAVEMENT LIMITS (501900) NEW 6" CRUSHED AGGREGATE BASE COURSE (501) COMPACTED SUBGRADE


SECTION C - TYPICAL SECTIONS P.C.C. APRON AT TERMINAL BUILDING

12" SQ.

EXISTING TIE DOWN DETAIL

N.T.S.

FABRIC





NOTE: THE MOORING EYE SHALL BE INSTALLED AFTER PAVING OPERATIONS ARE COMPLETE.


MOORING EYE IN PAVEMENT DETAIL

MOORING NOTES

- MOORING CASTINGS SHALL BE NEENAH
 SEMI-STEEL AIRPORT MOORING EYE
 CATALOG NO. R3490 OR APPROVED
- ANCHOR RODS SHALL BE #3 DEFORMED REBAR, 15" LONG AND SHALL BE BENT DOWNWARD AT 45 DEGREES.
- 3. THE MOORING EYE SHALL BE INSTALLED AFTER PAVING OPERATIONS ARE COMPLETE BY CORING THROUGH NEW PAVEMENT.







EXISTING TIE DOWNS

ARE FILLED WITH GROUT

THIS BAR IS EQUAL TO 2 AT FULL SCALE (34X22). APRON **PARKING** TAYLORVILLE MUNICIPAL AIRPORT **AIRCRAFT** DETAIL ILLINOIS MISCELLANEOUS P **PORTION** NORTH REHABILITATE CONSULTING DESIGN BY: AJH CMT CBG CHECKED BY: CET APPROVED BY: JOB No: 13050-01 IL. PROJ. NO. TAZ-4342

ILE: TAZ-4342-CDT501.dwg JPDATE BY: Chris Groth PLOT DATE: 11/17/2014 5:00 PM

REVISIONS

BY

DATE

TA006

NUMBER

NOVEMBER 14, 201

SBG NO. 3-17-SBGP-XX

SHEET 11 OF 14 SHEETS