

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
9302	10-00049-00-PV	MONROE	27	1
FEDERAL AID PROJECT		ILLINOIS	CONTRACT NO. 97558	

INDEX OF SHEETS

SHEET NO.	ITEM
1	COVER SHEET
2	GENERAL NOTES & UTILITIES
3-4	SUMMARY OF QUANTITIES
5	TYPICAL SECTIONS
6-9	SCHEDULE OF QUANTITIES
10-13	PLAN SHEETS
14-26	CURB RAMP DETAILS
27	CONSTRUCTION DETAILS

PLANS FOR PROPOSED
CITY OF COLUMBIA
NORTH MAIN STREET RESURFACING – PHASE 1
FAU 9302
SECTION 10-00049-00-PV
MONROE COUNTY
PROJECT NO. M5011 (344)
JOB NO. C-98-366-11

HIGHWAY STANDARDS

000001-06	STANDARD SYMBOLS, ABBREVIATIONS AND PATTERNS
420001-08	PAVEMENT JOINTS
420701-02	PAVEMENT FABRIC
424001-08	PERPENDICULAR CURB RAMPS FOR SIDEWALKS
424011-02	CORNER PARALLEL CURB RAMPS FOR SIDEWALKS
442101-07	CLASS B PATCHES
604001-04	FRAME AND LIDS TYPE 1
604006-05	FRAME AND GRATE TYPE 3
606001-06	CONCRETE CURB TYPE B AND COMBINATION CONCRETE CURB AND GUTTER
701001-02	OFF-RD OPERATIONS, 2L, 2W, MORE THAN 15' (4.5 m) AWAY
701006-05	OFF-RD OPERATIONS, 2L, 2W 15' (4.5 m) TO 24' (600 mm) FROM PAVEMENT EDGE
701301-04	LANE CLOSURE, 2L, 2W, SHORT TIME OPERATIONS
701501-06	URBAN LANE CLOSURE, 2L, 2W, UNDIVIDED
701801-05	LANE CLOSURE MULTILANE 1W OR 2W CROSSWALK OR SIDEWALK CLOSURE
701901-04	TRAFFIC CONTROL DEVICES
720001-01	SIGN PANEL MOUNTING DETAILS
720006-04	SIGN PANEL ERECTION DETAILS
728001-01	TELESCOPING STEEL

GENERAL NOTES

UTILITIES

1. UNDERGROUND FACILITIES, STRUCTURES AND UTILITIES HAVE BEEN PLOTTED FROM AVAILABLE SURVEYS AND RECORDS. THEIR LOCATIONS MUST BE CONSIDERED TO BE APPROXIMATE ONLY. IT IS POSSIBLE THERE MAY BE OTHERS, THE EXISTENCE OF WHICH IS NOT PRESENTLY KNOWN OR SHOWN. IT IS THE CONTRACTOR'S RESPONSIBILITY TO DETERMINE THEIR EXISTENCE AND EXACT LOCATION AND TO AVOID DAMAGE THERETO. ILLINOIS LAW REQUIRES A MINIMUM 48-HOUR NOTICE TO ALL UTILITY COMPANIES BEFORE DIGGING. FIELD LOCATIONS OF UNDERGROUND FACILITIES MAY BE OBTAINED BY CALLING THE J.U.L.I.E. SYSTEM AT 800-892-0123 AND PROVIDING 48 HOURS ADVANCE NOTICE. NON-J.U.L.I.E MEMBERS MUST BE NOTIFIED INDIVIDUALLY. AGENCIES KNOWN TO HAVE FACILITIES WITHIN THE PROJECT LIMITS ARE LISTED BELOW.
2. ANY FACILITIES OR APPURTENANCES WHICH ARE THE PROPERTY OF ANY PUBLIC UTILITY LOCATED WITHIN THE LIMITS OF CONSTRUCTION SHALL BE RELOCATED OR ADJUSTED BY THEIR RESPECTIVE OWNERS. THE CONTRACTOR SHALL NOTIFY AND COOPERATE WITH THE OWNERS OF ANY SUCH FACILITY IN THEIR REMOVAL AND REARRANGEMENT OPERATIONS IN ORDER THAT THESE OPERATIONS AND THE CONSTRUCTION OF THIS PROJECT MAY PROGRESS IN A REASONABLE MANNER. ALL ROADSIDE OBJECTS (UTILITY POLES, FIRE HYDRANTS, SIGNS, ETC.) SHALL BE RELOCATED TO PROVIDE A MINIMUM OF 1.5 FEET CLEARANCE, MEASURED FROM THE FACE OF CURB TO THE NEAR EDGE OF THE OBJECT.
3. THE FOLLOWING UTILITY COMPANIES MAY HAVE FACILITIES LOCATED WITHIN THE LIMITS OF CONSTRUCTION WHICH MAY REQUIRE ADJUSTMENT, RELOCATION OR REMOVAL. ALL ARE MEMBERS OF J.U.L.I.E., UNLESS NOTED OTHERWISE.
- CHARTER COMMUNICATIONS (COMMUNICATIONS)
GARY WARREN
815 CHARTER COMMONS
TOWN & COUNTRY, MO 63017
(636) 387-6650
- HARRISONVILLE TELEPHONE COMPANY (TELEPHONE & COMMUNICATIONS)
THOMAS SCHRIEBER
213 SOUTH MAIN STREET
P.O. BOX 149
WATERLOO, IL 62298
(618) 939-6112
- AMEREN ILLINOIS (GAS & ELECTRIC)
DAVE SCHULTE
1050 WEST BOULEVARD
BELLEVILLE, IL 62222
(618) 234-3400
- CITY OF COLUMBIA (WATER & SEWER)
208 SOUTH RAPP AVENUE
COLUMBIA, IL62236
(618) 281-7144
4. THE PRECEDING UTILITY INFORMATION REPRESENTS THE BEST INFORMATION AVAILABLE TO THE LOCAL AGENCY AND IS ONLY INCLUDED FOR THE CONVENIENCE OF THE BIDDER. IT IS UNDERSTOOD AND AGREED THAT THE CONTRACTOR HAS TAKEN THE FOREGOING INTO CONSIDERATION IN PREPARING HIS/HER BID, AND NO ADDITIONAL COMPENSATION WILL BE ALLOWED FOR ANY DELAYS OR INCONVENIENCE CAUSED BY SAME.

GENERAL CONSTRUCTION

5. THE CONTRACTOR SHALL VERIFY ALL DIMENSIONS AND CONDITIONS IN THE FIELD PRIOR TO ORDERING MATERIALS AND COMMENCING CONSTRUCTION.
6. THE CONTRACTOR SHALL STAGE ALL WORK IN SUCH A WAY AS TO MAINTAIN INGRESS AND EGRESS TO ALL ABUTTING PROPERTIES AT ALL TIMES DURING CONSTRUCTION. AGGREGATE FOR TEMPORARY ACCESS WILL BE MEASURED FOR PAYMENT AS SPECIFIED IN THE CONTRACT. THE COST OF ALL OTHER MATERIALS REQUIRED AND ALL OTHER LABOR NECESSARY TO COMPLY WITH THIS PROVISION WILL NOT BE PAID FOR SEPARATELY, BUT SHALL BE CONSIDERED AS INCLUDED IN THE UNIT BID PRICES OF THE CONTRACT.
7. THE CONTRACTOR SHALL CONFINE ALL OPERATIONS TO THE CONSTRUCTION LIMITS LINE SHOWN ON THE PLANS. ANY AREA DISTURBED BEYOND THESE LIMITS SHALL BE RESTORED TO ITS ORIGINAL CONDITION AT THE CONTRACTOR'S EXPENSE.
8. THE CONTRACTOR SHALL FERTILIZE, SEED, AND MULCH ALL EARTH SURFACES DISTURBED BY CONSTRUCTION. THIS WORK WILL NOT BE PAID FOR SEPARATELY, BUT

SI	SP	CODE NO.	ITEM	UNIT	TOTAL QUANTITY
	•	20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	100
		35100300	AGGREGATE BASE COURSE, TYPE A 4"	SO YD	557
		40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	100
		40600275	BITUMINOUS MATERIALS (PRIME COAT)	POUND	7,030
		40600990	TEMPORARY RAMP	SO YD	60
		40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	1,750
	•	40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	14
		42000200	PORTLAND CEMENT CONCRETE PAVEMENT 7"	SO YD	305
		42400300	PORTLAND CEMENT CONCRETE SIDEWALK 6 INCH	SO FT	3,130
	•	42400800	DETECTABLE WARNINGS	SO FT	290
	•	44000100	PAVEMENT REMOVAL	SO YD	350
	•	44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SO YD	15,630
		44000600	SIDEWALK REMOVAL	SO FT	2,840
	•	44200919	CLASS B PATCHES, TYPE II, 7 INCH	SO YD	44

SI	SP	CODE NO.	ITEM	UNIT	TOTAL QUANTITY
	•	44200924	CLASS B PATCHES, TYPE III, 7 INCH	SO YD	67
				</	

