

SPECIALTY ITEM	CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY	ROADWAY	BRIDGE SN 016-0090	TRAFFIC SIGNS	SURVEILLANCE
					90% FED 10% STATE	90% FED 10% STATE	90% FED 10% STATE	90% FED 10% STATE
					CONSTRUCTION TYPE CODE			
					I000-2A	X071-2A	Y002-1C	Y032-1F
**	20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	811	811			
**	20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	51	51			
**	20101300	TREE PRUNING (1 TO 10 INCH DIAMETER)	EACH	10	10			
**	20101350	TREE PRUNING (OVER 10 INCH DIAMETER)	EACH	12	12			
	28000510	INLET FILTERS	EACH	381	381			
**	40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	297	297			
	40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	208	208			
	40600300	AGGREGATE (PRIME COAT)	TON	1,038	1,038			
	40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGWAYS	TON	389	389			
	40600895	CONSTRUCTING TEST STRIP	EACH	2	2			
	40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	2,600	2,600			
	40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	2,831	2,831			
	40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	6,015	6,015			
	40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	4,010	4,010			
**	40800052	INCIDENTAL HOT-MIX ASPHALT SURFACING (SPECIAL)	TON	119	119			
	42001300	PROTECTIVE COAT	SQ YD	600	600			
	44000162	HOT-MIX ASPHALT SURFACE REMOVAL, 3 1/4"	SQ YD	20,238	20,238			
	44000164	HOT-MIX ASPHALT SURFACE REMOVAL, 3 3/4"	SQ YD	59,086	59,086			
	44000165	HOT-MIX ASPHALT SURFACE REMOVAL, 4"	SQ YD	180,224	180,224			
	44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	410	410			
	44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	31	31			
	44002213	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 3 1/4"	SQ YD	810	810			
	44002216	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 4"	SQ YD	10,648	10,648			
**	44004260	PAVED SHOULDER REMOVAL (SPECIAL)	SQ YD	530	530			
	44200549	CLASS A PATCHES, TYPE I, 10 INCH	SQ YD	300	300			
	44200553	CLASS A PATCHES, TYPE II, 10 INCH	SQ YD	300	300			
	44201761	CLASS D PATCHES, TYPE I, 10 INCH	SQ YD	87	87			
	44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	4,742	4,742			
	44201769	CLASS D PATCHES, TYPE III, 10 INCH	SQ YD	1,770	1,770			
	44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SQ YD	4,859	4,859			
	44213000	PATCHING REINFORCEMENT	SQ YD	600	600			
	44213200	SAW CUTS	FOOT	294	294			
Δ	55039700	STORM SEWERS TO BE CLEANED	FOOT	9144	9,144			
	58700300	CONCRETE SEALER	SQ FT	29,427		29,427		
	60300205	FRAMES AND GRATES TO BE ADJUSTED (SPECIAL)	EACH	235	235			

Δ NON-PARTICIPATING  
• SPECIALTY ITEMS  
\*\* FOR LOCATIONS AND EXTENT OF WORK NOT SHOWN IN THE PLANS, THE CONTRACTOR SHALL COORDINATE WITH THE ENGINEER AND CONTACT RICK WANNER, ROADSIDE DEVELOPMENT ARCHITECT, IDOT ROADSIDE DEVELOPMENT UNIT AT (847) 705-4172 AT LEAST 72 HOURS PRIOR TO STARTING WORK.

FILE NAME =	DESIGNED - AJP	REVISED -	<b>benesch</b>	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>			F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
#FILE#	DRAWN - TMB	REVISED -						290	(3131, ETC., 3435)RS-6	COOK	215	3
USER NAME = #USER#	CHECKED - JMM	REVISED -			SCALE: N.T.S. SHEET NO. 1 OF 4 SHEETS STA. TO STA.			CONTRACT NO. 60K10				
PLOT DATE = #DATE#	DATE - 1/25/10	REVISED -						FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				