SIGN DETAIL

1:75

EB-BM-83
STA. 769+75

SIGN NUMBER	name
WIDTH x HGHT.	19'-6" x 9'-6"
BORDER WIDTH	2"
CORNER RADIUS	12"
MOUNTING	Overhead
BACKGROUND	TYPE: Reflective
	COLOR: Green
LEGEND/BORDER	TYPE: Reflective
	COLOR: White/White

SYMBOL	ROT	X	Y	WID	HT
M1-1100A-2-22-1000		125.7	38.5	39.3	36
ARMED	135	21	23.7	20	31.5

Panel Style: sign_default.ssi
Dimensions are in inches.tenths

Letter locations are panel edge to lower left corner

LETTER POSITIONS (X)

																																				LENGTH	SERIES/SIZE
L	E	F	T																																				ClearviewHwy-5-W
18	28.8	40.5	50.6																																			41.2	12
E	X	I	T	2	1	B																																	ClearviewHwy-5-W
70.1	80.4	94.1	100	118.6	132.8	145.5																																86.8	12,15
H	a	r	l	e	m		A	v	e																														ClearviewHwy-5-W-R
68.5	85.1	101	112	120.3	136.5	154.5	170	186.6	201.3																													144.5	16/13

FILE NAME =	DESIGNED - SEW	REVISED -
$FILEL$	DRAWN - SEW	REVISED -
USER NAME = $USER$	CHECKED - FML	REVISED -
PLOT DATE = $DATE$	DATE - 1/25/10	REVISED -

LIN ENGINEERING,LTD.
Consulting Engineers
Chatham, Illinois Westmont, Illinois

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SIGNING DETAILS

SCALE: N.T.S. | SHEET NO. 10 OF 34 SHEETS | STA. | TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
290	(3131, ETC., 3435) RS-6	COOK	215	142
		CONTRACT NO. 60K10		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		