


STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION



PLAN



SILICONE JOINT SEALER DETAIL



SILICONE JOINT SEALER TREATMENT AT PARAPET

DESIGNED - DMS CHECKED - EFS DRAWN - RMG CHECKED - KJN



Stage III Note:

Bridge deck and approach slab repairs between Stage I and Stage II construction lines shall be performed over a weekend using IDOT District I Std. TC-25 Center Lane Closure. See Maintenance of Traffic Plans. Concrete for Stage III patching shall be Class PP-2.

BILL OF MATERIAL

Symbol	Item	Unit	Quantity	
	Deck Slab Repair (Partial)	Sq. Yd.	10.0	
	Approach Slab Repair (Partial Depth)	Sq. Yd.	49.0	
	Silicone Joint Sealer	Foot	199.5	

Notes:

- Deck and approach slab repair areas are estimated based on visual inspection completed in June 2009. Actual repair areas and locations shall be determined by the Engineer and shown on As-Built plans.
- Deck drains (downspouts, floor drains and scuppers) shall be cleaned with the bridge deck prior to application of the Concrete Sealer. Cost of cleaning the deck drains is included with Concrete Sealer.
- 3. The construction joint between the approach slab and backwall closure pour, adjacent to the existing preformed joint seal, shall be cleaned and sealed with hot-poured joint sealer according to Section 452 of the Std. Specifications. Cost included with "Concrete Sealer".
- 4. Cost of Removal of existing preformed joint seal is included with Silicone Joint Sealer

BRIDGE DECK AND APPROACH SLAB REPAIRS STRUCTURE NO. 016-0090

				_ =			010 0000		
SHEET NO. 4		F.A.I. RTE.	SECTION				COUNTY	TOTAL SHEETS	SHEET NO.
		290	(3131, ETC., 3435)RS-6			СООК	215	172	
5	SHEETS						CONTRACT	NO. 60	K10
		FED. RO	DAD DIST.	NO.	ILLINOIS	FED.	AID PROJECT		