

CONTRACT 60K11  
RESURFACING SCHEDULE

LOCATION					POLYMERIZED HMA SURFACE COURSE, SMA, N80	POLYMERIZED HMA BINDER COURSE, SMA, N80	HMA SURFACE COURSE, MIX D, N70	HMA BINDER COURSE, IL-19.0, N70	HMA SURFACE REMOVAL, 3-1/4"	HMA SURFACE REMOVAL, 3-3/4"	HMA SURFACE REMOVAL, 4"
ALIGNMENT	DIRECTION	DESCRIPTION	STATION	STATION	(TON)	(TON)	(TON)	(TON)	(SQ YD)	(SQ YD)	(SQ YD)
290	EB	OUTSIDE SHLDR	1058+43	1083+10			114	171		1,353	
290	EB	MAINLINE	1058+47	1116+50	3,259	2,704					24,140
290	WB	OUTSIDE SHLDR	1058+87	1079+97			83	125		999	
290	WB	MAINLINE	1059+29	1116+25	3,245	2,692					24,035
290	WB	RAMP/AUXILLARY	1079+97	1088+20			169	254		2,013	
290	WB	RAMP	1081+14	1086+88			86	129	1,023		
290	EB	RAMP	1081+55	1086+44			85	127	1,010		
290	EB	RAMP/AUXILLARY	1083+10	1087+76			111	167		1,326	
290	EB	RAMP/AUXILLARY	1087+76	1094+75			329	494		3,920	
290	WB	RAMP/AUXILLARY	1088+20	1095+16			287	430		3,414	
290	EB	RAMP/AUXILLARY	1094+75	1103+41			190	285		2,265	
290	WB	RAMP/AUXILLARY	1095+16	1099+91			117	176		1,397	
290	EB	RAMP	1096+03	1100+66			71	107	850		
290	WB	RAMP	1096+68	1100+79			74	111	880		
290	WB	OUTSIDE SHLDR	1099+91	1116+25			215	322		2,557	
290	EB	OUTSIDE SHLDR	1103+41	1116+50			137	205		1,627	
290	EB	RAMP	1113+76	1116+50			47	71	562		
290	WB	RAMP	1114+34	1116+25			46	69	549		
290	WB	MAINLINE	1116+25	1146+18	2,172	1,802					16,091
290	WB	RAMP/AUXILLARY	1116+25	1126+37			257	385		3,059	
290	EB	MAINLINE	1116+50	1144+66	2,046	1,698					15,157
290	EB	RAMP/AUXILLARY	1116+50	1124+96			194	290		2,305	
290	EB	OUTSIDE SHLDR	1124+96	1136+66			136	204		1,622	
290	WB	OUTSIDE SHLDR	1127+01	1137+67			109	164		1,301	
290	EB	RAMP	1133+50	1136+66			50	75	597		
290	WB	RAMP	1134+76	1137+67			44	66	522		
290	EB	RAMP/AUXILLARY	1136+66	1144+65			238	357		2,832	
290	WB	RAMP/AUXILLARY	1137+67	1145+70			260	389		3,091	
290	EB	OUTSIDE SHLDR	1144+65	1164+87			206	309		2,450	
290	EB	RAMP	1144+65	1148+25			61	91	720		
290	EB	MAINLINE	1144+66	1197+50	3,866	3,208					28,639
290	WB	OUTSIDE SHLDR	1145+70	1166+13			217	325		2,579	
290	WB	RAMP	1145+70	1148+73			51	76	604		
290	WB	MAINLINE	1146+18	1197+80	3,776	3,133					27,973
290	EB	RAMP	1161+03	1164+87			76	114	907		
290	WB	RAMP	1162+51	1165+13			76	114	903		
290	EB	RAMP/AUXILLARY	1164+87	1174+28			303	455		3,608	
290	WB	RAMP/AUXILLARY	1165+13	1178+02			392	588		4,665	
290	EB	OUTSIDE SHLDR	1174+28	1195+98			182	273		2,171	
290	EB	RAMP	1174+28	1178+25			90	134	1,067		
290	WB	OUTSIDE SHLDR	1178+02	1202+31			266	399		3,167	
290	WB	RAMP	1178+02	1182+30			72	108	859		
290	EB	RAMP/AUXILLARY	1195+98	1206+74			168	253		2,005	
290	EB	MAINLINE	1197+50	1203+84	458	380					3,390
290	WB	MAINLINE	1197+80	1207+50	647	537					4,791
290	WB	RAMP	1199+20	1202+31			62	93	741		
290	WB	RAMP/AUXILLARY	1202+31	1210+57			466	699		5,547	
290	EB	MAINLINE	1203+84	1214+90	606	503					4,492
290	EB	RAMP/AUXILLARY	1206+74	1209+10			36	54		425	
290	EB	RAMP	1206+74	1214+70			385	577	4,582		
290	WB	MAINLINE	1207+50	1215+15	420	349					3,113
290	WB	RAMP	1209+09	1214+33			223	335	2,657		
290	EB	OUTSIDE SHLDR	1209+10	1214+90			111	167		1,325	
290	WB	OUTSIDE SHLDR	1210+57	1215+15			97	146		1,158	
<b>TOTAL</b>					20,496	17,004	6,990	10,485	19,035	64,181	151,821

FILE NAME =	DESIGNED - AJP	REVISED -
...prpIn_ABC.C3_sch_01.dgn	DRAWN - TMB	REVISED -
USER NAME = jmcjwsk	CHECKED - JMM	REVISED -
PLOT DATE = 1/25/2018	DATE - 1/25/10	REVISED -

**benesch**

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**SCHEDULE OF QUANTITIES**

SCALE: N.T.S. SHEET NO. 1 OF 3 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
290	(2525, ETC., 2727)RS-8	COOK	201	12
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT			CONTRACT NO. 60K11	