

CONTRACT 60K11
RUMBLE STRIP SCHEDULE

I-290 WESTBOUND - INSIDE SHOULDER			
STATION TO STATION		RUMBLE STRIP LENGTH	SHOULDER SURFACE TYPE
START	END	(FOOT)	
1072+00	1214+96	14,310	CONCRETE

TOTAL	14,310
-------	--------

CONTRACT 60K11
RUMBLE STRIP SCHEDULE

I-290 WESTBOUND - OUTSIDE SHOULDER			
STATION TO STATION		RUMBLE STRIP LENGTH	SHOULDER SURFACE TYPE
START	END	(FOOT)	
1072+00	1079+89	800	HMA
1088+11	1095+07	696	HMA
1099+82	1116+82	1,636	HMA
1126+27	1137+58	1,129	HMA
1145+61	1166+05	2,045	HMA
1177+89	1202+11	2,430	HMA
1210+55	1215+00	442	HMA

TOTAL	9,178
-------	-------

CONTRACT 60K11
RUMBLE STRIP SCHEDULE

I-290 EASTBOUND - INSIDE SHOULDER			
STATION TO STATION		RUMBLE STRIP LENGTH	SHOULDER SURFACE TYPE
START	END	(FOOT)	
1072+00	1214+90	14,293	CONCRETE

TOTAL	14,293
-------	--------

CONTRACT 60K11
RUMBLE STRIP SCHEDULE

I-290 EASTBOUND - OUTSIDE SHOULDER			
STATION TO STATION		RUMBLE STRIP LENGTH	SHOULDER SURFACE TYPE
START	END	(FOOT)	
1072+00	1083+10	1,108	HMA
1087+76	1095+33	758	HMA
1103+41	1116+50	1,308	HMA
1124+96	1136+66	1,170	HMA
1144+66	1164+87	2,022	HMA
1174+28	1176+52	2,168	HMA
1209+10	1214+90	581	HMA

TOTAL	9,115
-------	-------

FILE NAME =	DESIGNED - AJP	REVISED -
...\\pripin-ABC_C3_sch_02.dgn	DRAWN - TMB	REVISED -
USER NAME = jnojewski	CHECKED - JMM	REVISED -
PLOT DATE = 1/25/2010	DATE - 1/25/10	REVISED -

benesch

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SCHEDULE OF QUANTITIES

SCALE: N.T.S. SHEET NO. 2 OF 3 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
290	(2525, ETC., 2727)RS-8	COOK	201	13
			CONTRACT NO. 60K11	
FED. ROAD DIST. NO. [ILLINOIS] FED. AID PROJECT				