


EASTBOUND SIGN SCHEDULE

SIGN NO.	STATION	LEGEND/DESCRIPTION	EXISTING PANEL DIMENSIONS		PROPOSED PANEL DIMENSIONS		REMOVE SIGN	REMOVE SIGN	REMOVE SIGN	REMOVE SIGN	REMOVE SIGN	REMOVE SIGN	SIGN PANEL	SIGN PANEL	SIGN PANEL	WOOD SIGN	TELESCOPING	REMOVAL OF	
			WIDTH (FT)	HEIGHT (FT)	WIDTH (FT)	HEIGHT (FT)	PANEL-TYPE 1	PANEL-TYPE 2	PANEL-TYPE 3	ASSEMBLY - TYPE A	ASSEMBLY - TYPE B	TYPE 1	TYPE 2	TYPE 3	SUPPORT (FOOT)	STEEL SIGN SUPPORT (FOOT)	LIGHTING UNIT, NO SALVAGE (EACH)		
EB-BM-108C	1077+65	CALIFORNIA AVE - 2800 W	9.1	2.5	9.1	2.5		22.8						22.8					
EB-CL-109	1083+10	EXIT 27C - WESTERN AVE - 2400 W	20.0	7.5	20.0	7.5			150.0						150.0			1.0	
EB-PM-109A	1083+10	W13-3 (30 MPH)	3.0	4.0	4.0	5.0		12.0					20.0						
EB-WP-109B	1085+67	W4-1R	4.0	4.0	4.0	4.0							1.0	16.0	18.0				
EB-WP-110	1088+00	EXIT - 27C	7.5	5.0	7.0	5.0							1.0		35.0	36.0			
EB-WP-110A	1095+31	W4-1R	4.0	4.0	4.0	4.0							1.0	16.0	18.0				
EB-WP-110B	1096+00	W13-3 (30 MPH)	3.0	4.0	4.0	5.0							1.0	20.0	18.0				
EB-BM-110C	1090+79	14 FT 3 IN	5.5	1.5	5.5	1.5	8.3					8.3							
EB-WP-111	1096+90	EXIT	6.0	5.0	6.0	5.0							1.0		30.0	36.0			
EB-PM-111A	1103+91	R2-1 (55 MPH)	4.0	5.0	4.0	5.0		20.0						20.0					
EB-BM-112	1104+40	EXIT 28B - PAULINA ST-ASHLAND AVE - 3/4 MILE	32.0	7.5	32.0	7.5			240.0						240.0			1.0	
EB-BM-113	1104+40	EXIT 28A - DAMEN AVE - 1/4 MILE	15.5	7.5	15.5	7.5			116.3						116.3			1.0	
EB-BM-113A	1104+40	WESTERN AVE - 2400 W	8.3	2.5	8.3	2.5		20.8					20.8						
EB-TS-113B1	1106+90	M3-2	2.5	1.3	2.5	1.3				1.0		3.1					18.0		
EB-TS-113B2	1106+90	M1-1-3 (I 290)								1.0		9.0							
EB-BM-113C	1111+26	OAKLEY BLVD - 2300 W	8.0	2.5	8.0	2.5		20.0						20.0					
EB-WP-113D	1115+92	W4-1R	4.0	4.0	4.0	4.0							1.0	16.0	18.0				
EB-TS-113E	1117+95	LEAVITT ST - 2200 W	6.6	2.5	6.6	2.5							1.0	16.5			18.0		
EB-BM-114	1118+00	EXIT 29A - RACINE AVE - 1 MILE	15.5	8.0	15.5	8.0			124.0						124.0			1.0	
EB-BM-115	1118+00	EXIT 28B - PAULINA ST-ASHLAND AVE - 1/2 MILE	32.0	8.0	32.0	8.0			256.0						256.0			1.0	
EB-BM-116	1118+00	EXIT 28A - DAMEN AVE - 2000 W	19.0	8.0	19.0	8.0			152.0						152.0			1.0	
EB-PM-116A	1123+31	W13-3 (30 MPH)	3.0	4.0	4.0	5.0		12.0					20.0						
EB-WP-117	1125+50	EXIT - 28A	7.5	5.0	7.0	5.0							1.0		35.0	36.0			
EB-PM-117A	1127+98	TRUCKS - USE - 2 - RIGHT - LANES	4.0	5.0	4.0	5.0		20.0						20.0					
EB-GM-118	1130+50	ILLINOIS MED DISTRICT - UNIV OF ILL MED CENTER - RUSH UNIVERSITY - EXIT 28B	19.0	9.0	19.0	9.0			171.0						171.0				
EB-BM-118A	1131+11	DAMEN AVE - 2000 W	7.5	2.5	7.5	2.5		18.8						18.8					
EB-WP-118B	1136+11	W4-1R	4.0	4.0	4.0	4.0							1.0	16.0	18.0				
EB-CL-119	1138+50	EXIT 28B - PAULINA ST 1700 W - ASHLAND AVE 1600 W	31.5	8.5	31.5	8.5			267.8						267.8			1.0	
EB-BM-119A	1139+45	OGDEN AVE - 1850 W	7.3	2.5	7.3	2.5		18.3						18.3					
EB-WP-119B	1144+14	W13-3 (30 MPH)	3.0	4.0	4.0	5.0							1.0	20.0	18.0				
EB-WP-120	1145+20	EXIT - 28B	7.5	5.0	7.0	5.0							1.0		35.0	36.0			
EB-PM-120A	1148+73	END - TRUCK - LANE - RESTRICTIONS	4.0	5.0	4.0	5.0		20.0					20.0						
EB-GM-121	1149+50	UNIVERSITY - OF ILLINOIS - AT CHICAGO - EXIT 29A	13.0	10.0	13.0	10.0			130.0						130.0				
EB-BM-122	1151+20	90 94 KENNEDY EXPY RYAN EXPY - WISCONSIN - INDIANA - 1 MILE	25.0	11.0	25.0	11.0			275.0						275.0			1.0	
EB-BM-123	1151+20	EXIT 29A - RACINE AVE - 1/2 MILE	15.5	8.0	15.5	8.0			124.0						124.0			1.0	
EB-BM-123A	1151+20	PAULINA ST - 1700 W	7.0	2.5	7.0	2.5		17.5						17.5					
EB-BM-123B	1157+93	ASHLAND BLVD - 1600 W	8.6	2.5	8.6	2.5		21.5						21.5					
EB-WP-123C	1163+84	W4-1R	4.0	4.0	4.0	4.0							1.0	16.0	18.0				
EB-PM-123D1	1167+46	SPEED - ZONE - AHEAD	3.0	4.0	3.0	4.0		12.0						12.0					
EB-PM-123D2	1167+46	W13-1 (45 MPH)	2.0	2.0	2.0	2.0	4.0					4.0							
EB-BM-124	1170+30	EXIT 29A - RACINE AVE - 1200 W	19.5	7.5	19.5	7.5			146.3						146.3			1.0	
EB-BM-124A	1170+30	LOOMIS ST - 1400 W	6.8	2.5	6.8	2.5		16.9						16.9					
EB-PM-124B	1174+20	W13-3 (30 MPH)	3.0	4.0	4.0	5.0		12.0						20.0					
EB-WP-125	1175+20	EXIT - 29A	7.5	5.0	7.0	5.0							1.0		35.0	36.0			
EB-TS-125B1	1178+98	SPEED - ZONE - AHEAD	3.0	4.0	3.0	4.0							1.0					18.0	
EB-TS-125B2	1178+98	W13-1 (45 MPH)	2.0	2.0	2.0	2.0				1.0		4.0			12.0				
EB-PM-125A1	1178+98	SPEED - ZONE - AHEAD	3.0	4.0	3.0	4.0		12.0						12.0					
EB-PM-125A2	1178+98	W13-1 (45 MPH)	2.0	2.0	2.0	2.0	4.0					4.0							
EB-WP-125C	1184+00	R2-1 (45 MPH)	4.0	5.0	4.0	5.0							1.0		20.0	18.0			
EB-PM-125D	1184+00	R2-1 (45 MPH)	4.0	5.0	4.0	5.0		20.0						20.0					
EB-BM-126	1184+20	CONGRESS PKWY - CHICAGO LOOP	19.0	9.0	19.0	9.0			171.0						171.0			1.0	
EB-BM-127	1184+20	90 94 WEST KENNEDY EXPY - WISCONSIN	17.5	11.5	17.5	11.5			201.3						201.3			1.0	
EB-BM-128	1184+20	90 94 EAST RYAN EXPY - INDIANA	15.5	11.5	15.5	11.5			178.3						178.3			1.0	
EB-BM-128A	1184+20	RACINE AVE - 1200 W	7.4	2.5	7.4	2.5		18.6						18.6					
EB-BM-128B	1198+41	MORGAN ST - 1000 W	7.0	2.5	7.0	2.5		17.5						17.5					
EB-BM-129	1204+80	90 94 WEST KENNEDY EXPY - WISCONSIN	15.5	10.5	16.5	10.5			162.8						173.3			1.0	
EB-BM-130	1204+80	90 94 EAST RYAN EXPY - INDIANA	17.0	11.0	17.0	11.0			187.0						187.0			1.0	
EB-BM-130A	1204+80	PEORIA ST - 900 W	6.4	2.5	6.4	2.5		16.1						16.1					
EB-TR-131	1208+20	CONGRESS PKWY - CHICAGO LOOP	30.0	9.5	30.0	9.5			285.0						285.0			1.0	
EB-TR-132	1208+20	90 94 WEST KENNEDY EXPY - WISCONSIN	16.5	10.5	16.5	10.5			173.3						173.3			1.0	
EB-TR-133	1208+20	90 94 EAST RYAN EXPY - INDIANA	17.0	11.0	17.0	11.0			187.0						187.0			1.0	
EB-PM-133A	1208+20	R2-1 (45 MPH)	4.0	5.0	4.0	5.0		20.0						20.0					
EB-TS-133B	1210+38	R2-1 (45 MPH)	4.0	5.0	4.0	5.0							1.0		20.0			18.0	
EB-TR-134	1210+50	90 94 WEST KENNEDY EXPY - WISCONSIN	15.5	10.5	16.5	10.5			162.8						173.3			1.0	
EB-TR-135	1210+50	90 94 EAST RYAN EXPY - INDIANA	17.0	11.0	17.0	11.0			187.0						187.0			1.0	
EB-BM-136	1211+18	LANES SPLIT	4.0	4.0	4.0	4.0		16.0						16.0					
EB-BM-137	1211+18	HALSTED ST - 800 W	7.0	2.5	7.0	2.5			17.5					17.5					
EASTBOUND SUBTOTAL							17	403	4048	3	16	33	615	4239	324	72	20		

*EXISTING SIGN DIMENSIONS NOT AVAILABLE; PROPOSED SIGN DIMENSIONS USED

FILE NAME =	DESIGNED - SEW	REVISED -	 LIN ENGINEERING, LTD. Consulting Engineers Chatham, Illinois Westmont, Illinois	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES			F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
FILEL	DRAWN - SEW	REVISED -						290	(2525, ETC., 2727) RS-8	COOK	201	15
USER NAME = #USER*	CHECKED - FML	REVISED -			SCALE: N.T.S. SHEET NO. 1 OF 3 SHEETS STA. TO STA.			CONTRACT NO. 60K11				
PLOT DATE = #DATE*	DATE - 1/25/10	REVISED -						FED. ROAD DIST. NO. [ILLINOIS] FED. AID PROJECT				