


WESTBOUND SIGN SCHEDULE

SIGN NO.	STATION	LEGEND/DESCRIPTION	EXISTING PANEL DIMENSIONS		PROPOSED PANEL DIMENSIONS		REMOVE SIGN PANEL-TYPE 1 (SQ FT)	REMOVE SIGN PANEL-TYPE 2 (SQ FT)	REMOVE SIGN PANEL-TYPE 3 (SQ FT)	REMOVE SIGN PANEL ASSEMBLY - TYPE A EACH	REMOVE SIGN PANEL ASSEMBLY - TYPE B EACH	SIGN PANEL TYPE 1 (SQ FT)	SIGN PANEL TYPE 2 (SQ FT)	SIGN PANEL TYPE 3 (SQ FT)	WOOD SIGN SUPPORT (FOOT)	TELESCOPING STEEL SIGN SUPPORT (FOOT)	REMOVAL OF LIGHTING UNIT, NO SALVAGE (EACH)
			WIDTH (FT)	HEIGHT (FT)	WIDTH (FT)	HEIGHT (FT)											
WB-BM-124	1078+70	EXIT 26A - INDEPENDENCE BLVD - 1 MILE	23.5	8.5	23.5	8.5			199.8					199.8			1.0
WB-BM-125	1078+70	EXIT 26B - HOMAN AVE - 1/2 MILE	15.5	8.5	15.5	8.5			131.8					131.8			1.0
WB-BM-125A	1078+70	CALIFORNIA AVE - 2800 W	9.1	2.5	9.1	2.5		22.8				22.8					
WB-PM-125B	1079+39	TRUCKS - USE - RIGHT - 2 - LANES	4.0	5.0	4.0	5.0		20.0				20.0					
WB-TS-125C	1079+39	TRUCKS - USE - RIGHT - 2 - LANES	4.0	5.0	4.0	5.0						20.0					
WB-WP-126	1085+40	EXIT	6.0	5.0	6.0	5.0				1.0		20.0		30.0	36.0	18.0	
WB-TS-126A	1088+30	W4-1R	4.0	4.0	4.0	4.0				1.0		16.0				18.0	
WB-WP-127	1094+90	EXIT - 27B	7.5	5.0	7.0	5.0				1.0				35.0	36.0		
WB-TS-127A	1096+87	W4-1R	4.0	4.0	4.0	4.0				1.0		16.0				18.0	
WB-CL-128	1100+00	EXIT 27B - CALIFORNIA AVE - 2800 W	23.0	7.5	23.0	7.5			172.5					172.5			1.0
WB-TS-128A	1100+00	W13-3 (30 MPH)	3.0	4.0	4.0	5.0				1.0		20.0				18.0	
WB-BM-128B	1105+86	WESTERN AVE - 2400 W	8.3	2.5	8.3	2.5		20.8				20.8					
WB-BM-128C	1112+21	OAKLEY BLVD - 2300 W	8.0	2.5	8.0	2.5		20.0				20.0					
WB-WP-129	1115+80	EXIT - 27C	7.5	5.0	7.0	5.0				1.0				35.0	36.0		
WB-PM-129A	1117+00	W13-3 (30 MPH)	3.0	4.0	4.0	5.0		12.0				20.0					
WB-BM-130	1118+70	EXIT 26B - HOMAN AVE - 1 1/4 MILES	15.5	8.5	15.5	8.5			131.8					131.8			1.0
WB-BM-131	1118+70	EXIT 27B - CALIFORNIA AVE - 1/4 MILE	19.0	8.0	19.0	8.0			152.0					152.0			1.0
WB-BM-132	1118+70	EXIT 27C - OAKLEY BLVD 2300 W - WESTERN AVE 2400 W	21.5	11.5	21.5	11.5			247.3					247.3			1.0
WB-BM-132A	1118+70	LEAVITT ST - 2200 W	6.6	2.5	6.6	2.5		16.5				16.5					
WB-PM-132B1	1120+80	M3-4	2.5	1.3	2.5	1.3		3.1				3.1					
WB-PM-132B2	1120+80	M1-1-3 (I 290)	PER MUTCD	STD (9FT?)	PER MUTCD	STD (9FT?)		9.0				9.0					
WB-TS-132C	1127+29	W4-1R								1.0		16.0				18.0	
WB-BM-133	1132+20	EXIT 27B - CALIFORNIA AVE - 1/2 MILE							152.0					152.0			1.0
WB-BM-134	1132+20	EXIT 27C - OAKLEY BLVD-WESTERN AVE - 1/4 MILE							264.0					264.0			1.0
WB-BM-134A	1132+20	DAMEN AVE - 2000 W						18.8				18.8					
AB-PM-134B	1134+51	TRUCKS - USE - RIGHT - 2 - LANES						20.0				20.0					
WB-TS-134C	1136+18	R2-1 (55 MPH)								1.0		20.0				18.0	
WB-WP-135	1137+50	EXIT - 28A								1.0				35.0	36.0		
WB-PM-135A	1138+32	W13-3 (30 MPH)						12.0				20.0					
WB-BM-135B	1142+93	OGDEN AVE - 1850 W						18.3				18.3					
WB-CL-136	1144+00	EXIT 28A - DAMEN AVE - 2000 W							152.0					152.0			1.0
WB-WP-136A	1146+34	W4-1R								1.0		16.0			18.0		
WB-BM-136B	1152+29	PAULINA ST - 1700 W						17.5				17.5					
WB-BM-137	1159+20	EXIT 27C - OAKLEY BLVD-WESTERN AVE - 3/4 MILE							280.5					280.5			1.0
WB-BM-138	1159+20	EXIT 28A - DAMEN AVE - 1/4 MILE							120.0					120.0			1.0
WB-BM-138A	1159+20	ASHLAND BLVD - 1600 W						21.5				21.5					
WB-WP-139	1165+50	EXIT - 28B								1.0				35.0	36.0		
WB-PM-139A	1166+30	W13-3 (30 MPH)						12.0				20.0					
WB-BM-140	1172+00	EXIT 28B - ASHLAND BLVD 1600 W - PAULINA ST 1700 W							267.8					267.8			1.0
WB-BM-140A	1172+00	LOOMIS ST - 1400 W						16.9				16.9					
WB-TS-140B	1178+75	W4-1R										16.0				18.0	
WB-GM-141	1183+00	ILLINOIS MED DISTRICT - UNIV OF ILL MED CENTER - RUSH UNIVERSITY - EXIT 28B							171.0					171.0			
WB-BM-141A	1185+38	RACINE AVE - 1200 W										18.5					

\*EXISTING SIGN DIMENSIONS NOT AVAILABLE; PROPOSED SIGN DIMENSIONS USED

FILE NAME =	DESIGNED - SEW	REVISED -	 <p>LIN ENGINEERING LTD. Consulting Engineers Chattanooga, Illinois Westmont, Illinois</p>	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION				SCHEDULE OF QUANTITIES				F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
USER NAME = #USER#	DRAWN - SEW	REVISED -						290	(2525, ETC., 2727) RS-8	COOK	201	16				
USER NAME = #USER#	CHECKED - FML	REVISED -		SCALE: N.T.S.				SHEET NO. 2 OF 3 SHEETS			STA.	TO STA.		CONTRACT NO. 60K11		
PLOT DATE = #DATE#	DATE - 1/25/10	REVISED -		FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT												