


WESTBOUND SIGN SCHEDULE (CONTINUED)			EXISTING PANEL DIMENSIONS		PROPOSED PANEL DIMENSIONS		REMOVE SIGN PANEL-TYPE 1	REMOVE SIGN PANEL-TYPE 2	REMOVE SIGN PANEL-TYPE 3	REMOVE SIGN PANEL ASSEMBLY - TYPE A	REMOVE SIGN PANEL ASSEMBLY - TYPE B	SIGN PANEL TYPE 1	SIGN PANEL TYPE 2	SIGN PANEL TYPE 3	WOOD SIGN SUPPORT	TELESCOPING STEEL SIGN SUPPORT	REMOVAL OF LIGHTING UNIT, NO SALVAGE
SIGN NO.	STATION	LEGEND/DESCRIPTION	WIDTH (FT)	HEIGHT (FT)	WIDTH (FT)	HEIGHT (FT)	(SQ FT)	(SQ FT)	(SQ FT)	EACH	EACH	(SQ FT)	(SQ FT)	(SQ FT)	(FOOT)	(FOOT)	(EACH)
WB-CM-142	1190+50	UNIVERSITY - OF ILLINOIS - AT CHICAGO - EXIT 28B	12.0	9.0	13.0	10.0			108.0					130.0			
WB-TS-142A1	1195+00	M3-4	2.5	1.3	2.5	1.3				1.0		3.1				18.0	
WB-TS-142A2	1195+00	M1-1-3 (I 290)	PER MUTCD STD (9FT ²)		PER MUTCD STD (9FT ²)					1.0		9.0					
WB-PM-142B	1193+49	R2-1 (55 MPH)	4.0	5.0	4.0	5.0		20.0					20.0				
WB-BM-143	1199+30	EXIT 28A - DAMEN AVE - 1 MILE	15.5	8.5	15.5	8.5			131.8					131.8			1.0
WB-BM-144	1199+30	EXIT 28B - ASHLAND AVE - PAULINA ST - 1/2 MILE	32.0	8.0	32.0	8.0		256.0						256.0			1.0
WB-BM-144A*	1199+30	MORGAN ST - 1000 W	7.0	2.5	7.0	2.5		17.5				17.5					
WB-WP-145	1202+35	EXIT - 29B	7.5	5.0	7.0	5.0				1.0				35.0	36.0		
WB-TS-145A	1203+10	W13-3 (30 MPH)	3.0	4.0	4.0	5.0				1.0			20.0			18.0	
WB-BM-146	1205+60	EXIT 28B - ASHLAND AVE - PAULINA ST - 3/4 MILE	32.0	8.0	32.0	7.5		256.0						240.0			1.0
WB-BM-147	1205+60	EXIT 29B - MORGAN ST - 1000 W	18.0	7.5	18.0	7.5		135.0						135.0			1.0
WB-TS-147A*	1205+60	PEORIA ST - 900 W	6.4	2.5	6.4	2.5				1.0		16.0				18.0	
WB-WP-148	1210+78	W4-3R	4.0	4.0	4.0	4.0				1.0		16.0			18.0		
WB-BM-148A	1212+07	HALSTED ST - 800 W	7.0	2.5	7.0	2.5		17.5				17.5					
WB-BM-149*	1212+90	EXIT TO - MORGAN ST - PROHIBITED	16.0	9.0	16.0	9.0			144.0					144.0			
WB-CM-150*	1213+10	DO NOT CROSS - SOLID WHITE LINE - STAY IN YOUR LANE	25.5	9.0	25.5	9.0			229.5					229.5			
WESTBOUND SUBTOTAL							13	323	3703	2	17	25	539	3914	252	180	16

*EXISTING SIGN DIMENSIONS NOT AVAILABLE; PROPOSED SIGN DIMENSIONS USED

MILE POST MARKER ASSEMBLY

DIRECTION	EACH
EASTBOUND	5
WESTBOUND	5
TOTAL	10

FILE NAME =	DESIGNED - SEW	REVISED -	 LIN ENGINEERING LTD. Consulting Engineers Orlaan, Illinois Westmont, Illinois	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES			F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*FILE#	DRAWN - SEW	REVISED -			290	(2525, ETC., 2727) RS-8	COOK	201	17			
USER NAME = #USER#	CHECKED - FML	REVISED -			CONTRACT NO. 60K11							
PLOT DATE = #DATE#	DATE - 1/25/10	REVISED -			SCALE: N.T.S.	SHEET NO. 3 OF 3 SHEETS	STA. TO STA.	FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT			