

SUMMARY OF QUANTITIES

100% STATE  
URBAN  
0044

ITEM NUMBER	DESCRIPTION	UNIT	QUANTITY	0004 DRAINAGE
20800150	TRENCH BACKFILL	CU YD	109	109
28100105	STONE RIP RAP, CLASS A3	SQ YD	35	35
28200200	FILTER FABRIC	SQ YD	10	10
42300500	DRIVEWAY PAVEMENT, 9 INCH <b>PORTLAND CEMENT CONCRETE</b>	SQ YD	15	15
42400200	SIDEWALK 5 INCH <b>PORTLAND CEMENT CONCRETE</b>	SQ FT	201	201
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	15	15
44000600	SIDEWALK REMOVAL	SQ FT	201	201
54213657	PRE CAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	1	1
<del>55000050</del>	STORM SEWERS, CLASS A, 12" TYPE 1	FOOT	10	10
X6022705	CATCH BASINS, TYPE A, 4'-DIAMETER, WITH SALVAGED FRAME AND GRATE	EACH	4	4
60206905	CATCH BASINS, TYPE C, TYPE 1 FRAME, OPEN LID	EACH	1	1
X6022210	MANHOLES, TYPE A, 4'-DIAMETER, WITH SALVAGED FRAME AND GRATE	EACH	1	1
X6023500	INLETS, TYPE A, WITH SALVAGED FRAME AND GRATE	EACH	3	3
60404300	FRAMES AND GRATES, TYPE 3	EACH	3	3
60406000	FRAMES AND LIDS, TYPE 1, OPEN LID	EACH	30	30
60500040	REMOVING MANHOLES	EACH	1	1
60500050	REMOVING CATCH BASINS	EACH	4	4
60500060	REMOVING INLETS	EACH	5	5
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6
67100100	MOBILIZATION	L SUM	1	1
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1
70102632	TRAFFIC CONTROL AND PROTECTION, STANDARD 701602	L SUM	1	1
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	30	30
X0325225	BRICK PAVEMENT REMOVAL AND REPLACEMENT	SQ FT	12	12
X5510100	STORM SEWER REMOVAL	FOOT	33	33
X5539700	STORM SEWERS TO BE CLEANED	FOOT	5185	5185
Z0004562	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	872	872
Z0018400	DRAINAGE STRUCTURES TO BE ADJUSTED	EACH	75	75
Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	33	33
Z0018600	DRAINAGE STRUCTURES TO BE RECONSTRUCTED	EACH	20	20
Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	1080	1080
Z0037310	PAVEMENT PATCHING (FULL DEPTH)	SQ YD	203	203

\* Specialty Item

Rev.

FILE NAME *	USER NAME * .USER.	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION		DRAINAGE REPAIRS SUMMARY OF QUANTITIES		F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
#FILE#		DRAWN - JJ	REVISED -					2010-065-T	COOK	14	3	
	PLOT SCALE = 4000.0000 1" = 4000'	CHECKED - RS	REVISED -	SCALE: 20		SHEET NO. 1 OF 1 SHEETS		STA.		TO STA.		CONTRACT NO. 60L46
	PLOT DATE = 12/14/2010	DATE - 12-10-2010	REVISED -					ILLINOIS FED. AID PROJECT				