

STR #	ADDRESS	CITY	CATCH BASIN TO BE ADJUSTED (Each)	CATCH BASIN TO BE RECONSTRUCTED (Each)	CATCH BASIN TO BE REMOVED (Each)	CATCH BASIN TO BE REPLACED (Each)	INLET TO BE REMOVED (Each)	INLET TO BE REPLACED (Each)	INLET TO BE ADJUSTED (Each)	MANHOLE TO BE REMOVED (Each)	MANHOLE TO BE REPLACED (Each)	MANHOLE TO BE ADJUSTED (Each)	TYPE I FRAME & OPEN LID (Each)	TYPE 3 FRAME & GRATE (Each)	TYPE I FRAME & CLOSED LID (Each)	CLEAN LATERAL (ft)	CURB & GTRR REPAIR/ RPLCMT (ft)	CLEAN STRUCTR (Each)	SIDEWALK REMV & RPLC (ft ²)	PVMNT PTCHNG (yd ²)	DRIVEWAY REMV & RPLC (YD ²)	TRENCH BACKFILL (yd ³)	ADDITIONAL COMMENTS
110	8400 W 159TH	ORLAND PARK	1	0	0	0	0	0	0	0	0	0	0	0	0	50	7	0	N/A	0.4	0	1	
111	7800 W 159TH	TINLEY PARK	1	0	0	0	0	0	0	0	0	0	0	0	0	50	12	0	0	0.4	0	0	
112	7509 W 159TH	TINLEY PARK	0	1	0	0	0	0	0	0	0	0	0	0	0	50	0	0	0	0.0	0	0	SEE NOTE 1
113	9301 W 123RD	PALOS PARK	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0.0	0	0	Repair Completed by Others
114	8901 W 123RD	PALOS PARK	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0.0	0	0	Repair Completed by Others
115	6411 W 127TH	PALOS HEIGHTS	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0.0	0	0	Repair Completed by Others
116	7101 W 95TH	OAK LAWN	0	1	0	0	0	0	0	0	0	0	0	0	0	50	8	1	0	1.3	0	2	
117	79TH AV AT 131ST	PALOS HEIGHTS	0	0	0	0	0	0	1	0	0	0	0	0	0	50	5	0	0	0.6	0	1	
118	135TH E/O RIDGELAND	COOK COUNTY	1	0	0	0	0	0	0	0	0	0	0	0	0	50	8	0	0	0.4	0	2	
119	5333 W 147TH	OAK FOREST	0	0	0	1	1	0	0	0	0	0	1	0	0	20	0	0	0	7.0	0	0	SEE NOTE 2
120	7213 RT83	PALOS HEIGHTS	0	0	1	1	0	0	0	0	0	0	0	0	0	50	12	0	0	2.7	0	3	Type A Catch Basin
121	71ST AV AT RT83	PALOS HEIGHTS	0	1	0	0	0	0	0	0	0	0	0	0	0	50	6	0	0	0.7	0	1	
122	IL 171 S/O MAIN	LEMONT	0	1	0	0	0	0	0	0	0	0	0	0	0	50	9	1	0	0.4	0	0	
123	11870 IL171	LEMONT	0	0	0	0	0	0	0	0	0	0	0	0	0	50	0	0	0	0.0	0	2	
124	13206 IL 171	LEMONT	0	0	0	0	0	0	0	0	0	0	0	0	0	40	0	0	0	0.0	0	2	
125	MAIN ST E/O WHEELER	LEMONT	0	1	0	0	0	0	0	0	0	0	0	0	0	55	0	0	0	0.0	0	3	SEE NOTE 3
126	17803 RT45	ORLAND PARK	1	0	0	0	0	0	0	0	0	0	1	0	0	50	14	1	0	1.3	0	2	
127	17701 RT 45	ORLAND PARK	1	0	0	0	0	0	0	0	0	0	1	0	0	50	0	0	0	2.7	0	2	
128	17301 RT 45	ORLAND PARK	1	0	0	0	0	0	0	0	0	0	0	0	0	50	34	1	0	6.7	0	4.4	
129	16858 RT 45	ORLAND PARK	1	0	0	0	0	0	0	0	0	0	0	0	0	50	19	1	0	3.3	0	2.2	
130	17801 RT 45	ORLAND PARK	1	0	0	0	0	0	0	0	0	0	0	0	0	50	23	1	0	2.6	0	2	
131	16603 RT 45	ORLAND PARK	1	0	0	0	0	0	0	0	0	0	1	0	0	50	14	1	0	0.4	0	2	
132	16157 RT 45	ORLAND PARK	1	0	0	0	0	0	0	0	0	0	0	0	0	50	11	1	0	1.0	0	1	
133	16057 RT 45	ORLAND PARK	1	0	0	0	0	0	0	0	0	0	1	0	0	50	12	1	0	0.7	0	1	
134	13061 RT 45	ORLAND PARK	1	0	0	0	0	0	0	0	0	0	0	0	0	50	11	1	0	0.7	0	1	
135	14100 RT 45	ORLAND PARK	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0.0	0	0	Repair Completed by Others
136	14150 RT 45	ORLAND PARK	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0.0	0	0	Repair Completed by Others
137	16640 RT 45	ORLAND PARK	0	1	0	0	0	0	0	0	0	0	0	0	0	50	8	0	0	0.7	0	0	
138	5323 W 159TH ST	OAK FOREST	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0.0	0	0	Repair Completed by Others
139	13641 SOUTHWEST HWY	ORLAND PARK	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0.0	0	0	Repair Completed by Others
			75	20	4	5	5	4	4	1	1	2	30	3	0	5185	872	33	201	203	15	108	

NOTE 1 5 CY Furnished Excavation is incidental to the reconstruction of this structure

NOTE 2 13 Feet Storm Sewer Removal, 10 Feet 12" RCP AND FES, Type C Catch Basin, 10 SY Rip Rap Class A3 and Filter Fabric

NOTE 3 20 Feet Storm Sewer Removal, 20 Feet 12" RCP , 25 SY Rip Rap Class A3