

SUMMARY OF QUANTITIES				CONSTRUCTION CODE
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	100% STATE
				0005
48300100	PORTLAND CEMENT CONCRETE SHOULDERS 6"	50 YD	52.8	52.8
50901760	PIPE HANDRAIL	FOOT	7	7
542A0217	PIPE CULVERTS, CLASS A, TYPE 1 12"	FOOT	40	40
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTION 12"	EACH	1	1
54213660	PRECAST REINFORCED CONCRETE FLARED END SECTION 15"	EACH	1	1
54214920	PRECAST REINFORCED CONC FLARED END SECTIONS - ARCH, EQUIVALENT ROUND-SIZE 15"	EACH	1	1
54215415	CAST-IN-PLACE REINFORCED CONCRETE FLARED END SECTIONS 15"	EACH	1	1
54247090	GRATING FOR CONCRETE FLARED END SECTION 12"	EACH	1	1
54247100	GRATING FOR CONCRETE FLARED END SECTION 15"	EACH	1	1
54248100	GRATING FOR CONCRETE FLARED END SECTION EQUIVALENT ROUND-SIZE 15"	EACH	1	1
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	16	16
550A0070	STORM SEWERS, CLASS A, TYPE 1 15"	FOOT	56	56
55100300	STORM SEWER REMOVAL 6"	FOOT	10	10
55100400	STORM SEWER REMOVAL 10"	FOOT	54	54
55100500	STORM SEWER REMOVAL 12"	FOOT	45	45

SUMMARY OF QUANTITIES				CONSTRUCTION CODE
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	100% STATE
				0005
55100700	STORM SEWER REMOVAL 15"	FOOT	24	24
60238800	INLET, TYPE A	EACH	1	1
60500060	REMOVING INLETS	EACH	3	3
60602800	CONCRETE GUTTER, TYPE B	FOOT	64	64
60801012	FLAP GATE 12"	EACH	2	2
*61139300	STORM SEWERS (SPECIAL), 6"	FOOT	53	53
*61140000	STORM SEWER (SPECIAL), 8"	FOOT	52	52
67100100	MOBILIZATION	L SUM	1	1
72000100	SIGN PANEL - TYPE 1	50 FT	6	6
72900100	METAL POST - TYPE A	FOOT	30	30
*78000100	PAINT PAVEMENT MARKING - LETTERS AND SYMBOLS	50 FT	59.8	59.8
*78000400	PAINT PAVEMENT MARKING - LINE 6"	FOOT	666	666
78300100	PAVEMENT MARKING REMOVAL	50 FT	300.8	300.8
*X0301430	PRECAST CONCRETE PARKING BLOCK	EACH	2	2
*X0325323	MANHOLES, TYPE A, SANITARY, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1

* SPECIALTY ITEM

FILE NAME : 0640315-4H1803-500.dgn	USER NAME : STEWAK	DESIGNED - R.H.D.	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES LINCOLN'S TOMB SITE RENOVATIONS		F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
Default	PLOT SCALE : 1:8000 1/2 in.	DRAWN - S.D.K.	REVISED -		SCALE:	SHEET 3 OF 16 SHEETS	STA.	TO STA.	PARK ROADS	SANGAMON	16	3
	PLOT DATE : 12/19/2013	CHECKED - R.H.D.	REVISED -		CONTRACT NO. 46315							
		DATE - 12/19/13	REVISED -		ILLINOIS FED. AID PROJECT							

JOB NO. 250-081-13 WASCONELL'S ENGINEERING CORP. DESIGN FIRM REGISTRATION NUMBER 184-002107