

& Associates, Inc.

PLOT DATE = 8/16/2013

GM


JJĪ

CHECKED -

REVISED

REVISED

- 1. The Sliding plate Assemblies shall be galvanized after fabrication according to Article 520.03 of the Standard Specifications.
- 2. Sliding Plate Assemblies shall be provided for the multi-use path above Preformed Joint Seal (SW end only). Cost of furnishing and installing Sliding Plate Assemblies shall be included in the cost for Preformed Joint Strip Seal. Contractor shall submit for approval detailed shop drawings showing the plate dimensions prior to fabrication.



<u>TYPICAL END TREATMENT</u> AT SIDEWALK OR MEDIAN

Shorter plates with a single row of studs at 12" cts. may be necessary on medians which are shallower than 9". See manufacturer's recommendation.

Notes:

The strip seal shall be made continuous and shall have a minimum thickness of ${}^{l}_{4}$ ". The configuration of the strip seal shall match the configuration of the Locking Edge Rails. Open or "webbed" strip seal gland configurations are not permitted. The gland shall be sized for a maximum rated movement of 4 inches.

The Locking Edge Rails depicted are conceptual only, except for the minimum dimensions shown. The actual configuration of the Locking Edge Rails and matching strip seal may vary from manufacturer to manufacturer. Flanged edge rails will not be allowed. Locking Edge Rails may be spliced at slope discontinuities.

The manufacturer's recommended installation methods shall be followed.

The joint opening and deck dimensions detailed on the superstructure are based on a rolled rail expansion joint. If the Contractor elects to use the welded rail expansion joint, the opening and deck dimensions shall be modified according to the dimensions detailed on this sheet. Required modifications shall be made at no additional cost to the State.

All steel components shall be galvanized after fabrication according to Article 520.03 of the Standard Specifications.

Maximum space between rail segments shall be 3 ₁₆ $^\prime$ $^\prime$, sealed with a suitable sealant. Joints in rails within 10 ft. of curbs shall be welded. Except between Stage I and Stage III Construction.

BILL OF MATERIAL

Item	Unit	Total
Preformed Joint Strip Seal	Foot	218

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

DECK EXPANSION JOINT STRUCTURE NO. 016-3035 SHEET NO. 30 OF 62 SHEETS F.A.P. SECTION COUNTY TOTAL SHEET'S NO.

307 541Y-3-B COOK 143 91

CONTRACT NO. 60J11