

CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QTY	90% FED. / 10% STATE										
				90% FED. 10% STATE	90% FED. 10% STATE	90% FED. 10% STATE	90% FED. 10% STATE	100% VILL. OF UNIV. PARK	90% FED. 10% STATE	CULVERT UNDER STUENKEL RD	CULVERT UNDER RAMP B/ I-57/RAMP D	CULVERT UNDER RAMP A		
				ROADWAY	SAFETY	LIGHTING	SIGNAL		BRIDGE					
				0003	0021	0021	0021		0011	0011	0011	0011		
				URBAN	URBAN	URBAN	URBAN		SN-099-0526	SN-099-6010	SN-099-0608	SN-099-0609		
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	2062	2062										
44004250	PAVED SHOULDER REMOVAL	SO YD	14,365	14,365										
44200535	CLASS A PATCHES, TYPE IV, 8 INCH	SO YD	508	508										
44201741	CLASS D PATCHES, TYPE II, 8 INCH	SO YD	84	84										
44213000	PATCHING REINFORCEMENT	SO YD	508	508										
44213200	SAW CUTS	FOOT	437	437										
44213204	TIE BARS 3/4"	EACH	74	74										
48101200	AGGREGATE SHOULDERS, TYPE B	TON	8359	8359										
48203045	HOT-MIX ASPHALT SHOULDERS, 12"	SO YD	20,287	20,287										
48300515	PORTLAND CEMENT CONCRETE SHOULDERS 10 3/4"	SO YD	15122	15122										
48300700	PORTLAND CEMENT CONCRETE SHOULDERS 12"	SO YD	3758	3758										
50100300	REMOVAL OF EXISTING STRUCTURES NO. 1	EACH	1								1			
50100400	REMOVAL OF EXISTING STRUCTURES NO. 2	EACH	1									1		
50105220	PIPE CULVERT REMOVAL	FOOT	1834	1834										
50200100	STRUCTURE EXCAVATION	CU YD	100								32	20	30	24

• SPECIALTY ITEM

Rev. 1-9-14

Rev.

TYLIN INTERNATIONAL	DESIGNED - JTP	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	STUENKEL ROAD AT I-57 RIDGELAND AVENUE TO CENTRAL AVENUE		F.A.J. RTE. ST	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	DRAWN - JTP	REVISED -		SUMMARY OF QUANTITIES			99-IHB-RI	WILL	679	8
	CHECKED - JPM	REVISED -		SCALE: N.T.S.	SHEET 5 OF 24 SHEETS	STA. TO STA.	ILLINOIS FED. AID PROJECT		CONTRACT NO. 60L69	
	DATE 05/10/2013	REVISED -								