

GUARDRAIL REMOVAL

ALIGNMENT	STATION		OFFSET	QUANTITY (FT)
	FROM	TO		
STUENKEL ROAD	16025+10.99	16028+33.70	13.1 RT	322.77
STUENKEL ROAD	16025+13.51	16028+33.70	14.1 LT	320.20
STUENKEL ROAD	16033+00.00	16034+89.63	14.6 RT	189.63
STUENKEL ROAD	16033+00.00	16034+93.94	15.5 LT	193.96
I-57	1455+13.70	1457+88.70	67 LT	275.00
I-57	1451+89.56	1454+89.20	66.3 RT	297.91
TOTAL:				2000

WOVEN WIRE FENCE REMOVAL

ALIGNMENT	FROM		TO		QUANTITY (FT)
	STATION	OFFSET	STATION	OFFSET	
STUENKEL	16021+81.00	29.6 RT	16022+11.00	29.6 RT	30.00
STUENKEL	16025+99.96	41.01 RT	16029+29.81	62.03 RT	330.70
STUENKEL	16027+20.01	45.08 LT	16029+50.12	61.89 LT	231.03
I-57	1453+83.56	113.50 LT	1454+85.91	111.60 LT	103.63
I-57	1455+17.67	111.16 LT	1456+14.39	113.30 LT	98.21
STUENKEL	16031+62.23	62.39 RT	16034+99.37	41.07 RT	338.05
STUENKEL	16031+82.54	59.44 LT	16034+99.40	39.91 LT	317.50
I-57	1453+23.23	115.18 RT	1455+20.20	111.83 RT	195.75
I-57	1455+52.80	111.61 RT	1464+74.93	114.81 RT	913.40
I-57	1468+33.30	115.25 RT	1472+41.52	114.94 RT	404.39
I-57	1428+67.93	113.84 RT	1430+55.57	114.29 RT	187.64
I-57	1477+02.45	110.13 LT	1480+61.31	110.94 LT	360.00
TOTAL:					3511

PAVED SHOULDER REMOVAL

LOCATION	STATION		OFFSET	QUANTITY (SQ FT)	QUANTITY (SQ YD)
	FROM	TO			
I-57 SB INSIDE SHLDR.	1413+92.31	1494+17.08	LT	32099	3567
I-57 NB INSIDE SHLDR.	1417+82.56	1500+35.15	RT	33010	3668
I-57 NB OUTSIDE SHLDR.	1434+20.00	1453+78.66	RT	22797	2533
I-57 NB OUTSIDE SHLDR.	1469+45.24	1475+54.97	RT	7060	784
I-57 SB OUTSIDE SHLDR.	1437+77.10	1472+40.09	LT	31882	3542
				*REF Δ	14095

SHOULDER RUMBLE STRIP REMOVAL

ALIGNMENT	STATION		LOCATION	QUANTITY (SQ YD)
	FROM	TO		
I-57 SB PreStage	1408+50.00	1499+50.00	OUTSIDE	4044.44
I-57 NB PreStage	1412+50.00	1505+75.00	OUTSIDE	4144.44
TOTAL:				8189

RAISED REFLECTIVE PAVEMENT MARKER, REFLECTOR REMOVAL

ALIGNMENT	FROM STA.	TO STA.	SPACING (FT)	TYPE	COLOR	QUANTITY (EACH)
I-57 SB LANE CENTER LINE	1416+63.46	1493+79.92	80	ONE-WAY	CRYSTAL	194
I-57 NB LANE CENTER LINE	1416+85.32	1493+79.91	80	ONE-WAY	CRYSTAL	194
TOTAL:						388