

TRAFFIC SIGNAL - BILL OF MATERIALS

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	WEST RAMP INTERSECTION	EAST RAMP INTERSECTION	INTER-CONNECT	EMERGENCY VEHICLE PREEMPTION
72000100	SIGN PANEL - TYPE 1	SQ FT	50	32.5	17.5	-	-
72000200	SIGN PANEL - TYPE 2	SQ FT	37.5	18.75	18.75	-	-
80500020	SERVICE INSTALLATION - POLE MOUNTED	EACH	2	1	1	-	-
81028200	UNDERGROUND CONDUIT, GALVANIZED STEEL, 2" DIA.	FOOT	2745	954	833	958	-
81028210	UNDERGROUND CONDUIT, GALVANIZED STEEL, 2 1/2" DIA.	FOOT	186	46	140	-	-
81028220	UNDERGROUND CONDUIT, GALVANIZED STEEL, 3" DIA.	FOOT	352	139	213	-	-
81028240	UNDERGROUND CONDUIT, GALVANIZED STEEL, 4" DIA.	FOOT	863	461	402	-	-
81200230	CONDUIT EMBEDDED IN STRUCTURE, 2" DIA., PVC	FOOT	50	-	-	50	-
81304600	JUNCTION BOX EMBEDDED IN STRUCTURE 18" X 12" X 6"	EACH	2	-	-	2	-
81400100	HANDHOLE	EACH	14	5	7	2	-
81400200	HEAVY-DUTY HANDHOLE	EACH	3	2	1	-	-
81400300	DOUBLE HANDHOLE	EACH	3	2	1	-	-
85700200	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET	EACH	1	1	-	-	-
85700300	FULL-ACTUATED CONTROLLER AND TYPE V CABINET	EACH	1	-	1	-	-
86000100	MASTER CONTROLLER	EACH	1	-	-	1	-
86400100	TRANSCIVER - FIBER OPTIC	EACH	2	1	1	-	-
87300925	ELECTRIC CABLE IN CONDUIT, TRACER, NO. 14 1C	FOOT	1878	-	-	1878	-
87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	977	713	264	-	-
87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	2394	740	278	-	1376
87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	5207	2522	2685	-	-
87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	320	320	-	-	-
87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	5127	3097	2030	-	-
87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2C	FOOT	185	118	67	-	-
87301900	ELECTRIC CABLE IN CONDUIT, EQUIPMENT GROUNDING CONDUCTOR, NO. 6 1C	FOOT	1792	842	950	-	-

I:\371\DCAN_C100_Sheets\DI60L69-sh1-15-07.dgn 26-DEC-2013 14:56



USER NAME * kprajapati	DESIGNED - MG	REVISED Δ - ADDENDUM 1 1/03/14
PLOT SCALE * 48.000000:1.000000	DRAWN - MG	REVISED -
PLOT DATE * 26-DEC-2013 14:56	CHECKED - KCP/YD	REVISED -
	DATE - 05/09/2013	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**SCHEDULE OF QUANTITIES
STUENKEL ROAD
FROM I-57 WEST RAMP TO I-57 EAST RAMP**

SCALE: AS NOTED SHEET NO. 7 OF 18 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57	99-1HB-R	WILL	679	312
CONTRACT NO. 60L69				
ILLINOIS FED. AID PROJECT				

ENTIRE SHEET REVISED