

## NOTES:

- 1. THE WIDTH OF THE FULL DEPTH PATCH OVER A TRENCH SHALL BE 12 (300) WIDER ON EACH SIDE OF THE TRENCH.
- 2. FOR METHOD OF MEASUREMENT AND BASIS OF PAYMENT, SEE RECURRING SPECIAL PROVISION "PATCHING WITH HOT-MIX ASPHALT OVERLAY REMOVAL".

## SEQUENCE OF CONSTRUCTION (PATCHING FIRST)

- 1. REMOVE THE EXISTING HMA MATERIAL OVER THE AREA TO BE PATCHED.
- 2. REMOVE AND REPLACE WITH CLASS C OR D PATCH.
- 3. REPLACE HMA MATERIAL OVER THE AREA TO BE PATCHED.

## SEQUENCE OF CONSTRUCTION (MILLING FIRST)

- 1. MILL HMA FIRST IF THERE IS AT LEAST 41/2 INCHES OR MORE OF HMA MATERIAL ON TOP OF THE EXISTING PAVEMENT OR IF THE PAVEMENT IS FULL DEPTH HMA. A MINIMUM OF 2 INCHES OF HMA MATERIAL SHALL BE IN PLACE AFTER MILLING.
- 2. REMOVE AND REPLACE WITH FULL DEPTH CLASS D PATCHES TO TOP OF MILLED SURFACE.

ALL DIMENSIONS ARE IN INCHES (MILLIMETERS) UNLESS OTHERWISE SHOWN.

Pittie, Parane.	INER HOME - baser dl	DESIGNED - R. SHAH	REVISED - A. ABBAS 04-27-98		**************************************	1.
and the comments to be about the field of the street of th	.Jgn	DRAWN	REVISED - R. BORO 01-01-07	STATE OF ILLINOIS	PAVEMENT PATCHING FOR	RTE. SECTION COUNTY SHEETS NO.
Paragraph 4+4	PLOT SCALE - SMARCH - / IM.	CHECKED -	REVISED R. BORO 09-04-07	DEPARTMENT OF TRANSPORTATION	HMA SURFACED PAVEMENT	679 393
	FEG1 Belts > 187-27 (1998	DATE 10-25-94	REVISED K. ENG 10-27-08	The state of the s	SCALE: NONE SHEET NO. 1 OF 1 SHEETS STA TO STA	BD400-04 (BD-22) CONTRACT NO.
					10 STAL	FED. ROAD DIST, NO. 1   HLINOIS FED. AID PROJECT