

URBAN

CONSTRUCTION CODES  
80% FED. / 20% STATE

SP	SI	CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODES		
						ROADWAY 0004	BRIDGE 0014	TRAINEES 0042
X		40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	111	111		
		40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	107	107		
X		40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	14	14		
X		40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	221	221		
		42001420	BRIDGE APPROACH PAVEMENT CONNECTOR (PCC)	SQ YD	157	157		
		42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	1950	1950		
		44000100	PAVEMENT REMOVAL	SQ YD	347	347		
		44000161	HOT-MIX ASPHALT SURFACE REMOVAL, 3"	SQ YD	1556	1556		
		44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	514	514		
		44000600	SIDEWALK REMOVAL	SQ FT	2075	2075		
		44003100	MEDIAN REMOVAL	SQ FT	2531	2531		
		44004250	PAVED SHOULDER REMOVAL	SQ YD	68	68		
		44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	418	418		
		48101500	AGGREGATE SHOULDERS, TYPE B 6"	SQ YD	102	102		

14

\* SPECIALTY ITEM  
X SPECIAL PROVISION ITEM

I:\1132 over DesPlaines River\1132-154-0101\Drawings\CONC Sheets\011132-154-000.dgn



USER NAME : KyleC	DESIGNED - HTC	REVISED -
PLOT SCALE :	DRAWN - HTC	REVISED -
PLOT DATE : 9/3/2013	CHECKED - DPA	REVISED -
	DATE - 09/03/13	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

IL 132 (GRAND AVE.) OVER DES PLAINES RIVER  
SUMMARY OF QUANTITIES

SCALE: N/A SHEET NO. 3 OF 9 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
541	X-6-B-1-1	LAKE	93	7
ILLINOIS FED. AID PROJECT			CONTRACT NO. 60N22	