

SUMMARY OF TRAFFIC SIGNAL QUANTITIES

CODE	PAY ITEM	UNIT	QUANTITY	IL 132 @ RIVERSIDE DR	IL 132 @ O'PLAINE RD	INTERCONNECT
81028200	UNDERGROUND CONDUIT, GALVANIZED STEEL, 2" DIA.	FOOT	335			335
81300830	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 18" X 18" X 8"	EACH	2			2
81400100	HANDHOLE	EACH	3	1		2
85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	2	1	1	
87300925	ELECTRIC CABLE IN CONDUIT, TRACER, NO. 14 1C	FOOT	3630			3630
87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	24	24		
88600100	DETECTOR LOOP, TYPE I	FOOT	66	66		2
89502380	REMOVE EXISTING HANDHOLE	EACH	3	1		1
X0325938	TEMPORARY WIRELESS INTERCONNECT, COMPLETE	L SUM	1			3630
X8710040	FIBER OPTIC CABLE IN CONDUIT, NO. 62.5/125, MM24F SM12F	FOOT	3630			
Z0073510	TEMPORARY TRAFFIC SIGNAL TIMING	EACH	2	1	1	
	CONDUIT ATTACHED TO STRUCTURE, 2" DIA. RIGID GALVANIZED STEEL, PVC COATED	FOOT	150			150

K:\IL\_132\_cover\_DesPlaines\_River\12-154-001\DRAWINGS\CADD\_Sheets\I132-ph-t-1500.dgn



USER NAME = JPS	DESIGNED - KC	REVISED -
	DRAWN - KC	REVISED -
PLOT SCALE =	CHECKED - MCH	REVISED -
PLOT DATE = 12/19/2013	DATE - 12/17/13	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

IL 132 (GRAND AVE.) OVER DES PLAINES RIVER  
SUMMARY OF TRAFFIC SIGNAL QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
541	X-6-B-1-1	LAKE	93	30
CONTRACT NO. 60N22			ILLINOIS FED. AID PROJECT	