

				80% FED. / 20% STATE		100% STATE		100% COUNTY		80% FED. / 20% STATE		100% STATE		100% PRIVATE	
CODED PAY ITEM NO.	ITEM	UNIT	URBAN TOTAL QUANTITY	0003	0021	0031	0042	0040	0021						
				ROADWAY	SAFETY		LANDSCAPING	TRAINEES	RETAINING WALL	TRAFFIC SIGNALS					
					STATE	LOCAL				INTERCONNECT	RAKOW				
550A0450	STORM SEWERS, CLASS A, TYPE 2 36"	FOOT	1318	1318											
550A4300	STORM SEWERS, CLASS A, TYPE 1 EQUIVALENT ROUND-SIZE 30"	FOOT	457	457											
550A5100	STORM SEWERS, CLASS A, TYPE 2 EQUIVALENT ROUND-SIZE 30"	FOOT	274	274											
550B0330	STORM SEWERS, CLASS B, TYPE 2 10"	FOOT	36	36											
55100900	STORM SEWER REMOVAL 18"	FOOT	310	310											
55101100	STORM SEWER REMOVAL 21"	FOOT	154	154											
55101200	STORM SEWER REMOVAL 24"	FOOT	77	77											
60107600	PIPE UNDERDRAINS 4"	FOOT	948	948											
60201340	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 24 FRAME AND GRATE	EACH	37	37											
60205040	CATCH BASINS, TYPE A, 5'-DIAMETER, TYPE 24 FRAME AND GRATE	EACH	1	1											
60208240	CATCH BASIN, TYPE C, TYPE 24 FRAME AND GRATE	EACH	32	32											
60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	13	13											
60219540	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 24 FRAME AND GRATE	EACH	1	1											
60221100	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	15	15											
60222240	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 24 FRAME AND GRATE	EACH	1	1											
60224446	MANHOLES, TYPE A, 7'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	2	2											
60240328	INLETS, TYPE B, TYPE 24 FRAME AND GRATE	EACH	7	7											
60500050	REMOVING CATCH BASINS	EACH	2	2											
60600605	CONCRETE CURB, TYPE B	FOOT	210	210											
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	12736	12736											
60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SQ FT	1251	1251											
60619600	CONCRETE MEDIAN, TYPE SB-6.12	SQ FT	10476	10476											
66700305	PERMANENT SURVEY MARKERS, TYPE II	EACH	1	1											
A 66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	7200	7200											
A 66900450	SPECIAL WASTE PLANS AND REPORTS	L SUM	1	1											
A 66900530	SOIL DISPOSAL ANALYSIS	EACH	5	5											
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	16	16											
67100100	MOBILIZATION	L SUM	1	1											

• REQUIRES SPECIAL PROVISION
△ INDICATES SPECIALTY ITEM

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET NO. 3 OF 6 SHEETS STA. TO STA.

REV. 2-18-14

FILE NAME: ...2278_S00.B3.dgn	USER NAME: ctb	DESIGNED: DTE	REVISION: -	CONTRACT NO. 60V72
PLOT SCALE: 1/8" = 1'-0"	CHECKED: GAB	REVISION: -		
PLOT DATE: 8/14/2013	DATE: 06/24/2013	REVISION: -		

F.A.U. RTE. 3687	SECTION 18W&RS-5 (12)	COUNTY MCHEMRY	TOTAL SHEETS 151	SHEET NO. 7
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				