

CODED PAY ITEM NO.	ITEM	UNIT	URBAN TOTAL QUANTITY	0003	0021		0031	0042	0040	0021	
				ROADWAY	SAFETY		LANDSCAPING	TRAINEES	RETAINING WALL	TRAFFIC SIGNALS	
					STATE	LOCAL				INTERCONNECT	RAKOW
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1							
<del>70100500</del>	<del>TRAFFIC CONTROL AND PROTECTION, STANDARD 701326</del>	<del>L SUM</del>	<del>1</del>	<del>1</del>							
<del>70102620</del>	<del>TRAFFIC CONTROL AND PROTECTION, STANDARD 701501</del>	<del>L SUM</del>	<del>1</del>	<del>1</del>							
<del>70102625</del>	<del>TRAFFIC CONTROL AND PROTECTION, STANDARD 701606</del>	<del>L SUM</del>	<del>1</del>	<del>1</del>							
<del>70102630</del>	<del>TRAFFIC CONTROL AND PROTECTION, STANDARD 701601</del>	<del>L SUM</del>	<del>1</del>	<del>1</del>							
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1							
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	20		20						
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	13714		13714						
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	10131		10131						
70400100	TEMPORARY CONCRETE BARRIER	FOOT	4604		4604						
70600250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2	2							
70600260	IMPACT ATTENUATORS, TEMPORARY (SEVERE USE, NARROW), TEST LEVEL 3 <i>FULLY REDIRECTIVE</i>	EACH	1	1							
72000100	SIGN PANEL - TYPE I	SQ FT	125		125						
72400100	REMOVE SIGN PANEL ASSEMBLY - TYPE A	EACH	15		15						
72400500	RELOCATE SIGN PANEL ASSEMBLY - TYPE A	EACH	4			4					
72400600	RELOCATE SIGN PANEL ASSEMBLY - TYPE B	EACH	1			1					
72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	418		418						
78008200	POLYUREA PAVEMENT MARKING TYPE I - LETTERS AND SYMBOLS	SO FT	633		633						
78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	2507		2507						
78008230	POLYUREA PAVEMENT MARKING TYPE I - LINE 6"	FOOT	4550		4550						
78008250	POLYUREA PAVEMENT MARKING TYPE I - LINE 12"	FOOT	729		729						
78008270	POLYUREA PAVEMENT MARKING TYPE I - LINE 24"	FOOT	39		39						
78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	305		305						
78300100	PAVEMENT MARKING REMOVAL	SO FT	5413		5413						
81028200	UNDERGROUND CONDUIT, GALVANIZED STEEL, 2" DIA.	FOOT	3434							3324	110
81400100	HANDHOLE	EACH	8							8	
81400200	HEAVY-DUTY HANDHOLE	EACH	1								1
85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	2							1	1

\* REQUIRES SPECIAL PROVISION  
 Δ INDICATES SPECIALTY ITEM

Δ  
 Δ  
 Δ  
 Δ  
 Δ

Rev.