

FILE PATH = p:\388035\pmt\escomon\line\local\p\MECD\00\Documents\01\_Americas\Transportation\60269938\_Circle\Phase\_1\1000\_CAD\005\_Roadway\_Sheets\60W29\_Sheets\60W29\_sht-Eros-Schedule-01.dgn

**TEMPORARY EROSION CONTROL SCHEDULE**

STAGES	MULCH, METHOD 2 ACRE	MULCH, METHOD 4 ACRE	TEMPORARY EROSION CONTROL SEEDING POUND	PERIMETER EROSION BARRIER FOOT	INLET FILTERS EACH	TEMPORARY CHAIN LINK FENCE FOOT	TEMPORARY FENCE FOOT	STABILIZED CONSTRUCTION ENTRANCE SQ YD
STAGE 1A	0.95	-	95	966	29	811	226	568
STAGE 1B	0.90	-	90	-	5	-	-	430
STAGE 2	-	0.75	-	631	3	263	-	-
STAGE 3	0.56	-	56	565	-	-	-	-
<b>TOTAL</b>	<b>2.50</b>	<b>0.75</b>	<b>241</b>	<b>2,163</b>	<b>37</b>	<b>1,075</b>	<b>226</b>	<b>998</b>

**PERMANENT EROSION CONTROL SCHEDULE**

	POTASSIUM FERTILIZER NUTRIENT POUND	NITROGEN FERTILIZER NUTRIENT POUND	SEEDING, CLASS 2A ACRE	EROSION CONTROL BLANKET SQ YD	SODDING, SALT TOLERANT SQ YD	SUPPLEMENTAL WATERING UNIT	TOPSOIL FURNISH AND PLACE, 4" SQ YD	MOWING ACRE	MULCH CU YD	WEED CONTROL, PRE-EMERGENT GRANULAR HERBICIDE LB
PERMANENT CONDITION	81	81	0.25	611	4,610	207.6	5,221	0.25	14	1
<b>TOTAL</b>	<b>81</b>	<b>81</b>	<b>0.25</b>	<b>611</b>	<b>4,610</b>	<b>207.6</b>	<b>5,221</b>	<b>0.25</b>	<b>14</b>	<b>1</b>

**INLET FILTER SCHEDULE**

INLET FILTERS				
STAGE 1A				
	LOCATION		ALIGNMENT	AMOUNT (EACH)
	STATION	OFFSET		
STAGE 1A	3700+03.00	0.38' LT	PEORIA	1
STAGE 1A	3700+03.14	118.60' LT	PEORIA	1
STAGE 1A	3700+03.25	72.63' RT	PEORIA	1
STAGE 1A	3702+48.03	56.19' RT	PEORIA	1
STAGE 1A	3702+48.25	63.30' LT	PEORIA	1
STAGE 1A	3705+24.81	42.12' RT	PEORIA	1
STAGE 1A	3705+74.79	17.47' LT	PEORIA	1
STAGE 1A	3705+76.67	16.74' RT	PEORIA	1
STAGE 1A	3707+53.09	17.90' LT	PEORIA	1
STAGE 1A	3707+65.47	22.24' RT	PEORIA	1
STAGE 1A	3707+67.19	21.34' LT	PEORIA	1
STAGE 1A	3707+69.86	34.63' LT	PEORIA	1
STAGE 1A	343+73.66	42.44' RT	EB I-290	1
STAGE 1A	343+73.98	44.59' RT	EB I-290	1
STAGE 1A	345+25.53	37.26' RT	EB I-290	1
STAGE 1A	345+36.93	42.87' RT	EB I-290	1
STAGE 1A	345+39.79	25.23' LT	EB I-290	1
STAGE 1A	345+42.00	44.60' RT	EB I-290	1
STAGE 1A	346+62.28	25.27' LT	EB I-290	1
STAGE 1A	347+23.31	47.95' RT	EB I-290	1
STAGE 1A	347+83.48	26.10' LT	EB I-290	1
STAGE 1A	349+22.85	74.89' RT	EB I-290	1
STAGE 1A	345+27.44	27.59' RT	WB I-290	1
STAGE 1A	345+37.77	35.38' LT	WB I-290	1
STAGE 1A	345+37.78	36.13' LT	WB I-290	1
STAGE 1A	346+60.57	26.94' RT	WB I-290	1
STAGE 1A	347+93.22	26.18' RT	WB I-290	1
STAGE 1A	347+93.59	36.66' LT	WB I-290	1
STAGE 1A	349+20.23	41.75' LT	WB I-290	1
<b>TOTAL</b>				<b>29</b>

INLET FILTERS				
STAGE 1B				
	LOCATION		ALIGNMENT	AMOUNT (EACH)
	STATION	OFFSET		
STAGE 1B	3706+12.90	12.11' LT	PEORIA	1
STAGE 1B	3706+32.90	12.00' LT	PEORIA	1
STAGE 1B	3706+45.86	1.99' RT	PEORIA	1
STAGE 1B	3706+49.03	21.40' RT	PEORIA	1
STAGE 1B	3706+85.99	17.50' RT	PEORIA	1
<b>TOTAL</b>				<b>5</b>

INLET FILTERS				
STAGE 2				
	LOCATION		ALIGNMENT	AMOUNT (EACH)
	STATION	OFFSET		
STAGE 2	3700+96.17	108.43' LT	PEORIA	1
STAGE 2	3701+21.39	108.48' LT	PEORIA	1
STAGE 2	3701+45.19	108.54' LT	PEORIA	1
<b>TOTAL</b>				<b>3</b>



DI60W29-sht-Eros-Schedule-01.dgn  
 USER NAME = BAW1tor t  
 PLOT SCALE = 20.0000' / in.  
 PLOT DATE = 12/19/2013

DESIGNED - JLV  
 DRAWN - JSL  
 CHECKED - JMG  
 DATE - 10/30/2013

REVISED - 12/18/2013  
 REVISED -  
 REVISED -  
 REVISED -

**STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION**

**EROSION AND SEDIMENTATION CONTROL PLAN  
 SCHEDULES**

SCALE: NONE SHEET 1 OF 1 SHEETS STA. TO STA.

F.A.I. RTE. 90/94/290	SECTION 2013-011R	COUNTY COOK	TOTAL SHEETS 356	SHEET NO. 61
CONTRACT NO. 60W29			ILLINOIS FED. AID PROJECT	