

DOOR SCHEDULE																		
DOOR NO.	LABEL	LOCATION				DOOR						FRAME		DETAILS			HDWR	COMMENTS
		FROM	RM NO.	TO	RM NO.	LEAF	WIDTH	HEIGHT	THICK.	MATL	ELEV.	MATL	ELEV	HEAD	JAMB	SILL	SET#	
001A	NONE	UNPAID	001	EXT	BRIDGE	PAIR	5'-6"	7'-2"	1 3/4"	ST. STL.	A-202	ST. STL.	A-202	9 SIM	9/A-601	7/A-400	#5*	LAM GL, *AUTO OPEN -1 LEAF
001B	NONE	UNPAID	001	EXT	BRIDGE	PAIR	5'-6"	7'-2"	1 3/4"	ST. STL.	A-202	ST. STL.	A-202	9 SIM	9/A-601	7/A-400	#5	LAM GL
001C	NONE	UNPAID	001	EXT	BRIDGE	PAIR	5'-6"	7'-2"	1 3/4"	ST. STL.	A-202	ST. STL.	A-202	9 SIM	9/A-601	7/A-400	#5	LAM GL
002	NONE	UNPAID	001	PAID	002	GATE				ST. STL.		ST. STL.					#10	GATE BY CTA
003	NONE	KIOSK	003	UNPAID	001	SINGLE	3'-0"	7'-0"	1 3/4"	ST. STL.	A-401	ST. STL.	A-401	63/A-611	61-2/A-611	59/A-611	#2	VISION PANEL
004	NONE	JANITOR	004	PAID	002	SINGLE	3'-0"	7'-0"	1 3/4"	ST. STL.	A-401	ST. STL.	A-401	20 SIM	20/A-602	6/A-400	#1	LOUVER
005	NONE	RESTROOM	005	PAID	002	SINGLE	3'-0"	7'-0"	1 3/4"	ST. STL.	A-401	ST. STL.	A-401	20 SIM	20/A-602	6/A-400	#1	LOUVER
006	2HR	COMM	006	PAID	002	SINGLE	3'-0"	7'-0"	1 3/4"	ST. STL.	A-401	ST. STL.	A-401	20 SIM	20/A-602	6/A-400	#2	
007	2HR	ELEC	007	PAID	002	SINGLE	3'-0"	7'-0"	1 3/4"	ST. STL.	A-401	ST. STL.	A-401	20 SIM	20/A-602	6/A-400	#3	
007A	2HR	UPS	007A	ELECT	007	PAIR	6'-0"	7'-0"	1 3/4"	ST. STL.	A-401	ST. STL.	A-401	18 SIM	18/A-602		#7	LOUVER EACH LEAF
008A	NONE	PAID	002	ELEV CAB	008	BI-PASS		7'-0"		ST. STL.	A-503	ST. STL.			55/A-610	56/A-610		BI-PASSING ELEV DRS
008B	NONE	PLATFORM	002	ELEV CAB	008	BI-PASS		7'-0"		ST. STL.	A-503	ST. STL.			55/A-610	56/A-610		BI-PASSING ELEV DRS
009	2HR	PAID	002	MCHN RM	011	SINGLE	3'-0"	7'-0"	1 3/4"	ST. STL.	A-401	ST. STL.	A-401	51 SIM	51/A-608	6/A-400	#3	
010	2HR	SHEAVRM	012	CATWALK	011UP	SINGLE	3'-0"	7'-0"	1 3/4"	ST. STL.	A-401	ST. STL.	A-401	18 SIM	18/A-602		#3	

LOUVER SCHEDULE													
MARK NO.	LEVEL	LOCATION			SIZE				FRAME	DETAILS			COMMENTS
		ELEV	ROOM	RM NO.	WIDTH	HEIGHT	QUAN	MATL	MATL	HEAD	JAMB	SILL	
L1	STATION	EAST	UNPAID	001	VAR	VAR	7	ST STL	ST STL	50	9A/RA	23	WITHIN EXISTING HSS ARCHED OPENING
L2	STATION	WEST	PAID	002	VAR	VAR	5	ST STL	ST STL	36	12A	21/22	WITHIN EXISTING HSS ARCHED OPENING
L3	STATION	NORTH	PAID	002	4'	2' 7.7"	12	ST STL	ST STL	57	9A	22	WITHIN NEW HSS OPENING
L4	STATION	NORTH	KIOSK	003	12"	12"	1	ST STL	ST STL	35 A SIM	35 A SIM	35 A	WITHIN POLYCARB WALL PANEL
L5	STATION	NORTH	JAN	004	12"	12"	1	ST STL	ST STL	35 A SIM	35 A SIM	35 A	WITHIN POLYCARB WALL PANEL
L6	STATION	NORTH	RESTROOM	005	12"	12"	1	ST STL	ST STL	15 A SIM	15 A SIM	15 A	WITHIN ST STL WALL PANEL
L7	STATION	NORTH	UPS	007A	12"	12"	1	ST STL	ST STL	15 A SIM	15 A SIM	15 A	WITHIN ST STL WALL PANEL
L8	STATION	NORTH	ELECT	007	4'	2' 6"	1	ST STL	ST STL	15 A SIM	15 A SIM	15 A	WITHIN ST STL WALL PANEL
L7	STATION	WEST	ELEV MR	011	12"	12"	1	ST STL	ST STL	53 A SIM	53 A SIM	53 A	WITHIN ST STL WALL PANEL

WINDOW SCHEDULE														
MARK NO.	LEVEL	LOCATION			SIZE				FRAME	DETAILS			VANDAL RESISTANT FILM LOCATION	COMMENTS
		ELEV	ROOM	RM NO.	WIDTH	HEIGHT	QUAN	MATL	MATL	HEAD	JAMB	SILL		
W1	STATION	SOUTH	PAID	002	4'	6' 7"	6	1/2" LAM	ALUM	50	1/31	2	INTERIOR	WITHIN EXISTING HSS OPENING
W1	STATION	SOUTH	UNPAID	001	4'	6' 7"	2	1/2" LAM	ALUM	24	5/31	2	INTERIOR	WITHIN EXISTING HSS OPENING
W1	STATION	NORTH	UNPAID	001	4'	6' 7"	2	1/2" LAM	ALUM	37	6/31	2	INTERIOR	WITHIN EXISTING HSS OPENING
W2	STATION	EAST	UNPAID	001	4' 8"	6' 7"	6	1/2" LAM	ALUM	22A	3/5/6	4A	INTERIOR/EXTERIOR	WITHIN NEW HSS OPENING
W3	STATION	EAST	UNPAID	001	3'	6' 7"	2	1/2" LAM	ALUM	22A	3/9	4A	INTERIOR/EXTERIOR	WITHIN NEW HSS OPENING
W4	STATION	EAST	UNPAID	001	5'	6' 7"	2	1/2" LAM	ALUM	22A	9	4A	INTERIOR/EXTERIOR	WITHIN NEW HSS OPENING
W5	STATION	NORTH	PAID	002	4.5'+	8'+	12	1/2" LAM	ALUM	22	1	2	INTERIOR	WITHIN NEW HSS OPENING
W6	STATION	WEST	PAID	001	4'	6' 7"	1	1/2" LAM	ALUM	22	10/13	4	INTERIOR	WITHIN NEW HSS OPENING
W7	STATION	SOUTH	PAID	002	3'	6' 7"	12	1/2" LAM	ALUM	37	1	2	INTERIOR	WITHIN EXISTING HSS OPENING
W8	PLATFORM	SOUTH	CENTRAL	010	VAR	VAR	13	1/2" LAM	ALUM	46	3	3	INTERIOR/EXTERIOR	WITHIN EXISTING HSS OPENING
W9	PLATFORM	NORTH	CENTRAL	010	VAR	VAR	13	1/2" LAM	ALUM	46	3	3/73	INTERIOR/EXTERIOR	WITHIN EXISTING HSS OPENING
W10	PLATFORM	SOUTH	W STAIR	009	VAR	VAR	13	1/2" LAM	ALUM	46/48	3	3	INTERIOR/EXTERIOR	WITHIN EXIST HSS OPENING
W11	PLATFORM	NORTH	W STAIR	009	VAR	VAR	13	1/2" LAM	ALUM	46/48	3	3/73	INTERIOR/EXTERIOR	WITHIN EXIST HSS OPENING

4/3/14 4:04 PM 0161708-60W29-A-612.dgn



USER NAME = whbruce	DESIGNED - WHB	REVISED - 1/20/2014
	CHECKED - CRR	REVISED -
PLOT SCALE = 8:0.0009 '1" / in.	DRAWN - WHB	REVISED -
PLOT DATE = 1/20/2014	CHECKED - CRR	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**PEORIA STREET STATION  
WINDOWS, DOORS, LOUVER SCHEDULE**

MUN	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2090	2013-011R	COOK	356	253B
CONTRACT NO. 60W29				
ILLINOIS FED. AID PROJECT FED. AID PROJECT				

SHEET NO. A-612 OF 117 SHEETS

