

PROFILE  
 GRADES CHECKED  
 PLANNING CHECKED  
 STRUCTURE NOTATIONS CHECKED  
 DATE  
 BY  
 NOTE BOOK NO.

**CHRISTOPHER B. BURKE**  
 ENGINEERING LTD.  
 5075 West Higgins Road, Suite 600  
 Rosemont, IL 60018  
 (847) 826-6800

IL ROUTE 50 AT SOUTHWEST HIGHWAY INTERCONNECT  
CONSTRUCTION CODE

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	URBAN			
				0005	0021	0021	0021
				HSIP FUNDS	HSIP FUNDS	LOCAL FUNDS	HSIP FUNDS
				90% FED	90% FED	100% LOCAL	90% FED
				10% STATE			
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	3583		3583		
42400800	DETECTABLE WARNINGS	SQ FT	115		115		
44000100	PAVEMENT REMOVAL	SQ YD	466	466			
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	520		520		
44000600	SIDEWALK REMOVAL	SQ FT	2559		2559		
60261300	INLETS TO BE ADJUSTED WITH NEW TYPE 11 FRAME AND GRATE	EACH	1	1			
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	546		546		
* 66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	50	50			
67100100	MOBILIZATION	L SUM	1		1		
* 66900450	SPECIAL WASTE PLANS AND REPORTS	L SUM	1	1			
70102632	TRAFFIC CONTROL AND PROTECTION, STANDARD 701602	L SUM	1		1		
* 66900530	SOIL DISPOSAL ANALYSIS	EACH	4	4			
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1		1		
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1		1		
* 72000100	SIGN PANEL - TYPE 1	SQ FT	48		48		
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	110		110		
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	1610		1610		
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	827		827		

\* SPECIALITY ITEM

Rev. 2-19-14