

DATE	BY	REVISION

PLAN	NO.

PROFILE	DATE	BY	REVISION

CHRISTOPHER B. BURKE ENGINEERING LTD.
 9575 West Higgins Road, Suite 600
 Rosemont, Illinois 60018
 (847) 952-0000

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	IL ROUTE 50 AT SOUTHWEST HIGHWAY			INTERCONNECT
				CONSTRUCTION CODE			0021
				0005	0021	0021	0021
				HSIP FUNDS	HSIP FUNDS	LOCAL FUNDS	HSIP FUNDS
				90% FED	90% FED		90% FED
				10% STATE	10% STATE	100% LOCAL	10% STATE
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	45		45		
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	225		225		
* 78300100	PAVEMENT MARKING REMOVAL	50 FT	1375		1375		
80500020	SERVICE INSTALLATION - POLE MOUNTED	EACH	1		1		
81028200	UNDERGROUND CONDUIT, GALVANIZED STEEL, 2" DIA.	FOOT	1787		1579		208
81028210	UNDERGROUND CONDUIT, GALVANIZED STEEL, 2 1/2" DIA.	FOOT	78		78		
81028220	UNDERGROUND CONDUIT, GALVANIZED STEEL, 3" DIA.	FOOT	88		88		
81028240	UNDERGROUND CONDUIT, GALVANIZED STEEL, 4" DIA.	FOOT	569		569		
81028730	UNDERGROUND CONDUIT, COILABLE NONMETALLIC CONDUIT, 1 1/4" DIA.	FOOT	100		100		
81400100	HANDHOLE	EACH	6		6		
81400200	HEAVY-DUTY HANDHOLE	EACH	5		5		
81400300	DOUBLE HANDHOLE	EACH	3		3		
81702110	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 10	FOOT	2680		2680		
81702130	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 6	FOOT	880		880		

* SPECIALITY ITEM

Rev.

FILE NAME : \\s1000\130116\work_order_10016 - IL5054	USER NAME : ejensen	DESIGNED : LJ	REVISED : _____	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES SHEET 3 OF 7	F.A.R. RTE. : 350	SECTION : 461TS-2113	COUNTY : COOK	TOTAL SHEETS : 42	SHEET NO. : 5		
PLOT SCALE : # 2'	PLOT DATE : # 12/11/2013	DRAWN : FFB / FCP	REVISED : _____			SCALE : _____	SHEET NO. : _____ OF _____ SHEETS	STA. : _____ TO STA. : _____	CONTRACT NO. 60X25			
CHECKED : CMZ	DATE : _____	REVISED : _____	REVISED : _____			FED. ROAD DIST. NO. : ILLINOIS FED. AID PROJECT						